

Structural Calculations


Project #240268

Ogden Community Services Bldg Remodel

1875 Monroe Blvd, Ogden UT 84401

Prepared For:

GSBS
375 West 200 South
Salt Lake City, UT 84101



Structural Calculations
Project #240268

Ogden Community Services Bldg Remodel

INDEX

General Design Criteria..... G-1
Roof Joist Analysis for Loading on Openings..... R-1
Opening Analysis of Headers and Jambs O-1



DUNN ASSOCIATES, INC
Consulting Structural Engineers
Enabling Great Design™



DUNN ASSOCIATES, INC
Consulting Structural Engineers

Title
OGDEN COMMUNITY SERVICES BUILDING

Sheet Number:	G-1
Job Number:	240268
Date:	03/11/2025
By:	CF

GENERAL DESIGN CRITERIA



ASCE Hazards Report

Address:

1875 Monroe Blvd
Ogden, Utah
84401

Standard:

ASCE/SEI 7-16

Risk Category: II

Soil Class:

D - Default (see
Section 11.4.3)



Latitude:

41.2337

Longitude: -111.959294

Elevation:

4388.367800831308 ft
(NAVD 88)



Wind

Results:

Wind Speed	103 Vmph
10-year MRI	74 Vmph
25-year MRI	80 Vmph
50-year MRI	84 Vmph
100-year MRI	89 Vmph

Data Source:

ASCE/SEI 7-16, Fig. 26.5-1B and Figs. CC.2-1–CC.2-4, and Section 26.5.2

Date Accessed:

Fri Feb 14 2025

Value provided is 3-second gust wind speeds at 33 ft above ground for Exposure C Category, based on linear interpolation between contours. Wind speeds are interpolated in accordance with the 7-16 Standard. Wind speeds correspond to approximately a 7% probability of exceedance in 50 years (annual exceedance probability = 0.00143, MRI = 700 years).

Site is not in a hurricane-prone region as defined in ASCE/SEI 7-16 Section 26.2.

Site Soil Class: D - Default (see Section 11.4.3)

Results:

S_s :	1.366	S_{D1} :	N/A
S_1 :	0.502	T_L :	8
F_a :	1.2	PGA :	0.62
F_v :	N/A	PGA _M :	0.744
S_{MS} :	1.64	F_{PGA} :	1.2
S_{M1} :	N/A	I_e :	1
S_{DS} :	1.093	C_v :	1.373

$S_{d1} = 0.602g$

Ground motion hazard analysis may be required. See ASCE/SEI 7-16 Section 11.4.8.

Data Accessed: Fri Feb 14 2025

Date Source: [USGS Seismic Design Maps](#)

DESIGN CRITERIA
INTERMEDIATE MASONRY SHEAR WALLS

$R = 3.5$
 $\Omega = 2.5$
 $C_d = 2.25$

$S_{d1} = 0.602g$

Results:

Mapped Elevation: 4388.4 ft
 Data Source: ASCE/SEI 7-16, Table 7.2-8
 Date Accessed: Fri Feb 14 2025

In "Case Study" areas, site-specific case studies are required to establish ground snow loads. Extreme local variations in ground snow loads in these areas preclude mapping at this scale.

Ground snow load determination for such sites shall be based on an extreme value statistical analysis of data available in the vicinity of the site using a value with a 2 percent annual probability of being exceeded (50-year mean recurrence interval).

Values provided are ground snow loads. In areas designated "case study required," extreme local variations in ground snow loads preclude mapping at this scale. Site-specific case studies are required to establish ground snow loads at elevations not covered.

Snow load values are mapped to a 0.5 mile resolution. This resolution can create a mismatch between the mapped elevation and the site-specific elevation in topographically complex areas. Engineers should consult the local authority having jurisdiction in locations where the reported 'elevation' and 'mapped elevation' differ significantly from each other.

The ASCE Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE Hazard Tool.

Utah Ground Snow Load Map



Latitude: 41.234



Longitude: -111.960

Elevation: 4,349 ft

Ground Snow Load:

38 psf / 1.82 kPa

**This document is not legally binding. The user is urged to verify ground snow load values with the local authority having jurisdiction.*



These ground snow load values represent 50-year ground snow load estimated value at a 2% probability of exceedance for the location given. The grid used in the map is 3350ft by 3350ft. Elevations for these grid cells were estimated by aggregating data from 100ft by 100ft USGS digital elevation models and may not coincide with the actual site elevation. These predictions are calculated using the process outlined in The Utah Snow Load Study.¹

Final predictions given are bounded at a lower limit for a minimum ground snow load of 21 psf to meet ASCE 7. Estimated values for snow loads at elevations significantly higher than all nearby stations lead to unreasonably high snow load estimates, therefore, the predictions in the map are not allowed to extend beyond the highest 50-year station ground snow load of 429 psf. Elevations over 9,000 ft are also considered less accurate due to the limited number of stations at these elevations. The results shown in this report have included a warning if the results have reached or exceeded the upper limit.

While great efforts have been made to ensure these predictions are as accurate as possible, designers must use expert judgement to ensure that such predictions are appropriate for their particular project. The SEAU and the authors cannot accept responsibility for prediction errors or any consequences resulting therefrom.

¹ Bean, Brennan; Maguire, Marc; and Sun, Yan, "The Utah Snow Load Study" (2018). Civil and Environmental Engineering Faculty Publications. Paper 3589.

Utah State University sites use cookies. By continuing to use this site you accept our privacy and cookie policy.

I agree



DUNN ASSOCIATES, INC
Consulting Structural Engineers

Title
OGDEN COMMUNITY SERVICES BUILDING

Sheet Number:	R-1
Job Number:	240268
Date:	03/11/2025
By:	CF

ROOF JOIST ANALYSIS FOR LOADING ON OPENINGS




DUNN ASSOCIATES, INC
Consulting Structural Engineers

Title
OGDEN COMMUNITY SERVICES BUILDING

Sheet Number:	R-2
Job Number:	240268
Date:	
By:	CF

JOIST ANALYSIS FOR DETERMINATION OF LOADS ON NEW OPENING HEADERS/BEAMS



JOIST 1
For Backspan
DL = 20 psf
LLr = 20 psf
SL = 27 psf

For Cantilever
DL = 20 psf
LLr = 20 psf
SL = 32 psf

**REACTIONS
BACK SPAN**
DL = 0.18 klf
LLr = 0.16 klf
SL = 0.21 klf

CANTILEVER
DL = 0.32 klf
LLr = 0.27 klf
SL = 0.40 klf

JOIST 2
For Backspan
DL = 20 psf
LLr = 20 psf
SL = 27 psf

REACTIONS
DL = 0.14 klf
LLr = 0.12 klf
SL = 0.16 klf

JOIST 3
For Backspan
DL = 20 psf
LLr = 20 psf
SL = 27 psf

For Cantilever
DL = 20 psf
LLr = 20 psf
SL = 32 psf

**REACTIONS
BACK SPAN**
DL = 0.13 klf
LLr = 0.11 klf
SL = 0.15 klf

CANTILEVER
DL = 0.27 klf
LLr = 0.24 klf
SL = 0.34 klf

**REACTIONS
WITH DRIFT
BACK SPAN**
DL = 0.13 klf
LLr = 0.11 klf
SL = 0.24 klf

CANTILEVER
DL = 0.27 klf
LLr = 0.24 klf
SL = 0.36 klf

JOIST 4
For Backspan
DL = 20 psf
LLr = 20 psf
SL = 27 psf

For Cantilever
DL = 20 psf
LLr = 20 psf
SL = 32 psf

**REACTIONS
BACK SPAN**
DL = 0.19 klf
LLr = 0.16 klf
SL = 0.22 klf

CANTILEVER
DL = 0.32 klf
LLr = 0.28 klf
SL = 0.40 klf

Wood Beam

Project File: Ogden Community Services Building.ec6

LIC# : KW-06015170, Build:20.24.12.17

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Joist 1

CODE REFERENCES

Calculations per NDS 2018, IBC 2021, SDPWS 2021

Load Combination Set : IBC 2021

Material Properties

Analysis Method : Allowable Stress Design

Load Combination : IBC 2021

Wood Species : Douglas Fir-Larch

Wood Grade : No.2

Beam Bracing : Beam is Fully Braced against lateral-torsional buckling


Fb + 900.0 psi
 Fb - 900.0 psi
 Fc - Prll 1,350.0 psi
 Fc - Perp 625.0 psi
 Fv 180.0 psi
 Ft 575.0 psi

E : Modulus of Elasticity

Ebend- xx 1,600.0 ksi

Eminbend - xx 580.0 ksi

Density 31.210 pcf



Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Beam self weight calculated and added to loading

Loads on all spans...

Uniform Load on ALL spans : D = 0.020, Lr = 0.020 k/ft

Load for Span Number 1

Uniform Load : S = 0.0270, Tributary Width = 1.0 ft

Load for Span Number 2

Uniform Load : S = 0.0320, Tributary Width = 1.0 ft

DESIGN SUMMARY

Design OK

Maximum Bending Stress Ratio	=	0.753 1	Maximum Shear Stress Ratio	=	0.220 : 1
Section used for this span		2x10	Section used for this span		2x10
fb: Actual	=	857.84psi	fv: Actual	=	45.52 psi
F'b	=	1,138.50psi	F'v	=	207.00 psi
Load Combination			Load Combination		
		+D+S			+D+S
Location of maximum on span	=	7.788ft	Location of maximum on span	=	16.240 ft
Span # where maximum occurs	=	Span # 1	Span # where maximum occurs	=	Span # 1
Maximum Deflection					
Max Downward Transient Deflection	0.257 in	Ratio = 793 >=360	Span: 1 : S Only		
Max Upward Transient Deflection	-0.162 in	Ratio = 678 >=360	Span: 2 : S Only		
Max Downward Total Deflection	0.485 in	Ratio = 420 >=240	Span: 1 : +D+S		
Max Upward Total Deflection	-0.315 in	Ratio = 348 >=240	Span: 2 : +D+S		

Maximum Forces & Stresses for Load Combinations

Load Combination		Max Stress Ratios										Moment Values			Shear Values		
Segment Length	Span #	M	V	CD	CM	C _t	CLx	C _F	C _{fu}	C _i	C _r	M	fb	F'b	V	fv	F'v
D Only														0.0	0.00	0.0	0.0
Length = 17.0 ft	1	0.450	0.128	0.90	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.71	400.9	891.0	0.19	20.8	162.0
Length = 4.583 ft	2	0.152	0.128	0.90	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.24	135.6	891.0	0.09	20.8	162.0
+D+Lr						1.00	1.00	1.00	1.100	1.00	1.00			0.0	0.00	0.0	0.0

Wood Beam

Project File: Ogden Community Services Building.ec6

LIC# : KW-06015170, Build:20.24.12.17

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Joist 1

Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios										Moment Values			Shear Values		
			M	V	CD	CM	C _t	CLx	C _F	C _{fu}	C _i	C _r	M	fb	F'b	V	fv	F'v
Length = 17.0 ft	1		0.606	0.173	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	1.34	749.5	1,237.5	0.36	38.9	225.0
Length = 4.583 ft	2		0.205	0.173	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.45	253.4	1,237.5	0.16	38.9	225.0
+D+S						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 17.0 ft	1		0.753	0.220	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	1.53	857.8	1,138.5	0.42	45.5	207.0
Length = 4.583 ft	2		0.285	0.220	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.58	324.1	1,138.5	0.21	45.5	207.0
+D+0.750Lr						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 17.0 ft	1		0.535	0.153	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	1.18	662.3	1,237.5	0.32	34.3	225.0
Length = 4.583 ft	2		0.181	0.153	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.40	224.0	1,237.5	0.15	34.3	225.0
+D+0.750S						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 17.0 ft	1		0.653	0.190	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	1.33	743.6	1,138.5	0.36	39.3	207.0
Length = 4.583 ft	2		0.243	0.190	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.49	277.0	1,138.5	0.18	39.3	207.0
+0.60D						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 17.0 ft	1		0.152	0.043	1.60	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.43	240.6	1,584.0	0.12	12.5	288.0
Length = 4.583 ft	2		0.051	0.043	1.60	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.14	81.3	1,584.0	0.05	12.5	288.0

Overall Maximum Deflections

Span	Load Combination	Max. "+" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
1	+D+S	0.4848	8.263		0.0000	0.000
2		0.0000	8.263	+D+S	-0.3154	4.583

Vertical Reactions

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2	Support 3
Max Upward from all Load Conditions	0.391	0.711	
Max Upward from Load Combinations	0.391	0.711	
Max Upward from Load Cases	0.210	0.396	
D Only	0.181	0.315	
+D+Lr	0.339	0.589	
+D+S	0.391	0.711	
+D+0.750Lr	0.300	0.521	
+D+0.750S	0.339	0.612	
+0.60D	0.109	0.189	
Lr Only	0.158	0.274	
S Only	0.210	0.396	

Wood Beam

Project File: Ogden Community Services Building.ec6

LIC# : KW-06015170, Build:20.24.12.17

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Joist 2

CODE REFERENCES

Calculations per NDS 2018, IBC 2021, SDPWS 2021

Load Combination Set : IBC 2021

Material Properties

Analysis Method : Allowable Stress Design

Load Combination : IBC 2021

Wood Species : Douglas Fir-Larch

Wood Grade : No.2

Beam Bracing : Beam is Fully Braced against lateral-torsional buckling

Fb + 900 psi

Fb - 900 psi

Fc - Prll 1350 psi

Fc - Perp 625 psi

Fv 180 psi


Ft 575 psi

E : Modulus of Elasticity

Ebend- xx 1600ksi

Eminbend - xx 580ksi

Density 31.21pcf



Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Beam self weight calculated and added to loading

Uniform Load : D = 0.020, Lr = 0.020, S = 0.0270 , Tributary Width = 1.0 ft

DESIGN SUMMARY

Design OK

Maximum Bending Stress Ratio				Maximum Shear Stress Ratio			
Section used for this span	=	0.444	1	Section used for this span	=	0.137	1
		2x10				2x10	
fb: Actual	=	504.97 psi		fv: Actual	=	28.41 psi	
F'b	=	1,138.50 psi		F'v	=	207.00 psi	
Load Combination				Load Combination			
			+D+S				+D+S
Location of maximum on span	=	6.000 ft		Location of maximum on span	=	0.000 ft	
Span # where maximum occurs	=	Span # 1		Span # where maximum occurs	=	Span # 1	
Maximum Deflection							
Max Downward Transient Deflection	0.080 in	Ratio =	1798 >=360	Span: 1 : S Only			
Max Upward Transient Deflection	0 in	Ratio =	0 <360	n/a			
Max Downward Total Deflection	0.148 in	Ratio =	971 >=180	Span: 1 : +D+S			
Max Upward Total Deflection	0 in	Ratio =	0 <180	n/a			

Maximum Forces & Stresses for Load Combinations

Load Combination		Max Stress Ratios										Moment Values			Shear Values		
Segment Length	Span #	M	V	CD	CM	C _t	CLx	C _F	C _{fu}	C _i	C _r	M	fb	F'b	V	fv	F'v
D Only														0.0	0.00	0.0	0.0
Length = 12.0 ft	1	0.261	0.081	0.90	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.41	232.3	891.0	0.12	13.1	162.0
+D+Lr														0.0	0.00	0.0	0.0
Length = 12.0 ft	1	0.351	0.109	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.77	434.3	1,237.5	0.23	24.4	225.0
+D+S														0.0	0.00	0.0	0.0
Length = 12.0 ft	1	0.444	0.137	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.90	505.0	1,138.5	0.26	28.4	207.0
+D+0.750Lr														0.0	0.00	0.0	0.0
Length = 12.0 ft	1	0.310	0.096	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.68	383.8	1,237.5	0.20	21.6	225.0
+D+0.750S														0.0	0.00	0.0	0.0

Wood Beam

Project File: Ogden Community Services Building.ec6

LIC# : KW-06015170, Build:20.24.12.17

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Joist 2

Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios										Moment Values			Shear Values		
			M	V	CD	CM	C _t	CLx	C _F	C _{fu}	C _i	C _r	M	fb	F'b	V	fv	F'v
Length = 12.0 ft		1	0.384	0.119	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.78	436.8	1,138.5	0.23	24.6	207.0
+0.60D						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 12.0 ft		1	0.088	0.027	1.60	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.25	139.4	1,584.0	0.07	7.8	288.0

Overall Maximum Deflections

Span	Load Combination	Max. "." Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
1	+D+S	0.1483	6.044		0.0000	0.000

Vertical Reactions

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
Max Upward from all Load Conditions	0.300	0.300
Max Upward from Load Combinations	0.300	0.300
Max Upward from Load Cases	0.162	0.162
D Only	0.138	0.138
+D+Lr	0.258	0.258
+D+S	0.300	0.300
+D+0.750Lr	0.228	0.228
+D+0.750S	0.260	0.260
+0.60D	0.083	0.083
Lr Only	0.120	0.120
S Only	0.162	0.162

Wood Beam

Project File: Ogden Community Services Building.ec6

LIC# : KW-06015170, Build:20.24.12.17

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Joist 3

CODE REFERENCES

Calculations per NDS 2018, IBC 2021, SDPWS 2021

Load Combination Set : IBC 2021

Material Properties

Analysis Method : Allowable Stress Design

Load Combination : IBC 2021

Wood Species : Douglas Fir-Larch

Wood Grade : No.2

Beam Bracing : Beam is Fully Braced against lateral-torsional buckling

Fb + 900.0 psi

Fb - 900.0 psi

Fc - Prll 1,350.0 psi

Fc - Perp 625.0 psi

Fv 180.0 psi


Ft 575.0 psi

E : Modulus of Elasticity

Ebend- xx 1,600.0ksi

Eminbend - xx 580.0ksi

Density 31.210pcf



Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Beam self weight calculated and added to loading

Loads on all spans...

Uniform Load on ALL spans : D = 0.020, Lr = 0.020 k/ft

Load for Span Number 1

Uniform Load : S = 0.0270, Tributary Width = 1.0 ft

Load for Span Number 2

Uniform Load : S = 0.0320, Tributary Width = 1.0 ft

DESIGN SUMMARY

Design OK

Maximum Bending Stress Ratio	=	0.392 1	Maximum Shear Stress Ratio	=	0.173 1
Section used for this span		2x10	Section used for this span		2x10
fb: Actual	=	446.70psi	fv: Actual	=	35.85 psi
F'b	=	1,138.50psi	F'v	=	207.00 psi
Load Combination			Load Combination		
		+D+S			+D+S
Location of maximum on span	=	5.665ft	Location of maximum on span	=	12.274 ft
Span # where maximum occurs	=	Span # 1	Span # where maximum occurs	=	Span # 1
Maximum Deflection					
Max Downward Transient Deflection	0.073 in	Ratio = 2126 >=360	Span: 1 : S Only		
Max Upward Transient Deflection	-0.036 in	Ratio = 3026 >=360	Span: 2 : Lr Only		
Max Downward Total Deflection	0.141 in	Ratio = 1108 >=240	Span: 1 : +D+S		
Max Upward Total Deflection	-0.077 in	Ratio = 1406 >=240	Span: 2 : +D+Lr		

Maximum Forces & Stresses for Load Combinations

Load Combination		Max Stress Ratios										Moment Values			Shear Values		
Segment Length	Span #	M	V	CD	CM	C _t	CLx	C _F	C _{fu}	C _i	C _r	M	fb	F'b	V	fv	F'v
D Only																	
Length = 13.0 ft	1	0.237	0.101	0.90	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.38	211.2	891.0	0.15	16.3	162.0
Length = 4.50 ft	2	0.147	0.101	0.90	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.23	130.7	891.0	0.09	16.3	162.0
+D+Lr																	
					1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0

Wood Beam

Project File: Ogden Community Services Building.ec6

LIC# : KW-06015170, Build:20.24.12.17

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Joist 3

Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios										Moment Values			Shear Values		
			M	V	CD	CM	C _t	CLx	C _F	C _{fu}	C _i	C _r	M	fb	F'b	V	fv	F'v
Length = 13.0 ft	1		0.319	0.135	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.70	394.9	1,237.5	0.28	30.5	225.0
Length = 4.50 ft	2		0.197	0.135	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.44	244.3	1,237.5	0.16	30.5	225.0
+D+S						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.0 ft	1		0.392	0.173	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.80	446.7	1,138.5	0.33	35.8	207.0
Length = 4.50 ft	2		0.274	0.173	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.56	312.4	1,138.5	0.21	35.8	207.0
+D+0.750Lr						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.0 ft	1		0.282	0.120	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.62	348.9	1,237.5	0.25	26.9	225.0
Length = 4.50 ft	2		0.174	0.120	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.38	215.9	1,237.5	0.14	26.9	225.0
+D+0.750S						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.0 ft	1		0.341	0.150	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.69	387.8	1,138.5	0.29	31.0	207.0
Length = 4.50 ft	2		0.235	0.150	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.48	267.0	1,138.5	0.18	31.0	207.0
+0.60D						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.0 ft	1		0.080	0.034	1.60	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.23	126.7	1,584.0	0.09	9.8	288.0
Length = 4.50 ft	2		0.050	0.034	1.60	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.14	78.4	1,584.0	0.05	9.8	288.0

Overall Maximum Deflections

Span	Load Combination	Max. "+" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
1	+D+S	0.1408	6.173		0.0000	0.000
2		0.0000	6.173	+D+Lr	-0.0767	4.500

Vertical Reactions

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2	Support 3
Max Upward from all Load Conditions	0.282	0.615	
Max Upward from Load Combinations	0.282	0.615	
Max Upward from Load Cases	0.151	0.344	
D Only	0.132	0.271	
+D+Lr	0.246	0.507	
+D+S	0.282	0.615	
+D+0.750Lr	0.217	0.448	
+D+0.750S	0.245	0.529	
+0.60D	0.079	0.163	
Lr Only	0.114	0.236	
S Only	0.151	0.344	

Wood Beam

Project File: Ogden Community Services Building.ec6

LIC#: KW-06015170, Build:20.24.12.17

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Joist 3 - w/ Drift

CODE REFERENCES

Calculations per NDS 2018, IBC 2021, SDPWS 2021

Load Combination Set : IBC 2021


Material Properties

Analysis Method : Allowable Stress Design
 Load Combination : IBC 2021

Wood Species : Douglas Fir-Larch
 Wood Grade : No.2

Beam Bracing : Beam is Fully Braced against lateral-torsional buckling

Fb +	900.0 psi	E : Modulus of Elasticity	
Fb -	900.0 psi	Ebend- xx	1,600.0ksi
Fc - Prll	1,350.0 psi	Eminbend - xx	580.0ksi
Fc - Perp	625.0 psi		
Fv	180.0 psi		
Ft	575.0 psi	Density	31.210pcf



Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Beam self weight calculated and added to loading

Loads on all spans...

Uniform Load on ALL spans : D = 0.020, Lr = 0.020 k/ft

Load for Span Number 1

Uniform Load : S = 0.0270 , Tributary Width = 1.0 ft

Varying Uniform Load : S = 0.0320->0.0 k/ft, Extent = 0.0 -->> 6.667 ft, Trib Width = 1.0 ft

Load for Span Number 2

Uniform Load : S = 0.0320 , Tributary Width = 1.0 ft

DESIGN SUMMARY

Design OK

Maximum Bending Stress Ratio				Maximum Shear Stress Ratio			
Section used for this span				Section used for this span			
fb: Actual				fv: Actual			
F'b				F'v			
Load Combination				Load Combination			
Location of maximum on span				Location of maximum on span			
Span # where maximum occurs				Span # where maximum occurs			
Maximum Deflection							
Max Downward Transient Deflection				Span: 1 : S Only			
Max Upward Transient Deflection				Span: 2 : S Only			
Max Downward Total Deflection				Span: 1 : +D+S			
Max Upward Total Deflection				Span: 2 : +D+S			

Maximum Forces & Stresses for Load Combinations

Load Combination		Max Stress Ratios										Moment Values			Shear Values		
Segment Length	Span #	M	V	CD	CM	C _t	CLx	C _F	C _{fu}	C _i	C _r	M	fb	F'b	V	fv	F'v
D Only																	
Length = 13.0 ft	1	0.237	0.101	0.90	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.38	211.2	891.0	0.15	16.3	162.0
Length = 4.50 ft	2	0.147	0.101	0.90	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.23	130.7	891.0	0.09	16.3	162.0

Wood Beam

Project File: Ogden Community Services Building.ec6

LIC# : KW-06015170, Build:20.24.12.17

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Joist 3 - w/ Drift

Maximum Forces & Stresses for Load Combinations

Load Combination		Max Stress Ratios										Moment Values			Shear Values			
Segment	Length	Span #	M	V	CD	CM	C _t	CLx	C _F	C _{fu}	C _i	C _r	M	fb	F'b	V	fv	F'v
+D+Lr						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.0 ft		1	0.319	0.135	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.70	394.9	1,237.5	0.28	30.5	225.0
Length = 4.50 ft		2	0.197	0.135	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.44	244.3	1,237.5	0.16	30.5	225.0
+D+S						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.0 ft		1	0.459	0.183	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.93	522.7	1,138.5	0.35	37.8	207.0
Length = 4.50 ft		2	0.274	0.183	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.56	312.4	1,138.5	0.21	37.8	207.0
+D+0.750Lr						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.0 ft		1	0.282	0.120	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.62	348.9	1,237.5	0.25	26.9	225.0
Length = 4.50 ft		2	0.174	0.120	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.38	215.9	1,237.5	0.14	26.9	225.0
+D+0.750S						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.0 ft		1	0.391	0.157	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.79	444.7	1,138.5	0.30	32.4	207.0
Length = 4.50 ft		2	0.235	0.157	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.48	267.0	1,138.5	0.18	32.4	207.0
+0.60D						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 13.0 ft		1	0.080	0.034	1.60	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.23	126.7	1,584.0	0.09	9.8	288.0
Length = 4.50 ft		2	0.050	0.034	1.60	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.14	78.4	1,584.0	0.05	9.8	288.0

Overall Maximum Deflections

Span	Load Combination	Max. "-" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
1	+D+S	0.1658	6.101		0.0000	0.000
2		0.0000	6.101	+D+S	-0.0989	4.500

Vertical Reactions

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2	Support 3
Max Upward from all Load Conditions	0.371	0.634	
Max Upward from Load Combinations	0.371	0.634	
Max Upward from Load Cases	0.239	0.363	
D Only	0.132	0.271	
+D+Lr	0.246	0.507	
+D+S	0.371	0.634	
+D+0.750Lr	0.217	0.448	
+D+0.750S	0.311	0.543	
+0.60D	0.079	0.163	
Lr Only	0.114	0.236	
S Only	0.239	0.363	

Wood Beam

Project File: Ogden Community Services Building.ec6

LIC# : KW-06015170, Build:20.24.12.17

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Joist 4

CODE REFERENCES

Calculations per NDS 2018, IBC 2021, SDPWS 2021

Load Combination Set : IBC 2021


Material Properties

Analysis Method : Allowable Stress Design
 Load Combination : IBC 2021

Wood Species : Douglas Fir-Larch
 Wood Grade : No.2

Beam Bracing : Beam is Fully Braced against lateral-torsional buckling

F_b + 900.0 psi
 F_b - 900.0 psi
 F_c - Prll 1,350.0 psi
 F_c - Perp 625.0 psi
 F_v 180.0 psi
 F_t 575.0 psi
 E : Modulus of Elasticity
 E_{bend-xx} 1,600.0 ksi
 E_{minbend-xx} 580.0 ksi
 Density 31.210 pcf



Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Beam self weight calculated and added to loading

Loads on all spans...

Uniform Load on ALL spans : D = 0.020, L_r = 0.020 k/ft

Load for Span Number 1

Uniform Load : S = 0.0270, Tributary Width = 1.0 ft

Load for Span Number 2

Uniform Load : S = 0.0320, Tributary Width = 1.0 ft

DESIGN SUMMARY

Design OK

Maximum Bending Stress Ratio	=	0.793 1	Maximum Shear Stress Ratio	=	0.225 1
Section used for this span		2x10	Section used for this span		2x10
fb: Actual	=	903.14psi	fv: Actual	=	46.66 psi
F'b	=	1,138.50psi	F'v	=	207.00 psi
Load Combination			Load Combination		
Location of maximum on span	=	8.037ft	Location of maximum on span	=	16.655 ft
Span # where maximum occurs	=	Span # 1	Span # where maximum occurs	=	Span # 1
Maximum Deflection					
Max Downward Transient Deflection	0.283 in	Ratio = 735 >=360	Span: 1 : S Only		
Max Upward Transient Deflection	-0.178 in	Ratio = 606 >=360	Span: 2 : S Only		
Max Downward Total Deflection	0.533 in	Ratio = 390 >=240	Span: 1 : +D+S		
Max Upward Total Deflection	-0.344 in	Ratio = 312 >=240	Span: 2 : +D+S		

Maximum Forces & Stresses for Load Combinations

Load Combination		Max Stress Ratios										Moment Values			Shear Values		
Segment Length	Span #	M	V	CD	CM	C _t	CLx	C _F	C _{fu}	C _i	C _r	M	fb	F'b	V	fv	F'v
D Only														0.0	0.00	0.0	0.0
Length = 17.333 ft	1	0.473	0.132	0.90	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.75	421.6	891.0	0.20	21.3	162.0
Length = 4.50 ft	2	0.147	0.132	0.90	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.23	130.7	891.0	0.09	21.3	162.0
+D+L _r					1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0

Wood Beam

Project File: Ogden Community Services Building.ec6

LIC# : KW-06015170, Build:20.24.12.17

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Joist 4

Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios										Moment Values			Shear Values		
			M	V	CD	CM	C _t	CLx	C _F	C _{fu}	C _i	C _r	M	fb	F'b	V	fv	F'v
Length = 17.333 ft	1		0.637	0.177	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	1.40	788.0	1,237.5	0.37	39.9	225.0
Length = 4.50 ft	2		0.197	0.177	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.44	244.3	1,237.5	0.16	39.9	225.0
+D+S						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 17.333 ft	1		0.793	0.225	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	1.61	903.1	1,138.5	0.43	46.7	207.0
Length = 4.50 ft	2		0.274	0.225	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.56	312.4	1,138.5	0.21	46.7	207.0
+D+0.750Lr						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 17.333 ft	1		0.563	0.157	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	1.24	696.4	1,237.5	0.33	35.2	225.0
Length = 4.50 ft	2		0.174	0.157	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.38	215.9	1,237.5	0.14	35.2	225.0
+D+0.750S						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 17.333 ft	1		0.688	0.195	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	1.40	782.7	1,138.5	0.37	40.3	207.0
Length = 4.50 ft	2		0.235	0.195	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.48	267.0	1,138.5	0.18	40.3	207.0
+0.60D						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 17.333 ft	1		0.160	0.044	1.60	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.45	252.9	1,584.0	0.12	12.8	288.0
Length = 4.50 ft	2		0.050	0.044	1.60	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.14	78.4	1,584.0	0.05	12.8	288.0

Overall Maximum Deflections

Span	Load Combination	Max. "+" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
1	+D+S	0.5329	8.425		0.0000	0.000
2		0.0000	8.425	+D+S	-0.3443	4.500

Vertical Reactions

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2	Support 3
Max Upward from all Load Conditions	0.401	0.713	
Max Upward from Load Combinations	0.401	0.713	
Max Upward from Load Cases	0.215	0.397	
D Only	0.186	0.316	
+D+Lr	0.348	0.591	
+D+S	0.401	0.713	
+D+0.750Lr	0.307	0.523	
+D+0.750S	0.347	0.614	
+0.60D	0.112	0.190	
Lr Only	0.162	0.275	
S Only	0.215	0.397	



DUNN ASSOCIATES, INC
Consulting Structural Engineers

Title
OGDEN COMMUNITY SERVICES BUILDING

Sheet Number:	O-1
Job Number:	240268
Date:	03/11/2025
By:	CF

OPENING DESIGN




Sheet Number:	O-2
Job Number:	240268
Date:	
By:	CF

Title


OGDEN COMMUNITY SERVICES BUILDING

OPENINGS KEY PLAN





Sheet Number:	O-3
Job Number:	240268
Date:	
By:	CF

[illegible]
$$2 \text{ ft} * 22.11 \text{ psf} = 44.22 \text{ psf}$$



DUNN ASSOCIATES, INC
Consulting Structural Engineers

Title
OGDEN COMMUNITY SERVICES BUILDING


Sheet Number: **O-4**

Job Number: **240268**

Date:

By: **CF**

OPENING 2



OPENING 2

**LOADS FROM JOIST 1 AND JOIST 2
JOIST 1**

DL = 0.18 klf
LLr = 0.16 klf
SL = 0.21 klf

JOIST 2


DL = 0.14 klf
LLr = 0.12 klf
SL = 0.16 klf

SPAN = 7'-10"

USE (3) 2x10 DFL No. 2 FOR BEAM

INTERIOR 5 PSF PRESSURE
 $\text{TRIB} = 7.83' / 2 + 1' / 2 = 4.416'$
 $5 \text{ psf} \times 4.416' = 22.083 \text{ plf}$

FOR BEARING STUDS, USE (2) 2x6
USE (1) 2x6 KING STUD



Wood Beam

Project File: Ogden Community Services Building.ec6

LIC# : KW-06015170, Build:20.24.12.17

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Opening 2: Wood Beam

CODE REFERENCES

Calculations per NDS 2018, IBC 2021, SDPWS 2021

Load Combination Set : IBC 2021


Material Properties

Analysis Method : Allowable Stress Design
 Load Combination : IBC 2021

Wood Species : Douglas Fir-Larch
 Wood Grade : No.2

Beam Bracing : Beam is Fully Braced against lateral-torsional buckling

Fb + 900.0 psi
 Fb - 900.0 psi
 Fc - Prll 1,350.0 psi
 Fc - Perp 625.0 psi
 Fv 180.0 psi
 Ft 575.0 psi
 E : Modulus of Elasticity
 Ebend- xx 1,600.0 ksi
 Eminbend - xx 580.0 ksi
 Density 31.210pcf



Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Beam self weight NOT internally calculated and added

Uniform Load : D = 0.180, Lr = 0.160, S = 0.210, Tributary Width = 1.0 ft, (Joist 1 Loads)

Uniform Load : D = 0.140, Lr = 0.120, S = 0.160, Tributary Width = 1.0 ft, (Joist 2 Loads)

DESIGN SUMMARY

Design OK

Maximum Bending Stress Ratio				Maximum Shear Stress Ratio			
Section used for this span				Section used for this span			
fb: Actual = 989.67 psi				fv: Actual = 78.91 psi			
F'b = 1,138.50 psi				F'v = 207.00 psi			
Load Combination				Load Combination			
Location of maximum on span = 3.917 ft				Location of maximum on span = 7.090 ft			
Span # where maximum occurs = Span # 1				Span # where maximum occurs = Span # 1			
Maximum Deflection							
Max Downward Transient Deflection 0.066 in				Span: 1 : S Only			
Max Upward Transient Deflection 0 in				n/a			
Max Downward Total Deflection 0.124 in				Span: 1 : +D+S			
Max Upward Total Deflection 0 in				n/a			

Maximum Forces & Stresses for Load Combinations

Load Combination		Max Stress Ratios										Moment Values			Shear Values		
Segment Length	Span #	M	V	CD	CM	C _t	CLx	C _F	C _{fu}	C _i	C _r	M	fb	F'b	V	fv	F'v
D Only														0.0			
Length = 7.833 ft	1	0.515	0.226	0.90	1.00	1.00	1.00	1.100	1.00	1.00	1.00	2.45	459.0	891.0	1.02	36.6	162.0
+D+Lr														0.0			
Length = 7.833 ft	1	0.695	0.305	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	4.60	860.6	1,237.5	1.90	68.6	225.0
+D+S														0.0			
Length = 7.833 ft	1	0.869	0.381	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	5.29	989.7	1,138.5	2.19	78.9	207.0
+D+0.750Lr														0.0			
Length = 7.833 ft	1	0.614	0.269	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	4.07	760.2	1,237.5	1.68	60.6	225.0

Wood Beam

Project File: Ogden Community Services Building.ec6

LIC# : KW-06015170, Build:20.24.12.17

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Opening 2: Wood Beam

Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios										Moment Values			Shear Values		
			M	V	CD	CM	C _t	CLx	C _F	C _{fu}	C _i	C _r	M	fb	F'b	V	fv	F'v
+D+0.750S						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 7.833 ft	1		0.753	0.330	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	4.58	857.0	1,138.5	1.90	68.3	207.0
+1.153D						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 7.833 ft	1		0.334	0.147	1.60	1.00	1.00	1.00	1.100	1.00	1.00	1.00	2.83	529.2	1,584.0	1.17	42.2	288.0
+1.115D+0.750S						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 7.833 ft	1		0.574	0.252	1.60	1.00	1.00	1.00	1.100	1.00	1.00	1.00	4.86	909.7	1,584.0	2.01	72.5	288.0
+0.60D						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 7.833 ft	1		0.174	0.076	1.60	1.00	1.00	1.00	1.100	1.00	1.00	1.00	1.47	275.4	1,584.0	0.61	22.0	288.0
+0.4470D						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 7.833 ft	1		0.130	0.057	1.60	1.00	1.00	1.00	1.100	1.00	1.00	1.00	1.10	205.2	1,584.0	0.45	16.4	288.0

Overall Maximum Deflections

Span	Load Combination	Max. "-" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
1	+D+S	0.1238	3.945		0.0000	0.000

Vertical Reactions

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
Max Upward from all Load Conditions	2.703	2.703
Max Upward from Load Combinations	2.703	2.703
Max Upward from Load Cases	1.449	1.449
D Only	1.253	1.253
+D+Lr	2.350	2.350
+D+S	2.703	2.703
+D+0.750Lr	2.076	2.076
+D+0.750S	2.340	2.340
+0.60D	0.752	0.752
Lr Only	1.097	1.097
S Only	1.449	1.449

Wood Column

Project File: Ogden Community Services Building.ec6

LIC# : KW-06015170, Build:20.25.02.26

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Opening 2 Post

Code References

Calculations per NDS 2018, IBC 2021, SDPWS 2021
 Load Combinations Used : IBC 2021

General Information

Analysis Method	Allowable Stress Design			Wood Section Name	2-2x6	
End Fixities	Top & Bottom Pinned			Wood Grading/Manuf.	Graded Lumber	
Overall Column Height	10 ft			Wood Member Type	Sawn	
(Used for non-slender calculations)						
Wood Species	Douglas Fir-Larch			Exact Width	3.0 in	Allow Stress Modification Factors
Wood Grade	No.2			Exact Depth	5.50 in	
Fb +	900.0 psi	Fv	180.0 psi	Area	16.50 in^2	Cf or Cv for Bending 1.30
Fb -	900.0 psi	Ft	575.0 psi	Ix	41.594 in^4	Cf or Cv for Compression 1.10
Fc - Prll	1,350.0 psi	Density	31.210 pcf	Iy	12.375 in^4	Cf or Cv for Tension 1.30
Fc - Perp	625.0 psi					Cm : Wet Use Factor 1.0
						Ct : Temperature Fact 1.0
E : Modulus of Elasticity . . .	x-x Bending	y-y Bending	Axial			Cfu : Flat Use Factor 1.0
	Basic	1,600.0	1,600.0	1,600.0 ksi		Kf : Built-up columns 1.0
	Minimum	580.0	580.0			Use Cr : Repetitive ? No
Column Buckling Condition:						
ABOUT X-X Axis: Lux = 10 ft, Kx = 1.0						
ABOUT Y-Y Axis: Luy = 10 ft, Ky = 1.0						

Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Column self weight included : 35.761 lbs * Dead Load Factor

AXIAL LOADS . . .

Axial Load at 10.0 ft, Xecc = 1.0 in, D = 1.250, Lr = 1.10, S = 1.450 k

BENDING LOADS . . .

Lat. Uniform Load creating Mx-x, L = 0.02208 k/ft

DESIGN SUMMARY

Bending & Shear Check Results

PASS Max. Axial+Bending Stress Ratio = **0.8798 : 1**
 Load Combination +D+S
 Governing NDS Formula Comp + Myy, NDS Eq. 3.9-3
 Location of max.above base 9.933 ft
 At maximum location values are .
 Applied Axial 2.736 k
 Applied Mx 0.0 k-ft
 Applied My -0.2235 k-ft
 Fc : Allowable 286.430 psi

Maximum SERVICE Lateral Load Reactions . .

Top along Y-Y 0.1104 k Bottom along Y-Y 0.1104 k
 Top along X-X 0.02250 k Bottom along X-X 0.02250 k

Maximum SERVICE Load Lateral Deflections . . .

Along Y-Y 0.07547 in at 5.034 ft above base
 for load combination : +D+L
 Along X-X -0.1271 in at 5.839 ft above base
 for load combination : +D+S

Other Factors used to calculate allowable stresses . . .

Bending Compression Tension

PASS Maximum Shear Stress Ratio = **0.05577 : 1**
 Load Combination +D+L
 Location of max.above base 10.0 ft
 Applied Design Shear 15.057 psi
 Allowable Shear 180.0 psi

Load Combination Results

Load Combination	C _D	C _P	Maximum Axial + Bending Stress Ratios			Maximum Shear Ratios		
			Stress Ratio	Status	Location	Stress Ratio	Status	Location
D Only	0.900	0.212	0.2756	PASS	0.0 ft	0.005845	PASS	10.0 ft
+D+L	1.000	0.192	0.3782	PASS	6.040 ft	0.05577	PASS	10.0 ft
+D+Lr	1.250	0.155	0.6289	PASS	9.933 ft	0.007912	PASS	10.0 ft
+D+S	1.150	0.168	0.8798	PASS	9.933 ft	0.009881	PASS	10.0 ft
+D+0.750Lr+0.750L	1.250	0.155	0.5234	PASS	7.852 ft	0.03346	PASS	0.0 ft
+D+0.750L+0.750S	1.150	0.168	0.6723	PASS	8.523 ft	0.03637	PASS	0.0 ft
+0.60D	1.600	0.122	0.1613	PASS	0.0 ft	0.001973	PASS	10.0 ft

Wood Column

Project File: Ogden Community Services Building.ec6

LIC# : KW-06015170, Build:20.25.02.26

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Opening 2 Post

Maximum Reactions


Note: Only non-zero reactions are listed.

Load Combination	X-X Axis Reaction		k	Y-Y Axis Reaction		Axial Reaction	My - End Moments k-ft		Mx - End Moments	
	@ Base	@ Top		@ Base	@ Top	@ Base	@ Base	@ Top	@ Base	@ Top
D Only	-0.010	0.010				1.286				
+D+L	-0.010	0.010		0.110	0.110	1.286				
+D+Lr	-0.020	0.020				2.386				
+D+S	-0.023	0.023				2.736				
+D+0.750Lr+0.750L	-0.017	0.017		0.083	0.083	2.111				
+D+0.750L+0.750S	-0.019	0.019		0.083	0.083	2.373				
+0.60D	-0.006	0.006				0.771				
Lr Only	-0.009	0.009				1.100				
L Only				0.110	0.110					
S Only	-0.012	0.012				1.450				

Maximum Deflections for Load Combinations

Load Combination	Max. X-X Deflection	Distance	Max. Y-Y Deflection	Distance
D Only	-0.0588 in	5.839ft	0.000 in	0.000 ft
+D+L	-0.0588 in	5.839ft	0.075 in	5.034 ft
+D+Lr	-0.1106 in	5.839ft	0.000 in	0.000 ft
+D+S	-0.1271 in	5.839ft	0.000 in	0.000 ft
+D+0.750Lr+0.750L	-0.0976 in	5.839ft	0.057 in	5.034 ft
+D+0.750L+0.750S	-0.1100 in	5.839ft	0.057 in	5.034 ft
+0.60D	-0.0353 in	5.839ft	0.000 in	0.000 ft
Lr Only	-0.0518 in	5.839ft	0.000 in	0.000 ft
L Only	0.0000 in	0.000ft	0.075 in	5.034 ft
S Only	-0.0682 in	5.839ft	0.000 in	0.000 ft

Sketches





Sheet Number:	O-9
Job Number:	240268
Date:	
By:	CF

[illegible]

USE (2) 2x10 AS BEAM
USE (2) 2x6 BEARING STUDS
USE (1) 2x6 KING STUD

Wood Beam

Project File: Ogden Community Services Building.ec6

LIC# : KW-06015170, Build:20.24.12.17

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Opening 3: Wood Beam

CODE REFERENCES

Calculations per NDS 2018, IBC 2021, SDPWS 2021

Load Combination Set : IBC 2021

Material Properties

Analysis Method : Allowable Stress Design

Load Combination : IBC 2021

Wood Species : Douglas Fir-Larch

Wood Grade : No.2

Beam Bracing : Beam is Fully Braced against lateral-torsional buckling

Fb + 900.0 psi

Fb - 900.0 psi

Fc - Prll 1,350.0 psi

Fc - Perp 625.0 psi

Fv 180.0 psi


Ft 575.0 psi

E : Modulus of Elasticity

Ebend- xx 1,600.0 ksi

Eminbend - xx 580.0 ksi

Density 31.210pcf



Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Beam self weight NOT internally calculated and added

Uniform Load : D = 0.190, Lr = 0.160, S = 0.220, Tributary Width = 1.0 ft, (Joist 4 Loads)

Uniform Load : D = 0.140, Lr = 0.120, S = 0.160, Tributary Width = 1.0 ft, (Joist 2 Loads)

DESIGN SUMMARY

Design OK

Maximum Bending Stress Ratio				Maximum Shear Stress Ratio			
Section used for this span				Section used for this span			
= 0.787 : 1				= 0.414 : 1			
2-2x10				2-2x10			
fb: Actual = 896.19psi				fv: Actual = 85.72 psi			
F'b = 1,138.50psi				F'v = 207.00 psi			
Load Combination				Load Combination			
Location of maximum on span = 3.000ft				Location of maximum on span = 0.000 ft			
Span # where maximum occurs = Span # 1				Span # where maximum occurs = Span # 1			
Maximum Deflection							
Max Downward Transient Deflection 0.035 in Ratio = 2045 >=360				Span: 1 : S Only			
Max Upward Transient Deflection 0 in Ratio = 0 <360				n/a			
Max Downward Total Deflection 0.066 in Ratio = 1094 >=240				Span: 1 : +D+S			
Max Upward Total Deflection 0 in Ratio = 0 <240				n/a			

Maximum Forces & Stresses for Load Combinations

Load Combination		Max Stress Ratios										Moment Values			Shear Values		
Segment Length	Span #	M	V	CD	CM	C _t	CLx	C _F	C _{fu}	C _i	C _r	M	fb	F'b	V	fv	F'v
D Only																	
Length = 6.0 ft	1	0.467	0.246	0.90	1.00	1.00	1.00	1.100	1.00	1.00	1.00	1.49	416.5	891.0	0.74	39.8	162.0
+D+Lr																	
Length = 6.0 ft	1	0.622	0.327	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	2.75	770.0	1,237.5	1.36	73.6	225.0
+D+S																	
Length = 6.0 ft	1	0.787	0.414	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	3.20	896.2	1,138.5	1.59	85.7	207.0
+D+0.750Lr																	
Length = 6.0 ft	1	0.551	0.290	1.25	1.00	1.00	1.00	1.100	1.00	1.00	1.00	2.43	681.6	1,237.5	1.21	65.2	225.0

Wood Beam

Project File: Ogden Community Services Building.ec6

LIC# : KW-06015170, Build:20.24.12.17

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Opening 3: Wood Beam

Maximum Forces & Stresses for Load Combinations

Load Combination	Segment Length	Span #	Max Stress Ratios										Moment Values			Shear Values		
			M	V	CD	CM	C _t	CLx	C _F	C _{fu}	C _i	C _r	M	fb	F'b	V	fv	F'v
+D+0.750S						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 6.0 ft	1		0.682	0.359	1.15	1.00	1.00	1.00	1.100	1.00	1.00	1.00	2.77	776.3	1,138.5	1.37	74.3	207.0
+1.153D						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 6.0 ft	1		0.303	0.160	1.60	1.00	1.00	1.00	1.100	1.00	1.00	1.00	1.71	480.3	1,584.0	0.85	45.9	288.0
+1.115D+0.750S						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 6.0 ft	1		0.520	0.274	1.60	1.00	1.00	1.00	1.100	1.00	1.00	1.00	2.94	824.1	1,584.0	1.46	78.8	288.0
+0.60D						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 6.0 ft	1		0.158	0.083	1.60	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.89	249.9	1,584.0	0.44	23.9	288.0
+0.4470D						1.00	1.00	1.00	1.100	1.00	1.00	1.00			0.0	0.00	0.0	0.0
Length = 6.0 ft	1		0.118	0.062	1.60	1.00	1.00	1.00	1.100	1.00	1.00	1.00	0.66	186.2	1,584.0	0.33	17.8	288.0

Overall Maximum Deflections

Span	Load Combination	Max. "+" Defl	Location in Span	Load Combination	Max. "+" Defl	Location in Span
1	+D+S	0.0658	3.022		0.0000	0.000

Vertical Reactions

Support notation : Far left is #1

Values in KIPS

Load Combination	Support 1	Support 2
Max Upward from all Load Conditions	2.130	2.130
Max Upward from Load Combinations	2.130	2.130
Max Upward from Load Cases	1.140	1.140
D Only	0.990	0.990
+D+Lr	1.830	1.830
+D+S	2.130	2.130
+D+0.750Lr	1.620	1.620
+D+0.750S	1.845	1.845
+0.60D	0.594	0.594
Lr Only	0.840	0.840
S Only	1.140	1.140

Wood Column

Project File: Ogden Community Services Building.ec6

LIC# : KW-06015170, Build:20.25.02.26

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Opening 3 Post

Code References

Calculations per NDS 2018, IBC 2021, SDPWS 2021
 Load Combinations Used : IBC 2021

General Information

Analysis Method	Allowable Stress Design			Wood Section Name	2-2x6	
End Fixities	Top & Bottom Pinned			Wood Grading/Manuf.	Graded Lumber	
Overall Column Height	10 ft			Wood Member Type	Sawn	
(Used for non-slender calculations)						
Wood Species	Douglas Fir-Larch			Exact Width	3.0 in	Allow Stress Modification Factors
Wood Grade	No.2			Exact Depth	5.50 in	
Fb +	900.0 psi	Fv	180.0 psi	Area	16.50 in^2	Cf or Cv for Bending 1.30
Fb -	900.0 psi	Ft	575.0 psi	Ix	41.594 in^4	Cf or Cv for Compression 1.10
Fc - Prll	1,350.0 psi	Density	31.210 pcf	Iy	12.375 in^4	Cf or Cv for Tension 1.30
Fc - Perp	625.0 psi					Cm : Wet Use Factor 1.0
						Ct : Temperature Fact 1.0
E : Modulus of Elasticity . . .	x-x Bending	y-y Bending	Axial			Cfu : Flat Use Factor 1.0
	Basic	1,600.0	1,600.0	1,600.0 ksi		Kf : Built-up columns 1.0
	Minimum	580.0	580.0			Use Cr : Repetitive ? No
				Column Buckling Condition:		
				ABOUT X-X Axis:	Lux = 10 ft, Kx = 1.0	
				ABOUT Y-Y Axis:	Luy = 10 ft, Ky = 1.0	

Applied Loads

Service loads entered. Load Factors will be applied for calculations.

Column self weight included : 35.761 lbs * Dead Load Factor

AXIAL LOADS . . .

Axial Load at 10.0 ft, Xecc = 1.750 in, D = 1.0, Lr = 0.850, S = 1.150 k

BENDING LOADS . . .

Lat. Uniform Load creating Mx-x, L = 0.01750 k/ft

DESIGN SUMMARY

Bending & Shear Check Results

PASS Max. Axial+Bending Stress Ratio =	0.8201 : 1	Maximum SERVICE Lateral Load Reactions . .	
Load Combination	+D+S	Top along Y-Y	0.08750 k
Governing NDS Formula	Comp + Myy, NDS Eq. 3.9-3	Bottom along Y-Y	0.08750 k
Location of max.above base	9.933 ft	Top along X-X	0.03135 k
At maximum location values are .		Bottom along X-X	0.03135 k
Applied Axial	2.186 k	Maximum SERVICE Load Lateral Deflections . . .	
Applied Mx	0.0 k-ft	Along Y-Y	0.05980 in at 5.034 ft above base
Applied My	-0.3114 k-ft	for load combination : +D+L	
Fc : Allowable	286.430 psi	Along X-X	-0.1771 in at 5.839 ft above base
		for load combination : +D+S	
PASS Maximum Shear Stress Ratio =	0.04419 : 1	Other Factors used to calculate allowable stresses . . .	
Load Combination	+D+L	Bending	Compression
Location of max.above base	0.0 ft	Tension	
Applied Design Shear	11.932 psi		
Allowable Shear	180.0 psi		

Load Combination Results

Load Combination	C _D	C _P	Maximum Axial + Bending Stress Ratios			Maximum Shear Ratios		
			Stress Ratio	Status	Location	Stress Ratio	Status	Location
D Only	0.900	0.212	0.3028	PASS	9.933 ft	0.008184	PASS	10.0 ft
+D+L	1.000	0.192	0.3448	PASS	6.779 ft	0.04419	PASS	0.0 ft
+D+Lr	1.250	0.155	0.5904	PASS	9.933 ft	0.01090	PASS	10.0 ft
+D+S	1.150	0.168	0.8201	PASS	9.933 ft	0.01377	PASS	10.0 ft
+D+0.750Lr+0.750L	1.250	0.155	0.4857	PASS	9.463 ft	0.02652	PASS	10.0 ft
+D+0.750L+0.750S	1.150	0.168	0.6394	PASS	9.933 ft	0.02882	PASS	10.0 ft
+0.60D	1.600	0.122	0.1299	PASS	0.0 ft	0.002762	PASS	10.0 ft

Wood Column

Project File: Ogden Community Services Building.ec6

LIC# : KW-06015170, Build:20.25.02.26

DUNN ASSOCIATES INC.

(c) ENERCALC, LLC 1982-2025

DESCRIPTION: Opening 3 Post

Maximum Reactions


Note: Only non-zero reactions are listed.

Load Combination	X-X Axis Reaction		k	Y-Y Axis Reaction		Axial Reaction	My - End Moments k-ft		Mx - End Moments	
	@ Base	@ Top		@ Base	@ Top	@ Base	@ Base	@ Top	@ Base	@ Top
D Only	-0.015	0.015				1.036				
+D+L	-0.015	0.015		0.088	0.088	1.036				
+D+Lr	-0.027	0.027				1.886				
+D+S	-0.031	0.031				2.186				
+D+0.750Lr+0.750L	-0.024	0.024		0.066	0.066	1.673				
+D+0.750L+0.750S	-0.027	0.027		0.066	0.066	1.898				
+0.60D	-0.009	0.009				0.621				
Lr Only	-0.012	0.012				0.850				
L Only				0.088	0.088					
S Only	-0.017	0.017				1.150				

Maximum Deflections for Load Combinations

Load Combination	Max. X-X Deflection	Distance	Max. Y-Y Deflection	Distance
D Only	-0.0824 in	5.839ft	0.000 in	0.000 ft
+D+L	-0.0824 in	5.839ft	0.060 in	5.034 ft
+D+Lr	-0.1524 in	5.839ft	0.000 in	0.000 ft
+D+S	-0.1771 in	5.839ft	0.000 in	0.000 ft
+D+0.750Lr+0.750L	-0.1349 in	5.839ft	0.045 in	5.034 ft
+D+0.750L+0.750S	-0.1534 in	5.839ft	0.045 in	5.034 ft
+0.60D	-0.0494 in	5.839ft	0.000 in	0.000 ft
Lr Only	-0.0700 in	5.839ft	0.000 in	0.000 ft
L Only	0.0000 in	0.000ft	0.060 in	5.034 ft
S Only	-0.0947 in	5.839ft	0.000 in	0.000 ft

Sketches





DUNN ASSOCIATES, INC
Consulting Structural Engineers

Title
OGDEN COMMUNITY SERVICES BUILDING



Sheet Number: O-14

Job Number: 240268

Date:

By: CF

OPENING 4



OPENING 4

LOADS FROM JOIST 4
JOIST 4

DL = 0.32 klf
LLr = 0.28 klf
SL = 0.40 klf

6" BLOCK, 135 pcf, (6" * 1' / 12" * 135 pcf * 4 ft height) = 270 plf additional DL

SPAN = 9'-4"

FOR BEAM, USE L8x6x1/2

FOR POSTS, USE HSS3.1/2x2.1/2x1/4

SEISMIC LOADS

$EQ = 0.4 S_{DS} W_p I_E$
 $EQ = 0.4 * 1.093 * 36 \text{ PSF} * 1.0 = 15.74 \text{ psf}$

$EQ = 0.4 * 1.093 * 15 \text{ PSF} * 1.0 = 6.56 \text{ psf}$




EQ JAMB

BARS AT 48" O.C., ADD'L TRIB TO JAMB = 2 ft
2 ft * 15.74 psf = 31.48 psf

WL = 22.41 psf C&C

WL JAMB

2 ft * 22.11 psf = 44.82 psf





Current Date: 3/11/2025 11:56 AM

Units system: English

File name: K:\2024\240268\Ram Elements\Tube Steel Analysis for opening 4.retx

Load data

Load Conditions

Condition	Description	Comb.	Category
D1	1.4DL	Yes	
D2	1.2DL+0.5Lr_or_S	Yes	
D3	1.2DL+1.6Lr_or_S	Yes	
D4	1.2DL+0.5W_OOP	Yes	
D5	1.2DL+1.6Lr_or_S+0.5W_OOP	Yes	
D6	1.2DL+W_OOP	Yes	
D7	1.2DL+0.5Lr_or_S+W_OOP	Yes	
D8	0.9DL+W_OOP	Yes	
D9	1.2DL+0.2Lr_or_S	Yes	
D10	1.4186DL+EQ_OOP	Yes	
D11	1.4186DL+0.2Lr_or_S+EQ_OOP	Yes	
D12	0.7DL+EQ_OOP	Yes	
S1	DL	Yes	
S2	DL+Lr_or_S	Yes	
S3	DL+0.75Lr_or_S	Yes	
S4	DL+0.6W_OOP	Yes	
S6	DL+0.75Lr_or_S+0.45W_OOP	Yes	
S7	0.6DL+0.6W_OOP	Yes	
S8	1.15302DL+0.7EQ_OOP	Yes	
S9	1.115DL+0.525EQ_OOP	Yes	
S10	DL+0.75Lr_or_S	Yes	
S11	1.115DL+0.75Lr_or_S+0.525EQ_OOP	Yes	
S12	0.44698DL+0.7EQ_OOP	Yes	

Glossary

Comb : Indicates if load condition is a load combination



Current Date: 3/11/2025 11:58 AM

Units system: English

File name: K:\2024\240268\Ram Elements\Tube Steel Analysis for opening 4.retx

Load data

Load Conditions

Condition	Description	Comb.	Category
DL	Dead Load. Assumed SDS=1.093 in LCs with EQ	No	DL
Lr_or_S	Roof Live Load or Snow Load	No	SNOW
EQ_OOP	Out of Plane Earthquake Positive/Negative	No	EQ
W_OOP	Out of Plane Wind Positive/Negative	No	WIND

Distributed force on members

Condition	Member	Dir1	Val1 [Kip/ft]	Val2 [Kip/ft]	Dist1 [ft]	%	Dist2 [ft]	%
DL	9	Y	-0.32	-0.32	0.00	Yes	100.00	Yes
		Y	-0.27	-0.27	0.00	Yes	100.00	Yes
Lr_or_S	9	Y	-0.40	-0.40	0.00	Yes	100.00	Yes
EQ_OOP	7	Z	-0.0315	-0.0315	0.00	No	9.00	No
	8	Z	-0.0315	-0.0315	0.00	No	9.00	No
	9	Z	-0.0252	-0.0252	0.00	No	9.00	No
	10	Z	-0.0151	-0.0151	0.00	Yes	100.00	Yes
	11	Z	-0.0315	-0.0315	0.00	Yes	100.00	Yes
	12	Z	-0.0416	-0.0416	0.00	No	9.00	No
W_OOP	7	Z	-0.0448	-0.0448	0.00	No	9.00	No
	8	Z	-0.0448	-0.0448	0.00	No	9.00	No
	9	Z	-0.056	-0.056	0.00	No	9.00	No
	10	Z	-0.0215	-0.0215	0.00	Yes	100.00	Yes
	11	Z	-0.0448	-0.0448	0.00	Yes	100.00	Yes
	12	Z	-0.0794	-0.0794	0.00	No	9.00	No

Self weight multipliers for load conditions

Condition	Description	Self weight multiplier			
		Comb.	MultX	MultY	MultZ
DL	Dead Load. Assumed SDS=1.093 in LCs with EQ	No	0.00	-1.00	0.00
Lr_or_S	Roof Live Load or Snow Load	No	0.00	0.00	0.00
EQ_OOP	Out of Plane Earthquake Positive/Negative	No	0.00	0.00	0.00
W_OOP	Out of Plane Wind Positive/Negative	No	0.00	0.00	0.00

Glossary


Comb : Indicates if load condition is a load combination



Current Date: 3/11/2025 12:02 PM

Units system: English

File name: K:\2024\240268\Ram Elements\Tube Steel Analysis for opening 4.retx






Current Date: 3/11/2025 12:02 PM

Units system: English

File name: K:\2024\240268\Ram Elements\Tube Steel Analysis for opening 4.retx








Current Date: 3/11/2025 12:03 PM

Units system: English

File name: K:\2024\240268\Ram Elements\Tube Steel Analysis for opening 4.retx






Current Date: 3/11/2025 12:03 PM

Units system: English

File name: K:\2024\240268\Ram Elements\Tube Steel Analysis for opening 4.retx





Current Date: 3/11/2025 12:04 PM

Units system: English

File name: K:\2024\240268\Ram Elements\Tube Steel Analysis for opening 4.retx

Load condition: DL=Dead Load. Assumed SDS=1.093 in LCs with EQ

Loads

■ Distributed user loads - Members





Current Date: 3/11/2025 12:05 PM


Units system: English

File name: K:\2024\240268\Ram Elements\Tube Steel Analysis for opening 4.retx

Load condition: Lr_or_S=Roof Live Load or Snow Load

Loads

■ Distributed user loads - Members





Current Date: 3/11/2025 12:05 PM


Units system: English

File name: K:\2024\240268\Ram Elements\Tube Steel Analysis for opening 4.retx

Load condition: EQ_OOP=Out of Plane Earthquake Positive/Negative

Loads

- Distributed user loads - Members
- Distributed area loads - Members





- Distributed user loads - Members
- Distributed area loads - Members





Current Date: 3/11/2025 12:06 PM

Units system: English


File name: K:\2024\240268\Ram Elements\Tube Steel Analysis for opening 4.ret

Analysis result

Nodes

Envelope for nodal reactions

Note.- Ic is the controlling load condition



Direction of positive forces and moments

Envelope of nodal reactions for :

S1=DL

S2=DL+Lr_or_S

S3=DL+0.75Lr_or_S

S4=DL+0.6W_OOP

S6=DL+0.75Lr_or_S+0.45W_OOP

S7=0.6DL+0.6W_OOP

S8=1.15302DL+0.7EQ_OOP

S9=1.115DL+0.525EQ_OOP

S10=DL+0.75Lr_or_S

S11=1.115DL+0.75Lr_or_S+0.525EQ_OOP

S12=0.44698DL+0.7EQ_OOP

Node		Forces						Moments					
		Fx Ic		Fy Ic		Fz Ic		Mx Ic		My Ic		Mz Ic	
		[Kip]		[Kip]		[Kip]		[Kip*ft]		[Kip*ft]		[Kip*ft]	
7	Max	-0.013	S1	4.676	S2	0.393	S4	0.00000	S1	0.00000	S1	0.00000	S1
	Min	-0.028	S11	1.285	S12	0.000	S1	0.00000	S1	0.00000	S1	0.00000	S1
8	Max	0.028	S11	4.676	S2	0.393	S4	0.00000	S1	0.00000	S1	0.00000	S1
	Min	0.013	S1	1.285	S12	0.000	S1	0.00000	S1	0.00000	S1	0.00000	S1
9	Max	-0.001	S12	0.000	S1	0.393	S4	0.00000	S1	0.00000	S1	0.00000	S1
	Min	-0.053	S2	0.000	S1	0.000	S2	0.00000	S1	0.00000	S1	0.00000	S1
10	Max	0.053	S2	0.000	S1	0.393	S4	0.00000	S1	0.00000	S1	0.00000	S1
	Min	0.001	S12	0.000	S1	0.000	S2	0.00000	S1	0.00000	S1	0.00000	S1



Current Date: 3/11/2025 12:07 PM

Units system: English

File name: K:\2024\240268\Ram Elements\Tube Steel Analysis for opening 4.ret

Steel Code Check Summary - Group by member

Load conditions to be included in design :

D1=1.4DL
 D2=1.2DL+0.5Lr_or_S
 D3=1.2DL+1.6Lr_or_S
 D4=1.2DL+0.5W_OOP
 D5=1.2DL+1.6Lr_or_S+0.5W_OOP
 D6=1.2DL+W_OOP
 D7=1.2DL+0.5Lr_or_S+W_OOP
 D8=0.9DL+W_OOP
 D9=1.2DL+0.2Lr_or_S
 D10=1.4186DL+EQ_OOP
 D11=1.4186DL+0.2Lr_or_S+EQ_OOP
 D12=0.7DL+EQ_OOP

Description	Section	Member	Ctrl Eq.	Ratio	Status	Reference
<u>Bottom Angle</u>	<i>L 6X6X5_16</i>	12	D7 at 50.00%	0.16	OK	
<u>Columns</u>	<i>HSS_RECT 3-1_2X1-1_2X1_4</i>	7	D7 at 44.44%	0.70	OK	
		8	D7 at 44.44%	0.70	OK	
<u>Top Angle</u>	<i>LU 8X6X1_2</i>	9	D5 at 50.00%	0.80	OK	



DUNN ASSOCIATES, INC
Consulting Structural Engineers

Title
OGDEN COMMUNITY SERVICES BUILDING

Sheet Number: O-28

Job Number: 240268

Date:

By: CF

OPENING 4 DESIGN NARRATIVE

OPENING IN MASONRY WALL: OPENING 4

ALTERATION LEVEL 2

PER IEBC 2021

SECTION 603


ALTERATION-LEVEL 2

603.1 Scope. INSIGHTS

Level 2 alterations include the addition or elimination of any door or window, the reconfiguration or extension of any system, or the installation of any additional equipment, and shall apply where the work area is equal to or less than 50 percent of the building area.

Exception: The movement or addition of nonfixed and movable fixtures, cases, racks, counters and partitions not over 5 feet 9 inches (1753 mm) in height shall not be considered a Level 2 alteration.

ADDITIONS OF WINDOWS AND DOORS, WORK AREA IS LESS THAN 50% OF BUILDING AREA



BASEMENT FLOOR: 4299 sq ft

MAIN FLOOR: 4299 sq ft

WORK AREA: 2158 sq ft

TOTAL AREA = 8598 sq ft

$2158 / 8598 = 25\%$ OF BUILDING AREA IS WORK AREA

FOR LEVEL 2 ALTERNATIONS

[805] 805.3 Existing structural elements resisting lateral loads. INSIGHTS

Except as permitted by Section 805.4, where the alteration increases design lateral loads, or where the alteration results in prohibited structural irregularity as defined in ASCE 7, or where the alteration decreases the capacity of any existing lateral load-carrying structural element, the structure of the altered building or structure shall meet the requirements of Sections 1609 and 1613 of the *International Building Code*. **Reduced seismic forces shall be permitted.**

Exception: Any existing lateral load-carrying structural element whose demand-capacity ratio with the alteration considered is not more than 10 percent greater than its demand-capacity ratio with the alteration ignored shall be permitted to remain unaltered. For purposes of calculating demand-capacity ratios, the demand shall consider applicable load combinations with design lateral loads or forces in accordance with Sections 1609 and 1613 of the *International Building Code*. Reduced seismic forces shall be permitted. For purposes of this exception, comparisons of demand-capacity ratios and calculation of design lateral loads, forces and capacities shall account for the cumulative effects of additions and alterations since original construction.



DUNN ASSOCIATES, INC
Consulting Structural Engineers

Title
OGDEN COMMUNITY SERVICES BUILDING

Sheet Number: O-30

Job Number: 240268

Date:

By: CF

OPENING 4 DESIGN NARRATIVE

[bs] 304.3.2 Compliance with reduced seismic forces.

Where seismic evaluation and design is permitted to use reduced seismic forces, the criteria used shall be in accordance with one of the following:

1. The *International Building Code* using 75 percent of the prescribed forces. Values of R , Ω_0 and C_d used for analysis shall be as specified in Section 304.3.1 of this code.
2. Structures or portions of structures that comply with the requirements of the applicable chapter in Appendix A as specified in Items 2.1 through 2.4 and subject to the limitations of the respective Appendix A chapters shall be deemed to comply with this section.
 - 2.1. The seismic evaluation and design of unreinforced masonry bearing wall buildings in *Risk Category* I or II are permitted to be based on the procedures specified in Appendix Chapter A1.
 - 2.2. Seismic evaluation and design of the wall anchorage system in reinforced concrete and reinforced masonry wall buildings with flexible diaphragms in *Risk Category* I or II are permitted to be based on the procedures specified in Chapter A2.
 - 2.3. Seismic evaluation and design of cripple walls and sill plate anchorage in residential buildings of light-frame wood construction in *Risk Category* I or II are permitted to be based on the procedures specified in Chapter A3.
 - 2.4. Seismic evaluation and design of soft, weak or open-front wall conditions in multiple-unit residential buildings of wood construction in *Risk Category* I or II are permitted to be based on the procedures specified in Chapter A4.
3. ASCE 41, using the performance objective in Table 304.3.2 for the applicable *risk category*.


[bs] 304.3.1 Compliance with full seismic forces.

Where compliance requires the use of full seismic forces, the criteria shall be in accordance with one of the following:

1. One-hundred percent of the values in the *International Building Code*. Where the existing seismic force-resisting system is a type that can be designated as "Ordinary," values of R , Ω_0 and C_d used for analysis in accordance with Chapter 16 of the *International Building Code* shall be those specified for structural systems classified as "Ordinary" in accordance with Table 12.2-1 of ASCE 7, unless it can be demonstrated that the structural system will provide performance equivalent to that of a "Detailed," "Intermediate" or "Special" system.

DEFINED AS INTERMEDIATE WALL

PER TMS 7.3.2.5: Intermediate reinforced shear walls shall comply with the requirements of section 8.3. Reinforcement detailing shall also comply with the requirements of section 7.3.2.3.1, except that the spacing of vertical reinforcement shall not exceed 48 in.



6" CMU BLOCK
#6 AT 48" O.C. VERT
#5 AT 48" O.C. HORIZ

PER 7.3.2.5, VERTICAL REINFORCEMENT DOES NOT EXCEED 48" O.C.

PER 7.3.2.3.1, VERT REINF. MUST MEET 0.2 in² in area not spaced more than 120 in.
0.44 in² AT 48" O.C. meets this.

PER 7.3.2.3.1, HORIZ REINF. MUST MEET 0.2 in² in area not spaced more than 120 in.
0.31 in² AT 48" O.C. meets this.

MASONRY

1. ALL MASONRY SHALL BE REINFORCED WITH BOTH HORIZONTAL AND VERTICAL REINFORCEMENT. ALL BLOCK CELLS OR BRICK CAVITIES WITH REINFORCEMENT SHALL BE GROUTED FULL USING CONCRETE GROUT, 2000 PSI. CELLS SHALL BE ALIGNED TO PRESERVE UNOBSTRUCTED VERTICAL CAVITIES OF 4" X 5" MINIMUM.
2. ADDITIONAL VERTICAL BARS OF MATCHING WALL REINFORCING SHALL BE PLACED AT CORNERS AND JAMBS OF ALL OPENINGS.
3. HORIZONTAL BARS SHALL BE PLACED IN BOND BEAMS FILLED WITH GROUT AT THE TOP OF ALL WALLS AND AT 48" O.C. MAXIMUM BETWEEN TOP OF WALL AND FOUNDATION. BOND BEAM UNITS SHALL CONTINUE UNINTERRUPTED AROUND ALL CORNERS AND WALL INTERSECTIONS. WHERE STRUCTURAL STEEL COLUMNS OR BEAMS INTERRUPT THE CONTINUITY OF A BOND BEAM DOWELS MATCHING BOND BEAM REINFORCEMENT SHALL BE WELDED TO THE STRUCTURAL STEEL TO PROVIDE CONTINUITY. PLACE 3 GAUGE DUNE-WALL (OR EQUAL) AT 16" O.C. AS SHOWN ON DRAWINGS. REFER TO TYPICAL DETAILS FOR CORNER BARS.

MASONRY GSN ON DRAWINGS LISTS THAT ADD'L VERT BARS REQ NEXT TO OPENINGS AND CORNERS



DUNN ASSOCIATES, INC
Consulting Structural Engineers

Title
OGDEN COMMUNITY SERVICES BUILDING

Sheet Number: **O-31**

Job Number: 240268

Date:

By: CF

OPENING 4 DESIGN NARRATIVE

WALL ANALYZED AS INTERMEDIATE WALL WITH 75% OF SEISMIC FORCES

178 PLF, CALCULATION BELOW FOR MASS TRIBUTARY TO SHEAR WALL

Vertical grout spacing, in.(mm)		Mortar bedding	Table 3-6-in. (152-mm) Single Wythe Wall Weights						
			Wall weight, lb/ft ² (kg/m ²) for concrete densities, lb/ft ³ (kg/m ³) of:						
Units			85 (1,362)	95 (1,522)	105 (1,682)	115 (1,842)	125 (2,003)	135 (2,163)	
Hollow	No grout	Face shell	20 (98)	22 (108)	24 (117)	26 (127)	28 (137)	30 (147)	
Hollow	No grout	Full	20 (98)	22 (108)	24 (117)	26 (127)	28 (137)	31 (151)	
Solid	No grout	Full	42 (205)	46 (225)	50 (244)	55 (269)	59 (288)	63 (308)	
Hollow	8 (203)	Full	53 (259)	56 (274)	58 (283)	60 (293)	62 (303)	64 (313)	
Hollow	16 (406)	Face shell	37 (181)	39 (191)	41 (200)	43 (210)	45 (220)	47 (230)	
Hollow	24 (610)	Face shell	31 (151)	33 (161)	35 (171)	37 (181)	39 (191)	41 (200)	
Hollow	32 (812)	Face shell	28 (137)	30 (147)	32 (156)	34 (166)	37 (181)	39 (191)	
Hollow	40 (1,016)	Face shell	26 (127)	29 (142)	31 (151)	33 (161)	35 (171)	37 (181)	
Hollow	48 (1,219)	Face shell	25 (122)	27 (132)	30 (147)	32 (156)	34 (166)	36 (176)	

Seismic Analysis

$S_{ds} = 1.093$ g
 $R = 3.5$ For Intermediate Masonry Shear Walls
 $C_s = 0.312$


Roof Area = 2110 ft²
 $DL_{ROOF} = 20$ psf

Roof Weight
42200 lb

$DL_{WALL} = 36$ psf
Wall Height = 9 ft
Wall Length = 70.75 ft
Trib Height = 4.5 ft²

Wall Weight
11462 lb
53662 lb Total

$V = 758$ plf over 70.75 ft Wall length
 $0.75 \cdot C_s \cdot V = 178$ plf over 70.75 ft Wall length





Current Date: 2/21/2025 10:16 AM

Units system: English

File name: K:\2024\240268\Ram Elements\Masonry Opening 4 - Full Wall Design - Pre Opening.msw

Design Results

Masonry wall

MASONRY SHEAR WALL (INTERMEDIATE) DESIGN ANALYSIS - EXISTING CONDITION

General Information

Global status : Warnings in design

Design code : TMS 402-16 ASD

Materials:

Material : CMU 2.0-60
 Mortar type : Port/Mort - M/S
 Grouting type : Partial grouting
 Mortar bed type : Full bed
 Masonry compression strength (F'_m) : 2 [Kip/in²]
 Steel tension strength (f_y) : 60 [Kip/in²]
 Steel allowable tension strength (F_s) : 32 [Kip/in²]
 Steel elasticity modulus (E_s) : 29000 [Kip/in²]
 Masonry elasticity modulus (E_m) : 1800 [Kip/in²]
 Masonry unit weight : 0.135 [Kip/ft³]

Seismic data:

Seismic design category : SDC D
 Response modification factor : 1.00
 Shear wall type : Intermediate

Geometry

Total height : 9.00 [ft]
 Total length : 70.75 [ft]
 Foundation type : Continuous
 Wall bottom restraint : Pinned
 Column bottom restraint : Fixed
 Rigidity elements : None

Number of stories: 1

Story	Story height [ft]	Wall thickness [in]	Effective unit weight [Kip/ft ³]
1	9.00	5.63	0.08

Openings:

Reference	X Coordinate [ft]	Y Coordinate [ft]	Width [ft]	Height [ft]
Lower left	4.67	3.83	8.00	3.17
Lower left	19.33	3.83	8.00	3.17
Lower left	30.67	3.83	8.00	3.17
Lower left	41.25	0.00	9.50	7.17

Load Conditions

ID	Comb.	Category	Description
DL	No	DL	Dead Load
LLr	No	LLR	Live Load Roof
SL	No	SNOW	Snow Load
EQpos	No	EQ	Seismic In Plane Pos
EQneg	No	EQ	Seismic In Plane Neg
H	No	EARTH	Soil pressures
D1	Yes		1.4DL
D2	Yes		1.2DL+0.5LLr
D3	Yes		1.2DL+0.5SL
D4	Yes		1.2DL+1.6LLr
D5	Yes		1.2DL+1.6SL
D6	Yes		1.2DL+0.2SL
D7	Yes		1.4186DL+EQpos
D8	Yes		1.4186DL+EQneg
D9	Yes		1.4186DL+0.2SL+EQpos
D10	Yes		1.4186DL+0.2SL+EQneg
D11	Yes		1.1186DL+EQpos
D12	Yes		1.1186DL+EQneg
S1	Yes		DL
S2	Yes		DL+LLr
S3	Yes		DL+SL
S4	Yes		DL+0.75LLr
S5	Yes		DL+0.75SL
S6	Yes		1.15302DL+0.7EQpos
S7	Yes		1.15302DL+0.7EQneg
S8	Yes		1.114765DL+0.525EQpos
S9	Yes		1.11477DL+0.525EQneg
S10	Yes		DL+0.75SL
S11	Yes		1.11477DL+0.75SL+0.525EQpos
S12	Yes		1.11477DL+0.75SL+0.525EQneg
S13	Yes		0.44698DL+0.7EQpos
S14	Yes		0.44698DL+0.7EQneg
D13	Yes		1.4186DL+EQpos
D14	Yes		1.4186DL+EQneg
D15	Yes		1.4186DL+0.2SL+EQpos
D16	Yes		1.4186DL+0.2SL+EQneg
D17	Yes		1.1186DL+EQpos
D18	Yes		1.1186DL+EQneg
D19	Yes		1.1186DL+EQpos+1.6H
D20	Yes		1.1186DL+EQneg+1.6H
D21	Yes		1.1186DL+EQpos+0.9H
D22	Yes		1.1186DL+EQneg+0.9H
S15	Yes		DL
S16	Yes		DL+LLr
S17	Yes		DL+SL
S18	Yes		DL+0.75LLr
S19	Yes		DL+0.75SL
S20	Yes		1.15302DL+0.7EQpos
S21	Yes		1.15302DL+0.7EQneg
S22	Yes		1.15302DL+0.7EQpos+H
S23	Yes		1.15302DL+0.7EQneg+H
S24	Yes		1.15302DL+0.7EQpos+0.6H
S25	Yes		1.15302DL+0.7EQneg+0.6H
S26	Yes		1.11477DL+0.525EQpos
S27	Yes		1.11477DL+0.525EQneg
S28	Yes		DL+0.75SL
S29	Yes		1.11477DL+0.75SL+0.525EQpos
S30	Yes		1.11477DL+0.75SL+0.525EQneg
S31	Yes		0.44698DL+0.7EQpos
S32	Yes		0.44698DL+0.7EQneg

S33	Yes	$0.44698DL+0.7EQ_{pos}+H$
S34	Yes	$0.44698DL+0.7EQ_{neg}+H$
S35	Yes	$0.44698DL+0.7EQ_{pos}+0.6H$
S36	Yes	$0.44698DL+0.7EQ_{neg}+0.6H$

Loads

Distributed loads:

Consider self weight : DL


Story	Condition	Direction	Magnitude [Kip/ft]	Eccentricity [ft]
1	DL	Vertical	0.19	0.00
1	LLr	Vertical	0.16	0.00
1	SL	Vertical	0.22	0.00
1	EQpos	Horizontal	0.18	0.00
1	EQneg	Horizontal	-0.18	0.00

Out-of-plane loads:

Story	Condition	Magnitude [Kip/ft2]
1	H	0.02
Parapet	H	0.02

Bearing Wall Design

Status : OK



Geometry

Level	Segment	X Coordinate [ft]	Y Coordinate [ft]	Width [ft]	Height [ft]
0	1	0.00	0.00	4.67	3.83
	2	4.67	0.00	8.00	3.83
	3	12.67	0.00	6.67	3.83
	4	19.33	0.00	8.00	3.83
	5	27.33	0.00	3.33	3.83
	6	30.67	0.00	8.00	3.83
	7	38.67	0.00	2.58	3.83
	8	50.75	0.00	20.00	3.83
	9	0.00	3.83	4.67	3.17
	10	12.67	3.83	6.67	3.17
	11	27.33	3.83	3.33	3.17
	12	38.67	3.83	2.58	3.17
	13	50.75	3.83	20.00	3.17
	14	0.00	7.00	4.67	2.00
	15	4.67	7.00	8.00	2.00


16	12.67	7.00	6.67	2.00
17	19.33	7.00	8.00	2.00
18	27.33	7.00	3.33	2.00
19	30.67	7.00	8.00	2.00
20	38.67	7.00	2.58	2.00
21	41.25	7.00	9.50	2.00
22	50.75	7.00	20.00	2.00

Vertical reinforcement



Segment	Bars	Spacing [in]	Ld [in]
1	2-#6	48.00	63.77
2	2-#6	48.00	63.77
3	2-#6	48.00	63.77
4	2-#6	48.00	63.77
5	1-#6	48.00	63.77
6	2-#6	48.00	63.77
7	1-#6	48.00	63.77
8	5-#6	48.00	63.77
9	2-#6	48.00	63.77
10	2-#6	48.00	63.77
11	1-#6	48.00	63.77
12	1-#6	48.00	63.77
13	5-#6	48.00	63.77
14	2-#6	48.00	63.77
15	2-#6	48.00	63.77
16	2-#6	48.00	63.77
17	2-#6	48.00	63.77
18	1-#6	48.00	63.77
19	2-#6	48.00	63.77
20	1-#6	48.00	63.77
21	3-#6	48.00	63.77
22	5-#6	48.00	63.77

Combined axial flexure








Segment	Condition	P [Kip]	M [Kip*ft]	Ma [Kip*ft]	Ratio	
1	D19(Max)	1.91	-1.56	3.49	0.45	
2	D19(Top)	2.65	-1.53	5.93	0.26	
3	D19(Top)	4.01	-2.66	5.09	0.52	
4	D20(Top)	2.23	-1.87	5.90	0.32	
5	D19(Top)	3.14	-1.75	2.63	0.66	
6	D20(Max)	2.91	-1.47	5.95	0.25	
7	D20(Top)	3.99	-1.34	2.17	0.62	
8	D20(Top)	9.88	-5.45	15.09	0.36	
9	D19(Bottom)	2.64	-1.95	3.55	0.55	
10	D20(Max)	5.15	-3.12	5.18	0.60	
11	D20(Max)	3.77	-2.05	2.68	0.76	
12	D20(Bottom)	3.61	-1.36	2.13	0.64	
13	D20(Max)	8.93	-5.98	15.02	0.40	
14	D19(Max)	2.00	-1.17	3.50	0.33	
15	D19(Max)	2.59	-0.73	5.93	0.12	
16	D20(Bottom)	4.17	-1.99	5.10	0.39	
17	D20(Max)	2.90	-1.20	5.95	0.20	
18	D20(Bottom)	3.28	-1.22	2.64	0.46	
19	D19(Max)	2.18	-0.79	5.90	0.13	

20	D19(Max)	3.51	-1.02	2.13	0.48	
21	D19(Max)	2.86	-0.57	7.02	0.08	
22	D20(Bottom)	6.79	-4.28	14.85	0.29	

Interaction diagrams, P vs. M



Axial compression

Segment	Condition	P [Kip]	Pa [Kip]	Ratio	
1	D5(Bottom)	6.96	74.94	0.09	
2	D5(Bottom)	6.51	128.47	0.05	
3	D5(Bottom)	11.11	107.06	0.10	
4	D5(Bottom)	8.26	128.47	0.06	
5	D5(Top)	7.77	40.82	0.19	
6	D5(Bottom)	14.73	128.47	0.11	
7	D5(Top)	8.69	31.64	0.27	
8	D5(Bottom)	22.37	321.18	0.07	
9	D5(Bottom)	6.38	74.94	0.09	
10	D5(Bottom)	10.71	107.06	0.10	
11	D5(Bottom)	8.09	40.82	0.20	
12	D5(Bottom)	8.05	31.64	0.25	
13	D5(Bottom)	19.04	321.18	0.06	
14	D5(Bottom)	5.02	74.94	0.07	
15	D5(Bottom)	6.44	128.47	0.05	
16	D5(Bottom)	9.83	107.06	0.09	
17	D5(Bottom)	7.00	128.47	0.05	
18	D5(Bottom)	7.76	40.82	0.19	
19	D5(Top)	9.78	128.47	0.08	
20	D5(Bottom)	8.04	31.64	0.25	
21	D5(Top)	8.89	152.56	0.06	
22	D5(Bottom)	16.28	321.18	0.05	

Axial tension

Segment	Condition	ft [Kip/in ²]	Fs [Kip/in ²]	Ratio	
1	D1(Top)	0.00	32.00	0.00	
2	D1(Top)	0.00	32.00	0.00	
3	D1(Top)	0.00	32.00	0.00	
4	D1(Top)	0.00	32.00	0.00	
5	D1(Top)	0.00	32.00	0.00	
6	D1(Top)	0.00	32.00	0.00	
7	D1(Top)	0.00	32.00	0.00	
8	D1(Top)	0.00	32.00	0.00	
9	D1(Top)	0.00	32.00	0.00	
10	D1(Top)	0.00	32.00	0.00	
11	D1(Top)	0.00	32.00	0.00	
12	D1(Top)	0.00	32.00	0.00	
13	D1(Top)	0.00	32.00	0.00	
14	D1(Top)	0.00	32.00	0.00	
15	D1(Top)	0.00	32.00	0.00	
16	D1(Top)	0.00	32.00	0.00	
17	D1(Top)	0.00	32.00	0.00	
18	D1(Top)	0.00	32.00	0.00	
19	D1(Top)	0.00	32.00	0.00	
20	D1(Top)	0.00	32.00	0.00	
21	D1(Top)	0.00	32.00	0.00	
22	D1(Top)	0.00	32.00	0.00	

Shear


Segment	Condition	fv [Kip/in ²]	Fv [Kip/in ²]	Ratio	
1	D19(Bottom)	0.005	0.093	0.05	
2	D19(Bottom)	0.004	0.092	0.04	
3	D19(Bottom)	0.006	0.095	0.06	
4	D20(Bottom)	0.004	0.092	0.04	
5	D19(Bottom)	0.006	0.095	0.07	
6	D20(Bottom)	0.005	0.090	0.05	
7	D20(Bottom)	0.006	0.091	0.06	
8	D20(Bottom)	0.004	0.094	0.04	
9	D19(Top)	0.002	0.054	0.04	
10	D20(Top)	0.002	0.055	0.04	
11	D20(Top)	0.003	0.058	0.05	
12	D20(Top)	0.002	0.060	0.04	
13	D20(Top)	0.002	0.053	0.03	
14	D19(Top)	0.005	0.061	0.08	
15	D19(Top)	0.002	0.065	0.03	
16	D19(Top)	0.005	0.060	0.08	
17	D19(Top)	0.003	0.066	0.05	
18	D19(Top)	0.006	0.060	0.10	
19	D19(Max)	0.004	0.052	0.07	
20	D19(Bottom)	0.002	0.060	0.04	
21	D20(Top)	0.003	0.062	0.05	
22	D20(Top)	0.004	0.060	0.06	

Shear Wall Design

Status : Warnings in design

- Invalid wall type for the seismic design category, TMS 402-16 ASD, 7.3.2, 7.4.1 (Segment 1)

PER TMS 2016 AND IBC 2021,
EXISTING WALL REINFORCEMENT
PROVIDES PERFORMANCE OF
INTERMEDIATE WALL



Geometry

Level	Segment	X Coordinate [ft]	Y Coordinate [ft]	Width [ft]	Height [ft]
0	1	0.00	0.00	41.25	3.83
	2	50.75	0.00	20.00	3.83
	3	0.00	3.83	4.67	3.17
	4	12.67	3.83	6.67	3.17
	5	27.33	3.83	3.33	3.17
	6	38.67	3.83	2.58	3.17
	7	50.75	3.83	20.00	3.17
	8	0.00	7.00	70.75	2.00

Reinforcement


Segment	Vertical reinforcement			Horizontal reinforcement		
	Bars	Spacing [in]	Ld [in]	Bars	Spacing [in]	Ld [in]
1	2-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77
	1-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77
	1-#6	48.00	63.77	1-#6	48.00	63.77
2	5-#6	48.00	63.77	1-#6	48.00	63.77
3	2-#6	48.00	63.77	1-#6	48.00	63.77
4	2-#6	48.00	63.77	1-#6	48.00	63.77
5	1-#6	48.00	63.77	1-#6	48.00	63.77
6	1-#6	48.00	63.77	1-#6	48.00	63.77
7	5-#6	48.00	63.77	1-#6	48.00	63.77
8	2-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77
	1-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77
	1-#6	48.00	63.77	1-#6	48.00	63.77
	3-#6	48.00	63.77	1-#6	48.00	63.77
	5-#6	48.00	63.77	1-#6	48.00	63.77

Combined axial flexure


Segment	Condition	P [Kip]	M [Kip*ft]	Ma [Kip*ft]	Ratio
1	D9(Bottom)	29.82	-88.68	2721.19	0.03
2	D22(Bottom)	12.47	49.21	481.33	0.10
3	D9(Bottom)	3.86	-6.63	64.55	0.10
4	D22(Bottom)	5.15	9.23	72.16	0.13
5	S36(Bottom)	1.50	2.50	3.63	0.69
6	S36(Bottom)	1.41	1.70	2.95	0.58
7	D10(Bottom)	13.05	36.72	485.98	0.08
8	D22(Bottom)	20.71	25.87	5727.37	0.00

Interaction diagrams, P vs. M


P vs. M (Segment 1)




P vs. M (Segment 2)




P vs. M (Segment 3)




P vs. M (Segment 4)





P vs. M (Segment 5)



P vs. M (Segment 6)





Axial compression

Segment	Condition	P [Kip]	Pa [Kip]	Ratio	
1	D5(Bottom)	40.09	641.93	0.06	
2	D5(Bottom)	22.37	303.92	0.07	
3	D5(Bottom)	6.38	78.54	0.08	
4	D5(Bottom)	10.71	103.71	0.10	
5	D5(Bottom)	8.09	52.19	0.15	
6	D5(Bottom)	8.05	42.01	0.19	
7	D5(Bottom)	19.04	303.92	0.06	
8	D5(Bottom)	47.12	1097.01	0.04	

Axial tension

Segment	Condition	ft [Kip/in2]	Fs [Kip/in2]	Ratio	
1	D1(Top)	0.00	32.00	0.00	
2	D1(Top)	0.00	32.00	0.00	
3	D1(Top)	0.00	32.00	0.00	
4	D1(Top)	0.00	32.00	0.00	
5	D1(Top)	0.00	32.00	0.00	
6	D1(Top)	0.00	32.00	0.00	
7	D1(Top)	0.00	32.00	0.00	
8	D1(Top)	0.00	32.00	0.00	

Shear

SHEAR WALL DESIGN - EXISTING CONDITION

Segment	Condition	fv [Kip/in2]	Fv [Kip/in2]	Ratio	
1	D16(Bottom)	0.006	0.105	0.05	
2	D15(Bottom)	0.009	0.103	0.09	
3	D10(Top)	0.012	0.100	0.12	
4	D11(Bottom)	0.015	0.096	0.15	
5	D21(Bottom)	0.016	0.094	0.17	


6	D16(Bottom)	0.022	0.097	0.23	
7	D15(Top)	0.009	0.105	0.09	
8	D22(Bottom)	0.005	0.104	0.05	

Shear friction

Segment	Condition	ff [Kip/in ²]	Ff [Kip/in ²]	Ratio	
1	D16(Top)	0.006	0.127	0.04	
2	D15(Top)	0.009	0.118	0.08	

Lintel Design

Status : OK



Geometry

Lintel	X Coordinate [ft]	Y Coordinate [ft]	Length [ft]	Depth [in]
1	4.67	3.83	8.00	24.00
2	19.33	3.83	8.00	24.00
3	30.67	3.83	8.00	24.00
4	41.25	0.00	9.50	22.00


Reinforcement

Lintel	Top long. reinforcement		Bottom long. reinforcement		Transverse reinforcement		Ld [in]
	Bars	Extent [in]	Bars	Extent [in]	Bars	Spacing [in]	
1	1-#5	0.00	1-#5	6.00	--	0.00	0.00
2	1-#5	0.00	1-#5	5.50	--	0.00	0.00
3	1-#5	0.00	1-#5	6.50	--	0.00	0.00
4	1-#5	0.00	1-#5	12.50	--	0.00	0.00


Bending

Lintel	Condition	M [Kip*ft]	Ma [Kip*ft]	Ratio	
1	D5(Bottom)	-3.46	16.45	0.21	
2	D5(Bottom)	-2.96	16.45	0.18	
3	D5(Bottom)	-3.27	16.45	0.20	
4	D5(Top)	5.35	14.87	0.36	

Shear

Lintel	Condition	f_v [Kip/in ²]	F_v [Kip/in ²]	Ratio	
1	D5(Top)	0.021	0.050	0.41	
2	D5(Top)	0.025	0.050	0.50	
3	D5(Bottom)	0.028	0.050	0.56	
4	D5(Bottom)	0.037	0.050	0.73	

Deflection

Lintel	Condition	δ_s [in]	δ_{max} [in]	Ratio	
1		0.00	0.00	0.00	
2		0.00	0.00	0.00	
3		0.00	0.00	0.00	
4		0.00	0.00	0.00	

Notes

- * P = Axial load
- * Pa = Allowable compressive force due to axial load.
- * M = Moment at the section under consideration.
- * Ma = Wall allowable moment due to axial force or lintel pure flexure allowable moment
- * fa = Calculated compressive stress due to axial load only
- * fb = Calculated compressive stress due to axial flexure only
- * ft = Calculated axial tension
- * Fa = Allowable compressive stress due to axial load only
- * Fb = Allowable compressive stress due to axial flexure only
- * fv = Calculated shear stress
- * Fs = Allowable tensile or compressive stress
- * Fv = Allowable shear stress
- * ld = Embedment length
- * As = Effective cross sectional area of reinforcement
- * δ_s = Calculated deflection
- * δ_{max} = Maximum allowable deflection



Current Date: 2/21/2025 10:15 AM

Units system: English

File name: K:\2024\240268\Ram Elements\Masonry Opening 4 - Full Wall Design.msw

Design Results

Masonry wall

MASONRY SHEAR WALL (INTERMEDIATE) DESIGN ANALYSIS - POST OPENING INSTALLATION

General Information

Global status : Warnings in design

Design code : TMS 402-16 ASD

Materials:

Material : CMU 2.0-60
 Mortar type : Port/Mort - M/S
 Grouting type : Partial grouting
 Mortar bed type : Full bed
 Masonry compression strength (F'_m) : 2 [Kip/in²]
 Steel tension strength (f_y) : 60 [Kip/in²]
 Steel allowable tension strength (F_s) : 32 [Kip/in²]
 Steel elasticity modulus (E_s) : 29000 [Kip/in²]
 Masonry elasticity modulus (E_m) : 1800 [Kip/in²]
 Masonry unit weight : 0.135 [Kip/ft³]

Seismic data:

Seismic design category : SDC D
 Response modification factor : 1.00
 Shear wall type : Intermediate

Geometry

Total height : 9.00 [ft]
 Total length : 70.75 [ft]
 Foundation type : Continuous
 Wall bottom restraint : Pinned
 Column bottom restraint : Fixed
 Rigidity elements : None

Number of stories: 1

Story	Story height [ft]	Wall thickness [in]	Effective unit weight [Kip/ft ³]
1	9.00	5.63	0.08

Openings:

Reference	X Coordinate [ft]	Y Coordinate [ft]	Width [ft]	Height [ft]
Lower left	4.67	3.83	8.00	3.17
Lower left	19.33	3.83	8.00	3.17
Lower left	30.67	3.83	8.00	3.17
Lower left	41.25	0.00	9.50	7.17
Lower left	53.58	3.83	8.00	3.17

Load Conditions

ID	Comb.	Category	Description
DL	No	DL	Dead Load
LLr	No	LLR	Live Load Roof
SL	No	SNOW	Snow Load
EQpos	No	EQ	Seismic In Plane Pos
EQneg	No	EQ	Seismic In Plane Neg
H	No	EARTH	Soil pressures
D1	Yes		1.4DL
D2	Yes		1.2DL+0.5LLr
D3	Yes		1.2DL+0.5SL
D4	Yes		1.2DL+1.6LLr
D5	Yes		1.2DL+1.6SL
D6	Yes		1.2DL+0.2SL
D7	Yes		1.4186DL+EQpos
D8	Yes		1.4186DL+EQneg
D9	Yes		1.4186DL+0.2SL+EQpos
D10	Yes		1.4186DL+0.2SL+EQneg
D11	Yes		1.1186DL+EQpos
D12	Yes		1.1186DL+EQneg
S1	Yes		DL
S2	Yes		DL+LLr
S3	Yes		DL+SL
S4	Yes		DL+0.75LLr
S5	Yes		DL+0.75SL
S6	Yes		1.15302DL+0.7EQpos
S7	Yes		1.15302DL+0.7EQneg
S8	Yes		1.114765DL+0.525EQpos
S9	Yes		1.11477DL+0.525EQneg
S10	Yes		DL+0.75SL
S11	Yes		1.11477DL+0.75SL+0.525EQpos
S12	Yes		1.11477DL+0.75SL+0.525EQneg
S13	Yes		0.44698DL+0.7EQpos
S14	Yes		0.44698DL+0.7EQneg
D13	Yes		1.4186DL+EQpos
D14	Yes		1.4186DL+EQneg
D15	Yes		1.4186DL+0.2SL+EQpos
D16	Yes		1.4186DL+0.2SL+EQneg
D17	Yes		1.1186DL+EQpos
D18	Yes		1.1186DL+EQneg
D19	Yes		1.1186DL+EQpos+1.6H
D20	Yes		1.1186DL+EQneg+1.6H
D21	Yes		1.1186DL+EQpos+0.9H
D22	Yes		1.1186DL+EQneg+0.9H
S15	Yes		DL
S16	Yes		DL+LLr
S17	Yes		DL+SL
S18	Yes		DL+0.75LLr
S19	Yes		DL+0.75SL
S20	Yes		1.15302DL+0.7EQpos
S21	Yes		1.15302DL+0.7EQneg
S22	Yes		1.15302DL+0.7EQpos+H
S23	Yes		1.15302DL+0.7EQneg+H
S24	Yes		1.15302DL+0.7EQpos+0.6H
S25	Yes		1.15302DL+0.7EQneg+0.6H
S26	Yes		1.11477DL+0.525EQpos
S27	Yes		1.11477DL+0.525EQneg
S28	Yes		DL+0.75SL
S29	Yes		1.11477DL+0.75SL+0.525EQpos
S30	Yes		1.11477DL+0.75SL+0.525EQneg
S31	Yes		0.44698DL+0.7EQpos

S32	Yes	0.44698DL+0.7EQneg
S33	Yes	0.44698DL+0.7EQpos+H
S34	Yes	0.44698DL+0.7EQneg+H
S35	Yes	0.44698DL+0.7EQpos+0.6H
S36	Yes	0.44698DL+0.7EQneg+0.6H

Loads

Distributed loads:

Consider self weight : DL


Story	Condition	Direction	Magnitude [Kip/ft]	Eccentricity [ft]
1	DL	Vertical	0.19	0.00
1	LLr	Vertical	0.16	0.00
1	SL	Vertical	0.22	0.00
1	EQpos	Horizontal	0.18	0.00
1	EQneg	Horizontal	-0.18	0.00

Out-of-plane loads:

Story	Condition	Magnitude [Kip/ft2]
1	H	0.02
Parapet	H	0.02

Bearing Wall Design

Status : OK



Geometry

Level	Segment	X Coordinate [ft]	Y Coordinate [ft]	Width [ft]	Height [ft]
0	1	0.00	0.00	4.67	3.83
	2	4.67	0.00	8.00	3.83
	3	12.67	0.00	6.67	3.83
	4	19.33	0.00	8.00	3.83
	5	27.33	0.00	3.33	3.83
	6	30.67	0.00	8.00	3.83
	7	38.67	0.00	2.58	3.83
	8	50.75	0.00	2.83	3.83
	9	53.58	0.00	8.00	3.83
	10	61.58	0.00	9.17	3.83
	11	0.00	3.83	4.67	3.17
	12	12.67	3.83	6.67	3.17
	13	27.33	3.83	3.33	3.17
	14	38.67	3.83	2.58	3.17

15	50.75	3.83	2.83	3.17
16	61.58	3.83	9.17	3.17
17	0.00	7.00	4.67	2.00
18	4.67	7.00	8.00	2.00
19	12.67	7.00	6.67	2.00
20	19.33	7.00	8.00	2.00
21	27.33	7.00	3.33	2.00
22	30.67	7.00	8.00	2.00
23	38.67	7.00	2.58	2.00
24	41.25	7.00	9.50	2.00
25	50.75	7.00	2.83	2.00
26	53.58	7.00	8.00	2.00
27	61.58	7.00	9.17	2.00

Vertical reinforcement



Segment	Bars	Spacing [in]	Ld [in]
1	2-#6	48.00	63.77
2	2-#6	48.00	63.77
3	2-#6	48.00	63.77
4	2-#6	48.00	63.77
5	1-#6	48.00	63.77
6	2-#6	48.00	63.77
7	1-#6	48.00	63.77
8	1-#6	48.00	63.77
9	2-#6	48.00	63.77
10	3-#6	48.00	63.77
11	2-#6	48.00	63.77
12	2-#6	48.00	63.77
13	1-#6	48.00	63.77
14	1-#6	48.00	63.77
15	1-#6	48.00	63.77
16	3-#6	48.00	63.77
17	2-#6	48.00	63.77
18	2-#6	48.00	63.77
19	2-#6	48.00	63.77
20	2-#6	48.00	63.77
21	1-#6	48.00	63.77
22	2-#6	48.00	63.77
23	1-#6	48.00	63.77
24	3-#6	48.00	63.77
25	1-#6	48.00	63.77
26	2-#6	48.00	63.77
27	3-#6	48.00	63.77

Combined axial flexure

Segment	Condition	P [Kip]	M [Kip*ft]	Ma [Kip*ft]	Ratio	
1	D19(Max)	1.89	-1.56	3.49	0.45	
2	D19(Top)	2.62	-1.53	5.93	0.26	
3	D19(Max)	3.96	-2.66	5.08	0.52	
4	D20(Max)	2.26	-1.87	5.90	0.32	
5	D19(Max)	3.03	-1.75	2.62	0.67	
6	D20(Top)	2.91	-1.48	5.95	0.25	
7	D20(Top)	3.94	-1.36	2.16	0.63	
8	D19(Top)	4.11	-1.38	2.35	0.59	
9	D19(Top)	2.48	-1.33	5.92	0.22	

10	D20(Top)	4.19	-2.85	6.89	0.41	
11	D19(Bottom)	2.63	-1.95	3.55	0.55	
12	D20(Max)	5.17	-3.12	5.18	0.60	
13	D19(Bottom)	3.76	-2.06	2.68	0.77	
14	D20(Bottom)	3.54	-1.39	2.13	0.65	
15	D19(Max)	3.63	-1.42	2.31	0.61	
16	D20(Max)	4.32	-3.30	6.90	0.48	
17	D19(Bottom)	2.00	-1.17	3.50	0.33	
18	D19(Max)	2.39	-0.72	5.91	0.12	
19	D20(Max)	4.23	-1.99	5.10	0.39	
20	D19(Max)	2.91	-1.17	5.95	0.20	
21	D19(Bottom)	3.23	-1.23	2.64	0.47	
22	D19(Max)	1.75	-0.74	5.86	0.13	
23	D19(Max)	3.33	-1.08	2.11	0.51	
24	D19(Max)	3.18	-0.81	7.05	0.12	
25	D20(Max)	3.08	-0.96	2.27	0.42	
26	D19(Max)	1.90	-0.57	5.88	0.10	
27	D20(Bottom)	3.69	-2.28	6.85	0.33	

Interaction diagrams, P vs. M



Axial compression

Segment	Condition	P [Kip]	Pa [Kip]	Ratio	
1	D5(Bottom)	6.96	74.94	0.09	
2	D5(Bottom)	6.51	128.47	0.05	
3	D5(Bottom)	11.13	107.06	0.10	
4	D5(Bottom)	8.27	128.47	0.06	
5	D5(Top)	7.75	40.82	0.19	
6	D5(Bottom)	14.56	128.47	0.11	
7	D5(Top)	8.57	31.64	0.27	
8	D5(Top)	8.82	34.70	0.25	
9	D5(Bottom)	12.81	128.47	0.10	
10	D5(Bottom)	10.41	147.21	0.07	
11	D5(Bottom)	6.37	74.94	0.09	
12	D5(Bottom)	10.72	107.06	0.10	
13	D5(Bottom)	8.08	40.82	0.20	

14	D5(Bottom)	7.93	31.64	0.25	
15	D5(Bottom)	8.15	34.70	0.24	
16	D5(Bottom)	9.90	147.21	0.07	
17	D5(Bottom)	5.04	74.94	0.07	
18	D5(Bottom)	6.37	128.47	0.05	
19	D5(Bottom)	9.84	107.06	0.09	
20	D5(Bottom)	6.64	128.47	0.05	
21	D5(Bottom)	7.65	40.82	0.19	
22	D5(Top)	9.01	128.47	0.07	
23	D5(Bottom)	7.90	31.64	0.25	
24	D5(Top)	8.91	152.56	0.06	
25	D5(Bottom)	7.26	34.70	0.21	
26	D5(Top)	6.58	128.47	0.05	
27	D5(Bottom)	9.32	147.21	0.06	

Axial tension

Segment	Condition	ft [Kip/in ²]	Fs [Kip/in ²]	Ratio	
1	D1(Top)	0.00	32.00	0.00	
2	D1(Top)	0.00	32.00	0.00	
3	D1(Top)	0.00	32.00	0.00	
4	D1(Top)	0.00	32.00	0.00	
5	D1(Top)	0.00	32.00	0.00	
6	D1(Top)	0.00	32.00	0.00	
7	D1(Top)	0.00	32.00	0.00	
8	D1(Top)	0.00	32.00	0.00	
9	D1(Top)	0.00	32.00	0.00	
10	D1(Top)	0.00	32.00	0.00	
11	D1(Top)	0.00	32.00	0.00	
12	D1(Top)	0.00	32.00	0.00	
13	D1(Top)	0.00	32.00	0.00	
14	D1(Top)	0.00	32.00	0.00	
15	D1(Top)	0.00	32.00	0.00	
16	D1(Top)	0.00	32.00	0.00	
17	D1(Top)	0.00	32.00	0.00	
18	D1(Top)	0.00	32.00	0.00	
19	D1(Top)	0.00	32.00	0.00	
20	D1(Top)	0.00	32.00	0.00	
21	D1(Top)	0.00	32.00	0.00	
22	D1(Top)	0.00	32.00	0.00	
23	D1(Top)	0.00	32.00	0.00	
24	D1(Top)	0.00	32.00	0.00	
25	D1(Top)	0.00	32.00	0.00	
26	D1(Top)	0.00	32.00	0.00	
27	D1(Top)	0.00	32.00	0.00	

Shear


Segment	Condition	fv [Kip/in ²]	Fv [Kip/in ²]	Ratio	
1	D19(Bottom)	0.005	0.093	0.05	
2	D19(Bottom)	0.004	0.092	0.04	
3	D19(Bottom)	0.006	0.095	0.06	
4	D20(Bottom)	0.004	0.092	0.04	
5	D19(Bottom)	0.006	0.095	0.07	
6	D20(Bottom)	0.005	0.090	0.05	

7	D20(Bottom)	0.006	0.091	0.07	
8	D19(Bottom)	0.006	0.091	0.06	
9	D19(Max)	0.004	0.053	0.07	
10	D20(Bottom)	0.004	0.091	0.04	
11	D19(Top)	0.002	0.054	0.04	
12	D20(Top)	0.002	0.055	0.04	
13	D19(Top)	0.003	0.058	0.05	
14	D20(Top)	0.002	0.060	0.04	
15	D19(Top)	0.002	0.059	0.03	
16	D20(Top)	0.002	0.053	0.04	
17	D19(Top)	0.005	0.061	0.08	
18	D19(Max)	0.002	0.053	0.04	
19	D19(Top)	0.005	0.060	0.09	
20	D20(Top)	0.003	0.066	0.05	
21	D19(Top)	0.006	0.061	0.09	
22	D19(Max)	0.003	0.052	0.07	
23	D19(Bottom)	0.002	0.060	0.04	
24	D20(Top)	0.003	0.056	0.05	
25	D19(Top)	0.005	0.056	0.10	
26	D19(Max)	0.002	0.052	0.04	
27	D19(Top)	0.004	0.059	0.07	

Shear Wall Design

Status : Warnings in design
 - Invalid wall type for the seismic design category, TMS 402-16 ASD, 7.3.2, 7.4.1 (Segment 1)

PER TMS 2016 AND IEBC 2021,
 EXISTING WALL REINFORCEMENT
 PROVIDES PERFORMANCE OF
 INTERMEDIATE WALL



Geometry

Level	Segment	X Coordinate [ft]	Y Coordinate [ft]	Width [ft]	Height [ft]
0	1	0.00	0.00	41.25	3.83
	2	50.75	0.00	20.00	3.83
	3	0.00	3.83	4.67	3.17
	4	12.67	3.83	6.67	3.17
	5	27.33	3.83	3.33	3.17
	6	38.67	3.83	2.58	3.17
	7	50.75	3.83	2.83	3.17
	8	61.58	3.83	9.17	3.17
	9	0.00	7.00	70.75	2.00

Reinforcement

Segment	Vertical reinforcement			Horizontal reinforcement		
	Bars	Spacing [in]	Ld [in]	Bars	Spacing [in]	Ld [in]
1	2-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77


	1-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77
	1-#6	48.00	63.77	1-#6	48.00	63.77
2	1-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77
	3-#6	48.00	63.77	1-#6	48.00	63.77
3	2-#6	48.00	63.77	1-#6	48.00	63.77
4	2-#6	48.00	63.77	1-#6	48.00	63.77
5	1-#6	48.00	63.77	1-#6	48.00	63.77
6	1-#6	48.00	63.77	1-#6	48.00	63.77
7	1-#6	48.00	63.77	1-#6	48.00	63.77
8	3-#6	48.00	63.77	1-#6	48.00	63.77
9	2-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77
	1-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77
	1-#6	48.00	63.77	1-#6	48.00	63.77
	3-#6	48.00	63.77	1-#6	48.00	63.77
	1-#6	48.00	63.77	1-#6	48.00	63.77
	2-#6	48.00	63.77	1-#6	48.00	63.77
	3-#6	48.00	63.77	1-#6	48.00	63.77

Combined axial flexure


Segment	Condition	P [Kip]	M [Kip*ft]	Ma [Kip*ft]	Ratio	
1	D15(Bottom)	29.70	-91.54	2719.37	0.03	
2	D16(Bottom)	15.72	45.05	616.43	0.07	
3	D15(Bottom)	3.85	-6.70	64.53	0.10	
4	D22(Bottom)	5.17	9.65	72.22	0.13	
5	S36(Bottom)	1.53	2.81	3.66	0.77	
6	S32(Bottom)	1.39	2.01	2.92	0.69	
7	S36(Bottom)	1.55	1.28	3.28	0.39	
8	D16(Bottom)	6.42	18.80	157.75	0.12	
9	D12(Bottom)	20.71	25.87	6214.26	0.00	

Interaction diagrams, P vs. M


P vs. M (Segment 1)




P vs. M (Segment 2)




P vs. M (Segment 3)




P vs. M (Segment 4)






P vs. M (Segment 5)



P vs. M (Segment 6)





Axial compression

Segment	Condition	P [Kip]	Pa [Kip]	Ratio	
1	D5(Bottom)	39.98	641.93	0.06	
2	D5(Bottom)	21.39	313.16	0.07	
3	D5(Bottom)	6.37	78.54	0.08	
4	D5(Bottom)	10.72	103.71	0.10	
5	D5(Bottom)	8.08	52.19	0.15	
6	D5(Bottom)	7.93	42.01	0.19	
7	D5(Bottom)	8.15	46.07	0.18	
8	D5(Bottom)	9.90	145.49	0.07	
9	D5(Bottom)	47.12	1106.23	0.04	

Axial tension

Segment	Condition	ft [Kip/in2]	Fs [Kip/in2]	Ratio	
1	D1(Top)	0.00	32.00	0.00	
2	D1(Top)	0.00	32.00	0.00	
3	D1(Top)	0.00	32.00	0.00	
4	D1(Top)	0.00	32.00	0.00	
5	D1(Top)	0.00	32.00	0.00	
6	D1(Top)	0.00	32.00	0.00	
7	D1(Top)	0.00	32.00	0.00	
8	D1(Top)	0.00	32.00	0.00	
9	D1(Top)	0.00	32.00	0.00	

Shear**SHEAR WALL DESIGN - POST OPENING INSTALLATION**


Segment	Condition	f _v [Kip/in2]	F _v [Kip/in2]	Ratio	
1	D10(Bottom)	0.006	0.105	0.06	
2	D15(Bottom)	0.008	0.101	0.08	
3	D16(Top)	0.012	0.101	0.12	
4	D21(Bottom)	0.016	0.096	0.16	
5	D21(Bottom)	0.018	0.094	0.19	
6	D16(Bottom)	0.023	0.096	0.24	
7	D9(Bottom)	0.020	0.095	0.21	
8	D15(Bottom)	0.011	0.104	0.11	
9	D22(Bottom)	0.005	0.104	0.05	

Shear friction

Segment	Condition	f _f [Kip/in2]	F _f [Kip/in2]	Ratio	
1	D12(Top)	0.006	0.123	0.05	
2	D15(Top)	0.008	0.132	0.06	

Lintel Design

Status : OK

**Geometry**

Lintel	X Coordinate [ft]	Y Coordinate [ft]	Length [ft]	Depth [in]
1	4.67	3.83	8.00	24.00
2	19.33	3.83	8.00	24.00
3	30.67	3.83	8.00	24.00
4	41.25	0.00	9.50	22.00
5	53.58	3.83	8.00	24.00

Reinforcement

Lintel	Top long. reinforcement		Bottom long. reinforcement		Transverse reinforcement		Ld [in]
	Bars	Extent [in]	Bars	Extent [in]	Bars	Spacing [in]	
1	1-#5	0.00	1-#5	6.00	--	0.00	0.00
2	1-#5	0.00	1-#5	5.50	--	0.00	0.00
3	1-#5	0.00	1-#5	6.50	--	0.00	0.00
4	1-#5	0.00	1-#5	10.50	--	0.00	0.00
5	1-#5	0.00	1-#5	5.00	--	0.00	0.00

Bending

Lintel	Condition	M	Ma	Ratio	
		[Kip*ft]	[Kip*ft]		
1	D5(Bottom)	-3.46	16.45	0.21	
2	D5(Bottom)	-2.98	16.45	0.18	
3	D5(Bottom)	-3.23	16.45	0.20	
4	D5(Top)	4.52	14.87	0.30	
5	D5(Bottom)	-3.00	16.45	0.18	

Shear

Lintel	Condition	f _v	F _v	Ratio	
		[Kip/in ²]	[Kip/in ²]		
1	D5(Bottom)	0.021	0.050	0.41	
2	D5(Bottom)	0.025	0.050	0.50	
3	D5(Bottom)	0.028	0.050	0.56	
4	D5(Bottom)	0.036	0.050	0.72	
5	D5(Bottom)	0.021	0.050	0.42	

Deflection

Lintel	Condition	δ _s	δ _{max}	Ratio	
		[in]	[in]		
1		0.00	0.00	0.00	
2		0.00	0.00	0.00	
3		0.00	0.00	0.00	
4		0.00	0.00	0.00	
5		0.00	0.00	0.00	

Notes

- * P = Axial load
- * P_a = Allowable compressive force due to axial load.
- * M = Moment at the section under consideration.
- * M_a = Wall allowable moment due to axial force or lintel pure flexure allowable moment
- * f_a = Calculated compressive stress due to axial load only
- * f_b = Calculated compressive stress due to axial flexure only
- * f_t = Calculated axial tension
- * F_a = Allowable compressive stress due to axial load only
- * F_b = Allowable compressive stress due to axial flexure only
- * f_v = Calculated shear stress
- * F_s = Allowable tensile or compressive stress
- * F_v = Allowable shear stress
- * l_d = Embedment length
- * A_s = Effective cross sectional area of reinforcement
- * δ_s = Calculated deflection
- * δ_{max} = Maximum allowable deflection



DUNN ASSOCIATES, INC
Consulting Structural Engineers

Title
OGDEN COMMUNITY SERVICES BUILDING

Sheet Number: **O-57**

Job Number: 240268


Date:

By: CF

OPENING 4 DESIGN NARRATIVE

S.R. COMPARISON


EXISTING



Shear

Segment	Condition	f_v [Kip/in ²]	F_v [Kip/in ²]	Ratio	
1	D16(Bottom)	0.006	0.105	0.05	
2	D15(Bottom)	0.009	0.103	0.09	
3	D10(Top)	0.012	0.100	0.12	
4	D11(Bottom)	0.015	0.096	0.15	
5	D21(Bottom)	0.016	0.094	0.17	
6	D16(Bottom)	0.022	0.097	0.23	
7	D15(Top)	0.009	0.105	0.09	
8	D22(Bottom)	0.005	0.104	0.05	

POST OPENING



Shear

Segment	Condition	f_v [Kip/in ²]	F_v [Kip/in ²]	Ratio	
1	D10(Bottom)	0.006	0.105	0.06	
2	D15(Bottom)	0.008	0.101	0.08	
3	D16(Top)	0.012	0.101	0.12	
4	D21(Bottom)	0.016	0.096	0.16	
5	D21(Bottom)	0.018	0.094	0.19	
6	D16(Bottom)	0.023	0.096	0.24	
7	D9(Bottom)	0.020	0.095	0.21	
8	D15(Bottom)	0.011	0.104	0.11	
9	D22(Bottom)	0.005	0.104	0.05	

EXISTING	S.R.	POST OPENING	S.R.
	0.05		0.06
	0.09		0.08
	0.12		0.12
	0.15		0.16
	0.17		0.19
	0.23		0.24
	0.09		0.21
	0.05		0.11
			0.05
Average S.R.	0.119	Average S.R.	0.1356
		Difference in Stress Ratios =	1.14
			14% INCREASE
			14% INCREASE > 10%, EXCEPTION NOT TAKEN

IBC 304.3.2 Compliance with reduced seismic forces.

Where seismic evaluation and design is permitted to use reduced seismic forces, the criteria used shall be in accordance with one of the following:

1. The International Building Code using 75 percent of the prescribed forces. Values of R , C_s and C_u used for analysis shall be as specified in Section 304.3.1 of this code.

2. Structures or portions of structures that comply with the requirements of the applicable chapter in Appendix A as specified in Items 2.1 through 2.4 and subject to the limitations of the respective Appendix A chapters shall be deemed to comply with this section.

2.1. The seismic evaluation and design of unreinforced masonry bearing wall buildings in Risk Category I or II are permitted to be based on the procedures specified in Appendix Chapter A1.

2.2. Seismic evaluation and design of the wall anchorage system in reinforced concrete and reinforced masonry wall buildings with flexible diaphragms in Risk Category I or II are permitted to be based on the procedures specified in Chapter A2.

2.3. Seismic evaluation and design of cripple walls and sill plate anchorage in residential buildings of light-frame wood construction in Risk Category I or II are permitted to be based on the procedures specified in Chapter A3.

2.4. Seismic evaluation and design of soft, weak or open-front wall conditions in multiple-unit residential buildings of wood construction in Risk Category I or II are permitted to be based on the procedures specified in Chapter A4.

3. ASCE 41, using the performance objective in Table 304.3.2 for the applicable risk category.

WALL ANALYZED TO PROVE IT WORKS WITH NEW OPENING AND PER IBC 304.3.2 THE WALL IS ACCEPTABLE WITH 75% OF IBC FORCES FOR INTERMEDIATE MASONRY SHEAR WALL SEISMIC RESPONSE

DESIGN INFORMATION IN MASONRY


Table 13 — Allowable tension loads for Hilti KWIK HUS installed in grout-filled masonry walls (lb)^{1,2,3,4,5}

Nominal anchor diameter	Nominal embedment ³ in.	Loads at c _{cr} and s _{cr}	Spacing			Edge distance						
			Critical - s _{cr} ⁶ in.	Minimum - s _{min} ⁶ in.	Load reduction factor at s _{min} ⁶	Critical - c _{cr} ⁷ in.	Minimum c _{min} ⁸ in.	Load reduction factor ⁷				
	1-5/8	535	4	2	0.70	4	4	1.00				
3/8	2-1/2	895	6	4	0.80							
	3-1/4	1,210										
1/2	2-1/4	710	4	2	0.60	4	4	1.00				
	3	1,110	8									
	4-1/4	1,515										
5/8	3-1/4	1,155	10	4	0.60	10	4	1.00				
	5	1,735										
3/4	4	1,680	12	4	0.60	12	4	1.00				
	6-1/4	2,035										

Table 14 — Allowable shear loads for Hilti KWIK HUS installed in grout-filled masonry walls (lb)^{1,2,3,4,5}

Nominal anchor diameter	Nominal embedment ³ in.	Loads at c_{cr} and s_{cr}	Spacing			Edge distance			
			Critical - s_{cr} ⁶ in.	Minimum - s_{min} ⁶ in.	Load reduction factor at s_{min} ⁷	Critical - c_{cr} ⁸ in.	Minimum c_{min} ⁸ in.	Load reduction factor at c_{min}	
								Load direction perpendicular to edge	Load direction parallel to edge
3/8	1-5/8	1,140	6	4	0.94	6	4	0.61	1.00
	2-1/2	1,165						0.70	1.00
	3-1/4	1,190						0.70	1.00
1/2	2-1/4	1,845	8	4	0.88	8	4	0.50	1.00
	3	2,055						0.45	0.94
	4-1/4	2,745						0.40	0.89
5/8	3-1/4	3,040	10	4	0.36	10	4	0.36	0.82
	5	3,485						0.34	0.92
3/4	4	3,040	10	4	0.36	12	4	0.36	0.82
	6-1/4	3,485						0.34	0.92

WORST CASE OUT OF PLANE LOAD



$$44.82 \text{ plf} + 105 \text{ plf} = 150 \text{ plf OOP WL}$$


$$\text{ANCHORS SPACED AT 48" O.C.}$$

$$150 \text{ PLF} \times 48" \times 1/12" = 600 \text{ lb}$$

$$600 \text{ lb} \times 0.6 = 360 \text{ lb (ASD)}$$

$$\text{ALLOWABLE CAPACITY} = 535 \text{ lb}$$

$$360 \text{ lb} < 535 \text{ lb, O.K.}$$



$$30.6 \text{ plf} + 73.5 \text{ plf} = 105 \text{ plf OOP EQ}$$

$$\text{ANCHORS SPACED AT 48" O.C.}$$

$$150 \text{ PLF} \times 48" \times 1/12" = 420 \text{ lb}$$

$$420 \text{ lb} \times 0.7 = 294 \text{ lb (ASD)}$$

$$590 \text{ plf} + 400 \text{ plf} = 990 \text{ plf}$$

$$990 \text{ plf} \times 1 \text{ ft} = 990$$

$$\text{lb shear per anchor}$$



DUNN ASSOCIATES, INC
Consulting Structural Engineers

Title
OGDEN COMMUNITY BUILDING


Sheet Number: O-59

Job Number: 240268

Date: 3/11/2025

By: CF

OGDEN COMMUNITY BUILDING



REACTION AT COLUMN
TOP = 400 lb (ASD)

MINIMUM (3) JOISTS ATTACHED,
(2) SDS SCREWS PER JOIST,
(6) SDS SCREWS TOTAL
SDS SHEAR CAPACITY = 165 lb

$165 * 6 = 990 \text{ lb} > 400 \text{ lb (ASD)}$

SDS Heavy-Duty Connector Screw —
Allowable Shear Loads — Douglas Fir-Larch and Southern Pine Lumber

Fastener Length (in.)	Model No.	Reference DFL/SP Allowable Shear Loads (lb.)											
		Wood Side Plate Thickness (in.)											
		1/2	5/8	3/4	1	1 1/8	1 1/4	1 1/2	1 3/4	2	2 1/2	3	4
2	SDS25200	145	—	—	—	—	—	—	—	—	—	—	—
2 1/2	SDS25212	165	165	170	165	—	—	190 ¹	—	—	—	—	—

$400 \text{ lb} * 5" = 2000 \text{ lb-in}$

$2000 \text{ lb-in} / 3" = 667 \text{ lb}$
Tension/Compression

6 Screws Total,
3 of them in Tension

$3 * 255 \text{ lb} = 765 \text{ lb}$
Capacity

$765 \text{ lb} > 667 \text{ lb, O.K.}$

SDS Heavy-Duty Connector Screw — Reference Allowable Withdrawal Loads
— Douglas Fir-Larch, Southern Pine, Spruce-Pine-Fir and Hem-Fir Lumber

Model No.	Fastener Length (in.)	Thread Length (in.)	Reference Allowable Withdrawal Loads, W (lb./in.)		Max. Reference Allowable Withdrawal Loads, W _{max} (lb.)	
			DFL and SP Main Member	HF and SPF Main Member	DFL and SP Main Member	HF and SPF Main Member
SDS25112	1.5	1	172	121	170	120
SDS25200	2	1.25	172	121	215	150
SDS25212	2.5	1.5	172	121	255	180

Toe Nails: (3) 10d nails per side, (9) MIN,

10d Capacity = 118 lb
Toe Nail Factor = 0.83

$118 * 0.83 = 97 \text{ lb, } 97 \text{ lb} * 9 \text{ nails} = 873 \text{ lb} > 400 \text{ lb}$