



**INVITATION TO BID:** Lorin Farr Pool Repair - Fall 2025

**ADDENDUM NO.** 1

**DATE:** 09/08/2025

---

This addendum is issued to modify the previously released solicitation documents and/or given for informational purposes. It is hereby made part of the ITB document. It is made available to all interested and eligible parties via the Ogden City Purchasing website.

---

## **Scope of Work**

### **Big Pool:**

- Remove all existing plaster and rubber patch materials.
- Assess the exposed pool structure and repair any damage identified during removal.
- Install 2x2 tiles on both sides of the expansion joint.
- Install backer rod and seal the expansion joint with polysulfide.
- Strip, grind, and float the top steps; retile steps completely with new tile.
- Remove and **save all salvageable tiles.**
  - ~~attach~~ Install all **new** tiles along the edge of the pool **using Schluter edge system.**  
(existing tile)
  - Ensure all tile edging is smooth and safe, with no sharp edges.
- Install depth transition tile.
- Install new pool drains.
- Knock in return fittings and perform leak detection.
- Install **PebbleQuartz®** Quarts Finish upon completion of structural and tile work.
- Conduct full wet testing to confirm watertight integrity and performance.

**Little Pool:**

- ~~attach~~ Install all new tiles along the edge of the pool using Schluter edge system.  
~~(existing tile)~~
- Ensure all tile edging is smooth and safe, with no sharp edges.

**New Tiles:**

- The selected tile product must be approved by the project manager prior to installation. It should closely match the existing pool tile color and pattern.

**Acknowledgement:**

\_\_\_\_\_  
Name & Title

\_\_\_\_\_  
Firm Name

\_\_\_\_\_  
Authorized Signature & Date