

# *El Monte Cart Shed*



## **PLAN SHEETS**

- 0 : COVER \_ COVER SHEET
- 1 : DEMO \_ DEMOLITION
- 2 : UTIL \_ UTILITIES
- 3 : WALL 1 \_ WALL PLAN
- 4 : WALL 2 \_ WALL PROFILES
- 5 : GRADE \_ GRADING
- 6 : X-SEC 1 \_ CROSS SECTIONS
- 7 : X-SEC 2 \_ CROSS SECTIONS
- 8 : X-SEC 3 \_ CROSS SECTIONS
- 9 : X-SEC 4 \_ CROSS SECTIONS
- 10 : X-SEC 5 \_ CROSS SECTIONS
- 11 : B-PAD \_ BUILDING PAD
- 12 : FOUND \_ FOUNDATION LAYOUT
- 13 : FD-1 \_ FOUNDATION DETAILS
- 14 : FD-2 \_ FOUNDATION ELEVATIONS
- 15 : CONST 1 \_ SURFACE IMPROVEMENTS
- 16 : CONST 2 \_ MINOR ASPHALT WORK
- 17 : LAND \_ LANDSCAPING

## ***Project Location***

***El Monte Golf Course***  
***1300 Valley Dr, Ogden, UT, 84401***



# UTILITY ITEMS

EP: 3+17.64  
STATION=3+17.64  
OFFSET=0.00  
NORTHING=3609229.93  
EASTING=1518078.73

Adjust Spr. Head  
(By Others)

PT: 2+80.88

*i* Information

20 3/4" Poly Culinary Water

21 3/4" Culinary Water Connection

22 3/4" Frost Proof Hydrant

23 14"x19" Electrical Junction Box

24A 2" Electrical Conduit

24B 1" Electrical Conduit

24C 1-1/2" Electrical Conduit

25A 4" SDR 35 (LD)

25B 4" SDR 35 (FD)

26 4" Floor Drain

27 4" Cleanout

28 6" SDR 35

29 6" Cleanout

30 OS-50 Oil Separator

31 4" Flex Pipe Connection

32 Electrical Fuel Switch

SCALE: 1":10'




UTIL

17

2

PAGE



## UTILITIES

### EL MONTE MAINTENANCE SHED

EL MONTE GOLF COURSE

DRAWING NAME: Dalton's Final - AAA NEW El Monte - MAINTENANCE SHED FINAL PERT&DATA B00961 12/14 PM



2540 Washington Blvd, Suite 750 Ogden, UT 84401  
Phone: 801-629-8980 engineering.ogdencity.com

STATION=0+00.00  
OFFSET=0.00  
NORTHING=3608974.82  
EASTING=1518224.28

| REV | DATE     | DESCRIPTION             |
|-----|----------|-------------------------|
| 0   | MM/DD/YY | Initial drawing (Rev 0) |

This bar measures exactly one inch on the original drawing

| DESIGNED | DRAWN | CHECKED |
|----------|-------|---------|
| DSG      | DSG   | DSG     |

H: 1" = 10' (2234) (11x17) This bar measures exactly one inch on the original drawing

V: N/A

2540 Washington Blvd, Suite 750 Ogden, UT 84401

Phone: 801-629-8980 engineering.ogdencity.com


EP: 3+17.64  
STATION=3+17.64  
OFFSET=0.00  
NORTHING=3609229.93  
EASTING=1518078.73

**SCALE: 1":10'**



## **WALL ITEMS**

- Information
- Rock Wall 36"-12"+
- Rock Wall 24"-8"



TATION=0+00.00  
FFSET=0.00  
ORTHING=3608974.82  
ASTING=1518224.28


**Ogden** UTAH *Still Untamed™*  
2559 Washington Blvd, Suite 760 Ogden, UT 84401  
Phone: 801-628-8080 [www.orderlineutah.com](http://www.orderlineutah.com)

# EL MONTE MAINTENANCE SHED


EL MONTE GOLF COURSE

|   |     |                    |
|---|-----|--------------------|
| DRAWN   |     | 10/6/25            |
| CHECKED   |     |                    |
| DRAWN   | DSG |                    |
| DRAFTING SCALE  |     |                    |
| 1: 1" = 10'   |     | (22x34)<br>(11x17) |
| 1: N/A  |     | (22x34)            |
| <p><b>DANIEL GILLIES</b></p> <p>1000 Gillies Ln #1, 2020 06-26-2018</p> <p>DANIEL SHIPP-GILLIES</p> <p>NO. 409584-2002</p> <p>EXP. 12/20/2025</p> <p>CIVIL</p> <p>STATE OF UTAH</p>  |     |                    |

PAGE



**SCALE: 1":5'**




# **DEMOLITION ITEMS**


-  **Remove Asphalt**
-  **Grub Sod**
-  **Clear & Grub Area**
-  **Remove Concrete**
-  **Unclassified Excavation**

## CONSTRUCTION ITEMS

-  **Install 3" HMA**
-  **UTBC (t=6")**
-  **Import Common Fill**
-  **Topsoil**
-  **6" Concrete Flatwork**
-  **Sod**



## ***Landscape Rock Wall "C"***



## EL MONTE MAINTENANCE SHED




### WALL PROFILES

EL MONTE GOLF COURSE










# **DEMOLITION ITEMS**



-  **Remove Asphalt**
-  **Grub Sod**
-  **Clear & Grub Area**
-  **Remove Concrete**
-  **Unclassified Excavation**



# CONSTRUCTION ITEMS

-  **Install 3" HMA**
-  **UTBC (t=6")**
-  **Import Common Fill**
-  **Topsoil**
-  **6" Concrete Flatwork**
-  **Sod**

**SCALE: 1":5'**



## **CROSS SECTIONS**


---

## **EL MONTE MAINTENANCE SHED**


The logo for Ogden, Utah, featuring the word "Ogden" in a large, stylized, blue, cursive font. Below "Ogden", the word "UTAH" is written in a smaller, blue, sans-serif font, with two diagonal blue lines extending from the bottom right corner of "UTAH" towards the bottom right corner of the logo area.

2549 Washington Blvd, Suite 760 Ogden, UT 84401

|          |     |  |
|----------|-----|--|
| DESIGNED | DSG | DATE   |
| DRAWN    | DSG | 10/6/25  |
| CHECKED  |     | DRAWING SCALE                                  |
|          |     | H: 1" = 10' (22x34)<br>V: N/A (22x34)<br>_____ |




## **STA 9+13.80 (North)**




## **DEMOLITION ITEMS**

-  **Remove Asphalt**
-  **Grub Sod**
-  **Clear & Grub Area**
-  **Remove Concrete**
-  **Unclassified Excavation**




## **LAND-DRAIN REALIGNMENT**

**SCALE: 1":10'**




## **STA 9+13.80 (West)**




## **CONSTRUCTION ITEMS**


-  **Install 3" HMA**
-  **Import Common Fill**
-  **6" Concrete Flatwork**
-  **UTBC (t=6")**
-  **Topsoil**
-  **Sod**




# STA 9+33.80



# STA 9+53.80



# BUILDING FLOOR DRAIN



# DEMOLITION ITEMS

- Remove Asphalt
- Grub Sod
- Clear & Grub Area
- Remove Concrete
- Unclassified Excavation

# CONSTRUCTION ITEMS

- Install 3" HMA
- UTBC (t=6")
- Import Common Fill
- Topsoil
- 6" Concrete Flatwork
- Sod


|  |     |
|--|-----|
| X-SEC 5  |     |
| SHEETS   | 17  |
| PAGE 10  |     |
| <p>PROFESSIONAL ENGINEER<br/>Daniel Shipp Gillese<br/>State of Utah<br/>No. 493584-2202<br/>Exp. 12/23/2025<br/>CIVIL</p>                        |     |
| DESIGNED   | DSG |
| DRAWN  | DSG |
| CHECKED  |     |
| DATE 10/6/25   |     |
| DRAWING SCALE (22x34)<br>H: 1" = 10' (11x17)<br>V: N/A (22x34)<br>(11x17)<br>This bar measures exactly one inch on the original drawing          |     |
| CROSS SECTIONS   |     |
| EL MONTE MAINTENANCE SHED  |     |
| EL MONTE GOLF COURSE   |     |
| DRAWING NAME: Dalton's Final - AAA NEW El Monte - MAINTENANCE SHED FINAL PERT/DATA/Blanks/dwg096 12:15 PM  |     |
| <p>Ogden<br/>UTAH<br/>Still Untamed™</p> <p>2540 Washington Blvd, Suite 750 Ogden, UT 84401<br/>Phone: 801-629-8980 engineering.ogdencty.com</p> |     |






|                                 |            |
|---------------------------------|------------|
| FD-1                            |            |
| SHEET                           | 13         |
| REV                             | 0          |
| DATE                            | 0 MM/DD/YY |
| DESCRIPTION                     |            |
| PROFESSIONAL ENGINEER SIGNATURE |            |
| DANIEL SHIPP GILLES             |            |
| REGISTRATION NO. 4039584-2002   |            |
| EXPIRATION DATE 12/23/2025      |            |
| CIVIL                           |            |
| STATE OF UTAH                   |            |

|  |  |
|--|--|
| FOUNDATION DETAILS                     |  |
| EL MONTE CART SHED                     |  |
| 1300 VALLEY DR                         |  |
| H: T= 20' (22x34)<br>V: T= 40' (11x17) |  |
| DRAWING SCALE                          |  |
| PLOT DATE: 1/13/2026 12:15 PM          |  |
| DRAFTING NAME: Foundation Detail.dwg   |  |




Plan View




Profile View



## FOOTING & COLUMN DETAIL



## SLAB DETAIL




## ANCHOR BOLT LAYOUT



|   |                    |
|---|--------------------|
| FD-2  |                    |
| SHEET   | 14                 |
| 0   | REVISION           |
| PROFESSIONAL ENGINEER   |                    |
| DANIEL SHIPP GILLES   |                    |
| NO. 409584-2002   |                    |
| EXP. 12/21/2025   |                    |
| STATE OF UTAH   |                    |
| DESIGNED ▲ DBR<br>DRAWN ▲ DBR<br>CHECKED ▲ DSG                        | DATE<br>12/23/2025 |
| DRAWING SCALE<br>H: 1" = 20' (22x34)<br>V: 1" = 40' (11x17)           |                    |
| This drawing measures one inch equals 20 feet on the original drawing |                    |
| 1300 VALLEY DR<br>EL MONTE CART SHED                                  |                    |
| PLOT DATE: 1/13/2026 12:15 PM   |                    |
| DRAWING NAME: Foundation Detail.dwg                                   |                    |
| 2549 Washington Blvd, Suite 760 Ogden, UT 84401                       |                    |
| Phone: 801-629-8980 engineering.ogdencity.com                         |                    |

### Elevation Breakdown

| Column | Slab Elevation | Foundation Elevation | Footing Elevation | Bottom Elevation |
|--------|----------------|----------------------|-------------------|------------------|
| A      | 4431.58        | 4431.08              | 4427.96           | 4426.96          |
| B      | 4431.58        | 4431.08              | 4427.02           | 4426.02          |
| C      | 4431.58        | 4431.08              | 4427.02           | 4426.02          |
| D      | 4431.58        | 4431.08              | 4425.10           | 4424.10          |
| E      | 4431.58        | 4431.08              | 4425.01           | 4424.01          |
| F      | 4431.58        | 4431.08              | 4424.86           | 4423.86          |
| G      | 4431.58        | 4431.08              | 4424.51           | 4423.51          |
| H      | 4431.58        | 4431.08              | 4424.87           | 4423.87          |
| I      | 4431.58        | 4431.08              | 4425.35           | 4424.35          |
| J      | 4431.58        | 4431.08              | 4426.03           | 4425.03          |
| K      | 4431.58        | 4431.08              | 4429.05           | 4428.05          |
| L      | 4431.58        | 4431.08              | 4428.78           | 4427.78          |



### EL EVATION DETAIL





**LANDSCAPING**  
EL MONTE MAINTENANCE SHED

DRAWING NAME: Dalton's Final - AAA NEW El Monte - MAINTENANCE SHED FINAL PERT/DATA/Blanks/0096 12:15 PM

Ogden City to Complete Landscape & Irrigation Installation.

Planter areas will have water-wise shrubs that will cover 50% of the individual areas at mature growth.

Irrigation will be installed accordingly.

# LANDSCAPING

*i* Information

~~70 4' Chainlink Fence~~

~~71 Install Gas Pump/Incl Electrical Wiring~~

~~72 6" Concrete/6" UTBC~~

~~73 Kentucky Blue Grass Sod (Short)~~


~~77 3" (t) HMA / 6" UTBC~~

~~74 Kentucky Blue Grass Sod (Tall)~~

~~78 Great Basin Seed Mix~~


~~75 D-12" Cobble w/Marifi~~

~~76 6" (t) Landscape Rock w/Marifi~~



## ELECTRICAL STANDARDS LEGEND

(ALL SYMBOLS MAY NOT BE USED IN DRAWINGS)




## GENERAL ELECTRICAL ABBREVIATIONS

|      |                            |      |                             |     |                                |      |                                    |
|------|----------------------------|------|-----------------------------|-----|--------------------------------|------|------------------------------------|
| ACB  | AIR CIRCUIT BREAKER        | HMI  | HUMAN MACHINE INTERFACE     | MTU | MASTER TERMINAL UNIT           | SE   | SERVICE ENTRANCE                   |
| AFF  | ABOVE FINISHED FLOOR       | IC   | INSTRUMENTATION CONDUIT     | NC  | NORMALLY CLOSED                | SER  | SERVICE ENTRANCE RATED             |
| AFG  | ABOVE FINISHED GRADE       | IER  | INTEGRATED EQUIPMENT RATING | NO  | NORMALLY OPEN                  | SPC  | SPARE CONDUIT                      |
| ATS  | AUTOMATIC TRANSFER SWITCH  | INST | INSTRUMENTATION CONDUIT     | OL  | MOTOR OVERLOAD                 | SPD  | SURGE PROTECTIVE DEVICE            |
| C    | CONDUIT                    | JB   | JUNCTION BOX                | PB  | PULL BOX                       | SPIC | SPARE INSTRUMENT CONDUIT           |
| CB   | CIRCUIT BREAKER            | LCP  | LOCAL CONTROL PANEL         | PCP | PUMP CONTROL PANEL             | SSSS | SOLID STATE SOFT START             |
| CTRL | CONTROL                    | LP   | LIGHTING PANEL              | PLC | PROGRAMMABLE LOGIC CONTROLLER  | TSP  | TWISTED SHIELDED PAIR              |
| DS   | DISCONNECT SWITCH          | MCB  | MAIN CIRCUIT BREAKER        | RGS | RIGID GALVANIZED STEEL CONDUIT | TVSS | TRANSIENT VOLTAGE SURGE SUPPRESSOR |
| EMG  | ELECTRICAL MANHOLE         | MCP  | MOTOR CIRCUIT PROTECTOR     | PP  | POWER PANEL                    | VFD  | VARIABLE FREQUENCY DRIVE           |
| EMT  | ELECTRICAL METALLIC TUBING | MLO  | MAIN LUG ONLY               | RTU | REMOTE TERMINAL UNIT           | WP   | WEATHERPROOF                       |


## GENERAL ELECTRICAL REQUIREMENTS

- THE COMPLETED INSTALLATION SHALL CONFORM TO ALL APPLICABLE FEDERAL, STATE AND LOCAL CODES, ORDINANCES AND REGULATIONS. CONTRACTOR SHALL OBTAIN NECESSARY PERMITS AND INSPECTIONS REQUIRED BY THE GOVERNING AUTHORITIES. ALL WORK SHALL BE DONE IN A NEAT, PROFESSIONAL, FINISHED AND SAFE MANNER, UNDER COMPETENT SUPERVISION. INSTALL GROUNDING AND ALL ELECTRICAL WORK AS REQUIRED BY THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE AS WELL AS ANY OTHER APPLICABLE CODES.
- MATERIAL, EQUIPMENT AND INSTALLATION SHALL BE IN ACCORDANCE WITH PROJECT SPECIFICATIONS WHICH ARE PART OF THE CONTRACT DOCUMENTS FOR THIS PROJECT.
- VISIT THE SITE PRIOR TO BIDDING TO BECOME FAMILIAR WITH EXISTING CONDITIONS AND ALL OTHER FACTORS WHICH MAY AFFECT THE EXECUTION OF THIS WORK. INCLUDE ALL RELATED COSTS IN THE INITIAL BID PROPOSAL.
- ALL MATERIALS SHALL BE NEW AND OF THE BEST QUALITY, MANUFACTURED IN ACCORDANCE WITH NEMA, ANSI, U.L. OR OTHER APPLICABLE STANDARDS. THE USE OF MANUFACTURER'S NAMES, MODELS AND NUMBERS IS INTENDED TO ESTABLISH STYLE, QUALITY, APPEARANCE, USEFULNESS AND BID PRICE. PROPOSED SUBSTITUTIONS SHALL BE SUBMITTED IN WRITING AND APPROVED BY THE ENGINEER BEFORE ORDERING.
- PROTECT ALL ELECTRICAL MATERIAL AND EQUIPMENT INSTALLED UNDER THIS PROJECT AGAINST DAMAGE BY OTHER TRADES, WEATHER CONDITIONS OR ANY OTHER CAUSES. EQUIPMENT FOUND DAMAGED OR IN OTHER THAN NEW CONDITIONS WILL BE REJECTED AS DEFECTIVE.
- LEAVE THE SITE CLEAN, REMOVE ALL DEBRIS, EMPTY CARTONS, TOOLS, CONDUIT, WIRE SCRAPS AND ALL MISCELLANEOUS SPARE EQUIPMENT AND MATERIALS USED IN THE WORK DURING CONSTRUCTION. ALL COMPONENTS SHALL BE FREE OF DUST, GRIT AND FOREIGN MATERIALS, LEFT AS NEW BEFORE FINAL ACCEPTANCE OF WORK.
- ALL CONDUCTORS SHALL BE THHN/THWN COPPER, STRANDED RATED AT 600 VOLTS UNLESS OTHERWISE NOTED. ALUMINUM WIRE WILL NOT BE ALLOWED.
- ALL CONDUCTORS SHALL BE INSTALLED IN A CONDUIT SYSTEM EXCEPT WHERE NOTED IN DRAWINGS. REFER TO CONDUIT AND CONDUCTOR SCHEDULE FOR CONDUIT TYPE AND SIZE. WHERE CONDUIT SIZE IS NOT CALLED OUT, CONDUIT SHALL BE INSTALLED PER SPECIFICATION 16010 AND SIZED PER LATEST ADOPTED EDITION OF THE NEC.
- ALL UNDERGROUND CONDUIT TO BE SCHEDULE 40 PVC. MINIMUM DEPTH 30", MINIMUM SIZE 3/4" EXCEPT AS NOTED IN DRAWINGS AND SPECIFICATIONS. ALL UNDERGROUND ELBOWS SHALL BE RIGID LONG SWEEP WRAPPED WITH 3M-50 10 MIL PIPE WRAP OR APPROVED EQUAL EXCEPT FOR COMMUNICATIONS CABLE AND CONDUIT WHEN SPECIFIED DIFFERENTLY ON THE DETAILED ELECTRICAL DRAWINGS.
- ALL EXPOSED CONDUIT BELOW 4' AFG SHALL BE IMC OR RIGID STEEL CONDUIT, WITH A MINIMUM SIZE OF 1" EXCEPT AS NOTED IN DRAWINGS AND SPECIFICATIONS. EMT WILL BE PERMITTED, ONLY IN WALLS OR ABOVE 4' AFG. EXPOSED PVC CONDUIT SHALL NOT BE PERMITTED UNLESS NOTED OTHERWISE IN DRAWINGS.
- ALL SAFETY SWITCHES AND OTHER DISTRIBUTION AND CONTROL ELECTRICAL EQUIPMENT SHALL BE RATED FOR HEAVY DUTY SERVICE.
- ALL WIRING DEVICES SHALL BE SPECIFICATION GRADE GROUNDED BODY TYPE DEVICES.
- THE CONTRACTOR SHALL INSTALL ALL INSTRUMENTS AND CONTROLS, INCLUDING HVAC AND CONTROL PANELS. THE CONTRACTOR SHALL OBTAIN AND REVIEW ALL INSTRUMENT, CONTROL AND HVAC DRAWINGS FOR TOTAL SCOPE OF WORK.
- ALL PANELS, DISCONNECTS AND SWITCHGEAR ON THE OUTSIDE OF THE BUILDING SHALL BE NEMA 3R TYPE ENCLOSURES UNLESS OTHERWISE SPECIFIED. CT CABINET AND METER BASE SHALL BE OUTSIDE THE BUILDING.
- SURGE PROTECTIVE DEVICES (SPD) SHALL BE SIZED FOR 160KA UNLESS OTHERWISE NOTED.
- ALL CONDUIT FOR ALL EQUIPMENT, INCLUDING EQUIPMENT FURNISHED BY OTHERS, SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR.
- ALL CONDUIT, WHERE LEAVING ELECTRICAL EQUIPMENT TO GO UNDERGROUND, MUST BE ANCHORED TO THE FOUNDATION WITH STAND-OFF BRACKETS TO ALLOW FOR SUFFICIENT CLEARANCE FOR FOOTINGS AND WALL STUDS ON THE WALLS IN THE BUILDING. ALL RGS CONDUIT AND ELBOWS USED UNDERGROUND WILL BE WRAPPED WITH AN APPROVED PIPE WRAP. (TYP. FOR ALL BUILDINGS)
- ALL WIRING IN CLASS I HAZARDOUS LOCATIONS SHALL COMPLY WITH NEC 501. AS DEFINED BY NFPA 820.

| REV NO.  | COMMENT   | DATE  |             |                  |      |
|--|---|---|-------------|------------------|------|
|  16-JAN-2026<br>No. 362066<br>J. RANDALL KNAPP<br>REGISTERED PROFESSIONAL ENGINEER<br>STATE OF UTAH | <br>SUNRISE<br>ENGINEERING | 6875 SOUTH 900 EAST<br>SALT LAKE CITY, UTAH 84047<br>TEL 801.523.0100 - FAX 801.523.0990<br>www.sunrise-eng.com |             |                  |      |
| OGDEN CITY   |   |   |             |                  |      |
| EL MONTE GOLF COURSE SHED<br>ELECTRICAL<br>ELECTRICAL NOTES AND SYMBOLS  |   |   |             |                  |      |
| SEI NO. S  | DESIGNED KRD  | DRAWN GKP   | CHECKED JRK | SHEET NO. 1 of 6 | E100 |

## LIGHTNING PROTECTION

- PROVIDE A COMPLETE LIGHTNING PROTECTION SYSTEM BY VFC OR APPROVED COMPLYING WITH NFPA 780. SYSTEM TO INCLUDE: CABLING NETWORK, AIR TERMINALS, CONNECTIONS, SPLICES, BONDING, GROUND RING, GROUND RODS, AND ANY OTHER REQUIRED EQUIPMENT. ALL ROOF MOUNTED EQUIPMENT SHALL BE BONDED AND PROTECTED BY THE LIGHTNING PROTECTION SYSTEM. INSTALLER SHALL PROVIDE A UL MASTER LABEL FOR THE LIGHTNING PROTECTION SYSTEM UPON COMPLETION OF THE PROJECT.
- REFER TO SPECIFICATION 16065SP FOR ADDITIONAL DETAILS.



| PANEL LP1<br>EL MONTE GOLF COURSE SHED |      |      |                        |      |           |                |       |       |         | CU Bus                |                |             |
|--|------|------|------------------------|------|-----------|----------------|-------|-------|---------|-----------------------|----------------|-------------|
|  |      |      |                        |      |           |                |       |       |         | 10 KA SC Rating (RMS) |                |             |
| VOLTAGE                                | PH   | WIRE | PANEL SCHEDULE CIRCUIT |      |           |                |       |       |         | 125 AMP MAIN CB       |                |             |
|  |      |      | LOAD (VA)              | AMPS | LOAD (VA) |                |       |       |         | DESCRIPTION           | POLE           | AMPS        |
| CKT NO.                                | AMPS | POLE | DESCRIPTION            | L1   | L2        | OTHER          | RECEP | LIGHT | CKT NO. | DESCRIPTION           | POLE           | AMPS        |
| 1                                      | 20   | 1    | FUEL DISCONNECT        | 0    | 0         | 696            | 5.8   | 12.2  | 2       | 1469                  | 1              | 20          |
| 3                                      | 20   | 1    | COMPRESSOR             | 0    | 450       | 0              |       | 3.8   | 4       | 1080                  | 0              | RECEPTACLES |
| 5                                      | 20   | 1    | SPARE                  | 0    | 0         | 0.0            | 0.0   |       | 6       | 0                     | 0              | 0           |
| 7                                      | 50   | 2    | IRRIGATION PANEL       | 0    | 0         | 7200           |       | 30.0  | 8       | 0                     | 0              | 0           |
| 9                                      | -    | -    | ..                     | 0    | 0         | 0              | 30.0  | 0.0   | 10      | 0                     | 0              | 0           |
| 11                                     | -    | -    |                        | 0    | 0         | 0              |       | 0.0   | 12      | 0                     | 0              | 0           |
|  |      |      |                        | 0    | 450       | 7896           | 48    | 43    |         | 1080                  | 1469           |             |
|  |      |      |                        |      |           | Subtotal Watts |       |       |         | 2549                  | Subtotal Watts |             |
|  |      |      |                        |      |           | Total Watts    |       |       |         | 46                    | Average Amps   |             |

NEC DIVERSIFIED LOAD CALCULATIONS

| LIGHTING AND CONTINUOUS LOADS:<br>(100% CONNECTED LOAD PLUS 25%)   | 1.5 kVA                     | Lighting<br>Total kVA: 1.8    |
|--|-----------------------------|-------------------------------|
| RECEPTACLES:<br>(FIRST 10kVA @ 100%, REMAINDER @50%)   | 1.5 kVA                     | Receptacles<br>Total kVA: 1.5 |
| ALL OTHER LOADS @ 100%:<br>MOTOR TOTALS INCLUDED IN ALL OTHER LOADS<br>WITH LARGEST MOTOR CALCULATED AT 125% PER NEC | 7.9 kVA                     | Other Loads<br>Total kVA: 9.7 |
|  | DIVERSIFIED TOTAL kVA 13.1  |                               |
|  | AVERAGE AMPS PER PHASE 54.4 |                               |

### SHEET NOTES:

- ONE-LINE DIAGRAM SHOWS PROPOSED CONFIGURATION. CONTRACTOR SHALL CONFIRM ACTUAL CONFIGURATION WITH UTILITY PRIOR TO CONSTRUCTION AND PROVIDE ALL NECESSARY EQUIPMENT PADS, PULL BOXES OR OTHER ITEMS REQUIRED BY UTILITY.
- THE CONTRACTOR SHALL COORDINATE ALL WORK WITH OWNER PRIOR TO CONSTRUCTION.
- THE CONTRACTOR IS RESPONSIBLE FOR ALL TRENCHING, BACKFILL, COMPACTION, AND THE INSTALLATION OF CONDUIT SHOWN AS NEW OR TO BE EXTENDED TO NEW EQUIPMENT LOCATION.
- PROVIDE BONDING AND GREEN INSULATED GROUND FOR ALL ELECTRICAL ENCLOSURES PER LATEST EDITION OF NEC.

### KEY NOTES

(1) CONNECT TO EXISTING 100A FEEDER BREAKER IN CLUBHOUSE PANEL. COMPLETE CIRCUITING WILL BE FIELD ROUTED. WORK WITH OWNER PRIOR TO INSTALLATION FOR PRESERVATION OF BUILDING INTEGRITY.


(2) BOND TO ALL ELECTRODES PRESENT PER NEC 250 AND LOCAL AHJ.


| CONDUIT & CONDUCTOR SCHEDULE |           |        |      |     |                    |                   |
|------------------------------|-----------|--------|------|-----|--------------------|-------------------|
| TYPE                         | CONDUCTOR |        |      |     | CONDUIT SIZE (5)   |                   |
|                              | USE       | METAL  | SETS | QTY | SIZE (AWG OR KCML) | GND (AWG OR KCML) |
| PC125.3                      | POWER     | COPPER | 1    | 3   | 1                  | 6                 |
| PC050.3                      | POWER     | COPPER | 1    | 3   | 6                  | 10                |
| PC20.2                       | POWER     | COPPER | 1    | 2   | 12                 | 12                |
| PC002.0                      | POWER     |        | 1    |     |                    | 1"                |
| PC004.0                      | POWER     |        | 1    |     |                    | 1-1/2"            |

GENERAL NOTES:  
- GROUND CONDUCTOR SHALL BE DELETED ON SERVICE ENTRANCE CONDUCTORS.  
- SIZE ALL CONDUITS IN ACCORDANCE WITH NEC CHAPTER 9, TABLE 1.

KEYED NOTES:  
(1) REFER TO LATEST ADOPTED VERSION OF NEC ARTICLE 310.16 FOR 75C RATED COPPER.  
(2) 200% NEUTRAL (OR 2 NEUTRAL CONDUCTORS).  
(3) AMPACITY DERATED TO 80% DUE TO (4-6) CURRENT CARRYING CONDUCTORS IS BASED ON NEC 310.15(C)(1).  
(4) ALL UNDERGROUND CONDUIT AND CONDUCTORS SHALL BE INSTALLED PER SHEET E501 DETAIL E.  
(5) CONDUIT SIZE SHOWN SHALL BE USED UNLESS NOTED IN DRAWING. ALL CONDUIT SHALL BE IN COMPLIANCE PER NEC 2023.

| ELECTRICAL EQUIPMENT SCHEDULE |  |          |                                |                    |  |
|-------------------------------|--|----------|--------------------------------|--------------------|--|
| (X)                           | DESCRIPTION  | QUANTITY | MODEL / SPECIFICATION          | MANUFACTURER       | COMMENTS                               |
| 1                             | PANEL LP1, 120/240V, 10, 3-WIRE, 125A MAIN CB CU BUS 10 KAIC, 30 CIRCUIT | 1        | 16010                          |                    |  |
| 2                             | GENERAL DUTY FUSED DISCONNECT, 30A, 120/240V, 2-POLE, FUSED AT 20 AMPS   | 1        | 16010                          |                    |  |
| 3                             | EXPLOSION PROOF FUEL SWITCH  | 1        | DSDX910                        | EATON OR EQUAL     | LOCKABLE AND TAMPER PROOF.             |
| 4                             | ELECTRICAL PRECAST PULL BOX, 12"x12"x6"                                  | 2        | OLDCASTLE POLYMER 1212 / 16010 | OLDCASTLE OR EQUAL | LID SHALL BE ENGRAVED WITH ELECTRICAL. |

|  |          |       |         |           |
|--|----------|-------|---------|-----------|
| REV NO.  | COMMENT  | DATE  |         |           |
|  Know what's below.<br>Call before you dig.<br>1-800-662-4111 |          |       |         |           |
|  SUNRISE<br>ENGINEERING                                       |          |       |         |           |
| 6875 SOUTH 900 EAST<br>SALT LAKE CITY, UTAH 84047<br>TEL 801.523.0100 • FAX 801.523.0990<br>www.sunrise-eng.com                                    |          |       |         |           |
| OGDEN CITY   |          |       |         |           |
| EL MONTE GOLF COURSE SHED  |          |       |         |           |
| ELECTRICAL   |          |       |         |           |
| ONE-LINE & SCHEDULES   |          |       |         |           |
| SEI NO.  | DESIGNED | DRAWN | CHECKED | SHEET NO. |
| S  | KRD      | GKP   | JRK     | 2 of 6    |
| E201   |          |       |         |           |



#### SHEET NOTES:

1. THE CONTRACTOR WILL BE RESPONSIBLE TO LOCATE ALL EXISTING UNDERGROUND UTILITIES BEFORE ANY EXCAVATION IS PERFORMED. ANY DAMAGE TO EXISTING UTILITIES SHALL BE REPAIRED TO NEW CONDITION OR REPLACED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
2. NOT ALL CONDUITS ARE SHOWN. REFER TO CONDUIT AND CONDUCTOR SCHEDULE FOR INDIVIDUAL CONDUIT FILL REQUIREMENTS. CONDUIT LAYOUT SHOWN IS DIAGRAMMATIC ONLY. CONTRACTOR SHALL FIELD ROUTE AS NECESSARY TO ACCOMMODATE FIELD CONDITIONS AND AVOID OTHER STRUCTURES AS REQUIRED.
3. REFER TO DRAWING E201 FOR CONDUIT AND CONDUCTOR IDENTIFICATION.
4. DENOTES ELECTRICAL EQUIPMENT IDENTIFICATION. REFER TO DRAWING E201 FOR ELECTRICAL EQUIPMENT SCHEDULE.

#### KEY NOTES


1. CONTRACTOR SHALL COORDINATE WITH OWNER AND CONNECT TO EXISTING ELECTRICAL PANEL IN EXISTING CLUBHOUSE BUILDING. CONTRACTOR SHALL PROVIDE ALL CONDUIT, CONDUCTOR, BUILDING PENETRATIONS, CONDUIT SEALS AND ALL REQUIRED ACCESSORIES FOR AN OPERABLE SYSTEM.
2. BUILDING LOCATION IS APPROXIMATE. COORDINATE WITH CIVIL PLANS FOR EXACT LOCATION, PAD AND GRADING WORK TO BE PERFORMED.
3. FUEL TANK TO BE MOVED BY OWNER. COORDINATE WORK WITH OWNER PRIOR TO INSTALLATION FOR FINAL LOCATIONS AND STAGING.
4. CONTRACTOR SHALL PROVIDE ALL MOUNTING HARDWARE OR STAND FOR NEW FUEL SHUTOFF SWITCH WITH A LOCKABLE COVER, AT THE FUEL TANK. CONTRACTOR SHALL INSTALL A COMPLETE FUNCTIONAL SYSTEM WITH ALL NECESSARY SEAL OFFS AND OFFSETS PER NEC.
5. COORDINATE ALL ASPHALT CUTS WITH OWNER PRIOR TO WORK BEING PERFORMED. PATCHES ARE TO BE REPAIRED BACK TO OGDEN CITY STANDARDS AND SPECIFICATIONS.
6. CONTRACTOR SHALL LOCATE AND INSPECT EXISTING ELECTRICAL CONDUIT SYSTEM TO EXISTING BUILDING. INTERCEPT CONDUIT AT THIS LOCATION AND TIE INTO NEW BUILDING SERVICE. CONDUIT SHALL BE INSPECTED FOR NEC COMPLIANCE AND A MANDREL SHALL BE PULLED THROUGH EXISTING CONDUIT TO ENSURE SUITABILITY FOR USE. REPLACE CONDUIT IF DAMAGED OR UNDERSIZED.
7. CONDUIT ONLY. CONTRACTOR SHALL INSTALL PULL STRING AND CAP FOR FUTURE USE.
8. CONDUITS TO BE INSTALLED IN JOINT TRENCH WITH WATER LINE SEE CIVIL PLANS. MAINTAIN MIN OF 12" OF SEPARATION BETWEEN ELECTRICAL CONDUIT AND WATER LINE.
9. TIE TO EXISTING PULL AND VALVE BOXES AS DIRECTED BY OWNER.


| REV NO. | COMMENT                              | DATE   |
|---------|--------------------------------------|--|
|         | <b>SUNRISE</b><br><b>ENGINEERING</b> | P:\ogden city\000000_el monte golf course\04 Dwg\03 Electrical Site Plan.dwg Jan 16, 2026 11:33am gatlin.penne |

OGDEN CITY

EL MONTE GOLF COURSE SHED  
ELECTRICAL  
SITE PLAN

| SEI NO. | DESIGNED | DRAWN | CHECKED | SHEET NO. |
|---------|----------|-------|---------|-----------|
| S       | KRD      | GKP   | JRK     | 3 of 6    |
| E301    |          |       |         |           |





**SHEET NOTES:**

1. CONTRACTOR TO COMPLY WITH GENERAL ELECTRICAL REQUIREMENTS ON DRAWING E100.
2. CONDUITS SHOWN ARE SCHEMATIC ONLY. CONTRACTOR SHALL FIELD ROUTE CONDUIT AS NECESSARY TO AVOID OBSTACLES AND OTHER EQUIPMENT.
3. NOT ALL CONDUITS ARE SHOWN FOR CLARITY. REFER TO CONDUIT AND CONDUCTOR SCHEDULE FOR ADDITIONAL CIRCUITING INFORMATION.
4. SEE DRAWING E201 FOR CONDUIT AND CONDUCTOR SCHEDULE.
5.  DENOTES ELECTRICAL EQUIPMENT IDENTIFICATION. REFER TO DRAWING E201 FOR ELECTRICAL EQUIPMENT SCHEDULE.
6. PROVIDE LIGHTNING PROTECTION PER SPECIFICATION 16065SP AND DRAWING E100.




Know what's below.  
Call before you dig.  
1-800-662-4111

|  |         |      |
|--|---------|------|
| REV NO.  | COMMENT | DATE |
|  <b>SUNRISE</b><br>ENGINEERING                                      |         |      |
| 6875 SOUTH 900 EAST<br>SALT LAKE CITY, UTAH 84047<br>TEL 801.523.0100 • FAX 801.523.0990<br><a href="http://www.sunrise-eng.com">www.sunrise-eng.com</a> |         |      |


OGDEN CITY

EL MONTE GOLF COURSE SHED  
ELECTRICAL  
LIGHTING & RECEPTACLE PLAN


|         |                 |              |                |                     |      |
|---------|-----------------|--------------|----------------|---------------------|------|
| SEI NO. | DESIGNED<br>KRD | DRAWN<br>GKP | CHECKED<br>KRD | SHEET NO.<br>5 of 6 | E402 |
|---------|-----------------|--------------|----------------|---------------------|------|

| ELECTRICAL LIGHTING FIXTURE SCHEDULE  |   |          |   |                            |  |
|---|---|----------|---|----------------------------|--|
| ITEM #  | DESCRIPTION                               | QUANTITY | MODEL / SPECIFICATION                     | MANUFACTURER               | COMMENTS   |
|  A | CSS L96 8000 LUMEN STRIP LIGHTING FIXTURE | 18       | CSS L96 8000LM UVOLT 40K 80CRI 76W        | LITHONIA OR APPROVED EQUAL |  |
|  B | D-SERIES EXTERIOR LED WALL LUMINAIRE      | 4        | DSXW1 LED 10C 700 40K T4M MVOLT DDBXB 26W | LITHONIA OR APPROVED EQUAL | OPTIONAL PHOTOCELL (PE) TO BE PROVIDED WITH LIGHTING FIXTURE |


**A** ELECTRICAL LIGHTING AND RECEPTACLE PLAN  
 ~ SCALE: 1" = 40" AT SHEET SIZE 22" x 34"




**A** DETAIL - GROUND WELL  
N.T.S.




**B** DETAIL - NAMEPLATE  
N.T.S.




**C** DETAIL - CONDUIT MOUNT  
N.T.S.



**D** DETAIL - UFER CONCRETE ENCASED  
N.T.S.



1. WARNING TAPE MUST BE PLACED ON TOP OF CONDUIT (5 MILS THICKNESS)
2. ALL TRENCHES MUST BE INSPECTED PRIOR TO BACKFILLING
3. TRENCHES SHOULD BE SPOT BACKFILLED TO PREVENT MOVEMENT OF TAPE DURING BACKFILL.
4. SELECT BACKFILL MUST BE COMPACTED IN 1 FOOT LIFTS TO PREVENT SETTLING.



**F** CONDUIT PENETRATION  
N.T.S.

|  |              |           |             |                  |
|--|--------------|-----------|-------------|------------------|
| REV NO.  | COMMENT      | DATE      |             |                  |
|  Know what's below.<br>Call before you dig.<br>1-800-662-4111   |              |           |             |                  |
|  <b>SUNRISE</b><br>ENGINEERING<br>6875 SOUTH 900 EAST<br>SALT LAKE CITY, UTAH 84047<br>TEL 801.523.0100 • FAX 801.523.0990<br>www.sunrise-eng.com |              |           |             |                  |
| OGDEN CITY   |              |           |             |                  |
| EL MONTE GOLF COURSE SHED<br>ELECTRICAL<br>DETAILS   |              |           |             |                  |
| SEI NO. S  | DESIGNED KRD | DRAWN GKP | CHECKED JRK | SHEET NO. 6 of 6 |
| E501   |              |           |             |                  |

## Builder/Contractor Responsibilities

Drawing Validity- These drawings, supporting structural calculations and design certification are based on the order documents as of the date of these drawings. These documents describe the material supplied by the manufacturer as of the date of these drawings. Any changes to the order documents after the date on these drawings may void these drawings, supporting structural calculations and design certification. The Builder/Contractor is responsible for notifying the building authority of all changes to the order documents which result in changes to the drawings, supporting structural calculations and design certification.

Builder Acceptance of Drawings- Approval of the manufacturer's drawings and design data affirms that the manufacturer has correctly interpreted and applied the requirements of the order documents and constitutes Builder/Contractor acceptance of the manufacturer's interpretations of the order documents and standard product specifications, including its design, fabrication and quality criteria standards and tolerances. (AISC COSP June 2016 Section 4.4.1)

Code Official Approval- It is the responsibility of the Builder/Contractor to ensure that all project plans and specifications comply with the applicable requirements of any governing building authority. The Builder/Contractor is responsible for securing all required approvals and permits from the appropriate agency as required.

Building Erection - The Builder/Contractor is responsible for all erection of the steel and associated work in compliance with the Metal Building Manufacturers drawings. Temporary supports, such as temporary guys, braces, false work or other elements required for erection will be determined, furnished and installed by the erector (AISC COSP June 2016 Section 7.10.3).

Discrepancies - Where discrepancies exist between the Metal Building plans and plans for other trades, the Metal Building plans will govern. (AISC COSP June 2016 Section 3.3)

Materials by Others - All interface and compatibility of any materials not furnished by the manufacturer are the responsibility of and to be coordinated by the Builder/Contractor or A/E firm. Unless specific design criteria concerning any interface between materials if furnished as a part of the order documents, the manufacturer's assumptions will govern.

Modification of the Metal Building from Plans - The Metal Building supplied by the manufacturer has been designed according to the Building Code and specifications and the loads shown on this drawing. Modification of the building configuration, such as removing wall panels or braces, from that shown on these plans could affect the structural integrity of the building. The Metal Building Manufacturer or a licensed Structural Engineer should be consulted prior to making any changes to the building configuration shown on these drawings. The Metal Building Manufacturer will assume no responsibility for any loads applied to the building not indicated on these drawings.

Foundation Design- The Metal Building Manufacturer is not responsible for the design, materials and workmanship of the foundation. Anchor rod plans prepared by the manufacturer are intended to show only location, diameter and projection of the anchor rods required to attach the Metal Building System to the foundation. It is the responsibility of the end customer to ensure that adequate provisions are made for specifying rod embedment, bearing values, tie rods and/or other associated items embedded in the concrete foundation, as well as foundation design for the loads imposed by the Metal Building System, other imposed loads, and the bearing capacity of the soil and other conditions of the building site. (MBMA 06 Sections 3.2.2 and A3)

Shimming - In accordance with Section 6.10 of Chapter 4 Common Industry Practices in the Metal Building Systems Manual, shimming is a normal part of erection and is not subject to claim.

| Building Descriptions |        |        |        |
|-----------------------|--------|--------|--------|
| Building ID           | Width  | Length | Height |
| Building A            | 40'-0" | 80'-0" | 16'-0" |



Download panel installation manuals from:  
www.CBBmanuals.com

Descargue los manuales de instalación del panel desde:  
www.CBBmanuals.com



Sales: 877.268.3553  
Muellerinc.com

## DESIGN CRITERIA

Building Code .....: 2021 IBC  
Building Risk Category .....: Normal (Risk Category II)  
Roof Dead Load  
Superimposed .....: 2.22 psf  
Collateral .....: 1.00 psf  
(1.00 psf Other)  
Roof Live Load .....: 20.00 psf reduction allowed

Snow  
Ground Snow Load (Pg) .....: 43.00 psf  
Snow Importance Factor (I) .....: 1.00  
Snow Exposure Factor (Ce) .....: 0.90  
Thermal Factor (Ct) .....: 1.00  
Slope Factor (Cs) .....: 1.00  
Sloped Roof Snow (Ps) .....: 27.09 psf  
Minimum Roof Snow Load (Pm) .....: 30.00 psf

Wind  
Ultimate Wind Speed (Vult) .....: 110 mph  
Nominal Wind Speed (Vasd) .....: 85 mph (IBC section 1609.3.1)  
Serviceability Wind Speed .....: 74 mph  
Ground Elevation Factor .....: 0.85 (4458 ft ASL)  
Wind Exposure Category .....: C  
Exposure Coefficient (MMFRS) .....: 0.860  
Enclosure Classification .....: Enclosed Building  
Internal Pressure Coef (Gcp) .....: 0.187-0.18  
Unfactored Wall Loads for components not provided by building manufacturer  
Zone 5 Areas (within 4.00' of corner) .....: 20.82 psf pressure -27.76 psf suction  
Zone 4 Areas (away from corners) .....: 20.82 psf pressure -22.55 psf suction  
These values are the maximum values required based on a 10 sq ft area.  
Components with larger areas may have lower wind loads.

Seismic  
Seismic Importance Factor (Ie) .....: 1.00  
Seismic Design Category .....: D  
Soil Site Class .....: D Stiff Soil (Default)  
Ss .....: 1.351 g Sds .....: 1.081 g  
S1 .....: 0.498 g Sd1 .....: 0.598 g  
Analysis Procedure .....: Equivalent Lateral Force  
Column Line .....: 1-5 SWA & SWC  
Basic Force Resisting System .....: C4 B3  
Response Modification Coefficient (R) .....: 3.50 3.25  
Seismic Response Coefficient (Cs) .....: 0.309 0.333  
Design Base Shear in kips (V) .....: 6.32 6.26  
Basic Structural System (from ASCE 7-16 Table 12.2-1)  
B3 - Ordinary Steel Concentrically Braced Frame  
C4 - Ordinary Steel Moment Frame

## DEFLECTION CRITERIA

The material supplied by the manufacturer has been designed with the following minimum deflection criteria. The actual deflection may be less depending on actual load and actual member length.

## BUILDING DEFLECTION LIMITS .....: BLDG-A

| Roof Limits             | Rafters | Purlins | Panels |
|-------------------------|---------|---------|--------|
| Live: L/                | 180     | 150     | 60     |
| Snow: L/                | 180     | 180     | 60     |
| Serviceability Wind: L/ | 180     | 180     | 60     |
| Total Gravity: L/       | 120     | 120     | 60     |
| Total Uplift: L/        | N/A     | N/A     | 60     |

| Frame Limits            | Sidesway |
|-------------------------|----------|
| Live: H/                | 60       |
| Snow: H/                | 60       |
| Serviceability Wind: H/ | 60       |
| Seismic Drift: H/       | 40       |
| Total Gravity: H/       | 60       |
| Service Seismic: H/     | 40       |

| Wall Limits               | Limit |
|---------------------------|-------|
| Total Wind Panels: L/     | 60    |
| Total Wind Girts: L/      | 90    |
| Total Wind EW Columns: L/ | 120   |

The Service Seismic limit as shown here is at service level loads.

| 1/2" DIA. A325 BOLT GRIP TABLE   |             |
|--|-------------|
| GRIP   | LENGTH      |
| 0 TO 9/16"   | 1 1/4" F.T. |
| Over 9/16" TO 1 1/16"  | 1 3/4" F.T. |
| Over 1 1/16" TO 1 5/16"  | 2"          |
| Over 1 5/16" TO 1 9/16"  | 2 1/4"      |
| Over 1 9/16" TO 1 13/16"   | 2 1/2"      |
| Over 1 13/16" TO 2 1/16"   | 2 3/4"      |
| LOCATIONS OF BOLTS LONGER THAN 2 3/4" NOTED ON ERECTION DRAWINGS                               |             |
| ADD 5/32" FOR EACH WASHER TO MATERIAL THICKNESS TO DETERMINE GRIP. F.T. DENOTES FULLY THREADED |             |

NOTE: FULL THREAD ENGAGEMENT IS DEEMED TO HAVE BEEN MET WHEN THE END OF THE BOLT IS FLUSH WITH THE FACE OF THE NUT.  
WASHER REQUIRED ONLY WHEN SPECIFIED. WASHER MAY BE LOCATED UNDER HEAD OF BOLT, UNDER NUT, OR AT BOTH LOCATIONS NOTED ON ERECTION DRAWINGS. ADD 5/32" FOR EACH WASHER TO MATERIAL THICKNESS TO DETERMINE GRIP.

Cornerstone Building Brands  
13105 Northwest Freeway, Suite 500  
Houston, TX 77040  
cornerstonebuildingbrands.com

Field Services: 844.840.4603  
field.services@cornerstone-buildingbrands.com

## Drawing Index

| Page   | Description                   | Cr'd |
|--------|-------------------------------|------|
| F1     | Anchor Rod Setting Plan       |      |
| F2     | Anchor Rod Details            |      |
| F3-F4  | Reactions                     |      |
| E1     | Cover Sheet                   |      |
| E2     | Primary Steel                 |      |
| E3     | Roof Framing                  |      |
| E4     | Roof Sheeting RPA & RPC       |      |
| E5     | Sidewall Framing Sheeting SWA |      |
| E6     | Sidewall Framing Sheeting SWC |      |
| E7     | Endwall Framing Sheeting EWB  |      |
| E8     | Endwall Framing Sheeting EWD  |      |
| E9     | Cross Section at Frame Line 1 |      |
| E10    | Cross Section at Frame Line 2 |      |
| E11    | Cross Section at Frame Line 3 |      |
| E12    | Cross Section at Frame Line 4 |      |
| E13    | Cross Section at Frame Line 5 |      |
| E14    | Connection Detail             |      |
| R1-R3  | Erection Guides               |      |
| R4-R12 | Construction Drawings         |      |


|  |  |   |
|--|--|---|
| FORTIFY<br>BUILDING SOLUTIONS              | Project Name & Location:<br>13105 Northwest Freeway, Suite 500<br>Houston, TX 77040<br>cornerstonebuildingbrands.com                                 | Issued For Construction: <input checked="" type="checkbox"/>  |
|  | MARA BROWN<br>1300 VALLEY DR<br>ODGEN, UT 84401-0808   |   |
| MUeller<br>METAL BUILDINGS, ROOFING & MORE | Customer:<br>CITY OF OGDEN-212366<br>2549 WASHINGTON BLVD<br>ODGEN, UT 84401<br>MARA BROWN   | Drawing Status: <input type="checkbox"/> Issued For Approval<br><input type="checkbox"/> Not For Construction<br><input type="checkbox"/> Issued For Permit |
|  | Scale: NOT TO SCALE<br>Drawn by: AXD 12/9/25<br>Checked by: MC 12/15/25<br>Project Engineer: RAR<br>Job Number: 20-B-91454<br>Sheet Number: E1 of 14 |   |

The engineer whose seal appears herein is employed by or is contracted to provide engineering services for the manufacturer, Cornerstone Building Brands or one of its affiliates, for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project.

Kaushikumar J. Patel, P.E.  
KAUSHIKUMAR J. PATEL, P.E.  
UTAH P.E. 12592792-2202

Jan 02, 2026  
This item has been electronically signed and sealed by Kaushikumar J. Patel, P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd party. Certificate Authority on any electronic copy.





### Primary Steel


SWC  
Bldg A  
EWD  
SWA  
Key Plan

| Customer:   | 13105 Northwest Freeway, Suite 500<br>Houston, TX 77040<br>cornerstonebuildingbrands.com | Project Name & Location: | MARA BROWN<br>1300 VALLEY DR<br>ODGEN, UT 84401-0808 | Revision:         | By           | Date:         | Description | ckd |
|---|--|--------------------------|--|-------------------|--------------|---------------|-------------|-----|
| <b>MUELLER</b><br>METAL BUILDINGS, DOORSETS & MORE  |  |                          |  |                   |              |               |             |     |
| Customer:   | CITY OF OGDEN - 212366<br>2549 WASHINGTON BLVD<br>OGDEN, UT 84401<br>MARA BROWN          | Project Engineer:        | RAR  | Scale:            | NOT TO SCALE | Drawn by:     | AXD 12/9/25 |     |
|   |  | Checked by:              | MC 12/15/25  | Drawn by:         |              | Checked by:   |             |     |
|   |  | Job Number:              | 20-B-91454   | Project Engineer: |              | Job Number:   |             |     |
|   |  | Sheet Number:            | E2 of 14   | Scale:            |              | Sheet Number: |             |     |
| <p>The engineer whose seal appears hereon is employed by or is contracted to provide engineering services for the manufacturer, Cornerstone Building Brands or one of its affiliates, for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project.</p> <p>KAUSHIKKUMAR J. PATEL, P.E.<br/>UTAH P.E. 12592792-2202</p> |  |                          |  |                   |              |               |             |     |

Jan 02, 2026  
This item has been electronically signed and sealed by Kaushikumar J. Patel, P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.



- - DENOTES: CLIP LOCATION  
SC90 AT 8" PURLINS  
SC92 AT 10" PURLINS  
SC94 AT 12" PURLINS



| ZEE SECTION LAP TABLE   |             |   |            |
|---|-------------|---|------------|
| SYMBOL  | LAP LENGTH  | SYMBOL  | LAP LENGTH |
|  | -0'-0 1/4 " |  | 2'-5 3/4 " |
|  | 0'-3 3/4 "  |  | 3'-1 3/4 " |
|  | 1'-5 3/4 "  | REFERS TO CEF01122  |            |

## Roof Framing


| Revision   | Date | Description  | By   | Ck'd  |
|--|------|--|--|---|
| 13105 Northwest Freeway, Suite 500<br>Houston, TX 77040  |      |  |  |   |
| cornerstonebuildingbrands.com  |      |  |  |   |
| <br><b>MUELLER</b><br><small>METAL BUILDINGS, ROOFING &amp; MORE</small>   |      | <b>Project Name &amp; Location:</b><br>MARA BROWN<br>1300 VALLEY DR<br>OGDEN UT 84401-0808 |  | <input checked="" type="checkbox"/> Issued For Construction |
| <b>Customer:</b><br>CITY OF OGDEN-212366<br>2549 WASHINGTON BLVD<br>OGDEN UT 84401<br>MARA BROWN   |      |  | <b>Drawing Status:</b> <input type="checkbox"/> Issued For Approval<br><input type="checkbox"/> Not For Construction | <input type="checkbox"/> Issued For Permit                  |
| <b>Scale:</b> NOT TO SCALE<br><b>Drawn by:</b> AXD 12/9/25<br><b>Checked by:</b> MC 12/15/25<br><b>Project Engineer:</b> RAR<br><b>Job Number:</b> 20-B-91454<br><b>Sheet Number:</b> E3 of 14   |      |  |  |   |
| The engineer whose seal appears hereon is employed by or is contracted to provide engineering services for the manufacturer, Cornerstone Building Brands or one of its affiliates, for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer. The undersigned engineer is not the overall engineer of record for this project. |      |  |  |   |
| KAUSHIKKUMAR J. PATEL, P.E.<br>UTAH P.E. 12592792-2202   |      |  |  |   |

Jan 02, 2026  
Item has been electronically signed and sealed by  
Shikumar J. Patel, P.E. on the date and/or time  
shown using a digital signature. Printed copies of  
document are not considered signed and sealed  
The signature must be verified by a 3rd Party  
Authority on any electronic copy.


## Non-Standard PBR Roof Panel Fasteners

#3A member fasteners are to be used for panel to secondary attachment in lieu of #3 shown on the R Drawings


RPC  
Panel Type = PBR  
Panel Color = GALVALUME PLUS  
Panel Overhang From Outer Steel = 3"



## Roof Sheeting RPA &amp; RPC



| Customer:   | FORTIFY<br>BUILDING SOLUTIONS<br>METAL BUILDINGS, ROOFS & MORE |           |      |
|---|--|-----------|------|
| Project Name & Location:  | MARA BROWN<br>1300 VALLEY DR<br>ODGEN, UT 84401-0808           |           |      |
| Scale:  | NOT TO SCALE   | Revision: | Date |
| Drawn by:   | AXD  | 12/9/25   | By   |
| Checked by:   | MC   | 12/15/25  | Ck'd |
| Project Engineer:   | RAR  |           |      |
| Job Number:   | 20-B-91454   |           |      |
| Sheet Number:   | E4 of 14   |           |      |
| The engineer whose seal appears herein is employed by or is contracted to provide engineering services for the manufacturer, Cornerstone Building Brands or one of its affiliates, for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project. |  |           |      |
| KAUSHIKKUMAR J. PATEL, P.E.<br>UTAH P.E. 12592792-2202  |  |           |      |




This item has been electronically signed and sealed by Kaushikumar J. Patel, P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.

▲ - DENOTES: (4) 1/2" Ø BOLTS AT PURFLIN OR GIRT CONNECTION TO CLIP. REFER TO CF01122


### Non-Standard PBR Wall Panel Fasteners

#17B member fasteners are to be used for panel to secondary attachment in lieu of #17A shown on the R Drawings




Sidewall Framing SWA at Grid Line A

Man door locations identified on civil set



Sidewall Sheeting SWA

PBR Wall Panels  
Panel Coverage = 3'-0"  
Panel Color = S200 DESERT SAND  
Panel Pkg. Req'd. = PBS-3  
Field Cut Panel and Trim as required per Construction Details



| ZEE SECTION LAP TABLE |            |        |                  |
|-----------------------|------------|--------|------------------|
| SYMBOL                | LAP LENGTH | SYMBOL | LAP LENGTH       |
| ◇                     | 0'-0 1/4"  | ◇      | 2'-5 3/4"        |
| ◇                     | 0'-3 3/4"  | ◇      | 3'-1 3/4"        |
| ◇                     | 1'-5 3/4"  |        | REFER TO CF01122 |

|  |  |                          |   |   |
|--|--|--------------------------|---|---|
| FORTIFY<br>BUILDING SOLUTIONS <sup>®</sup>   | 13105 Northwest Freeway, Suite 500<br>Houston, TX 77040<br>cornerstonebuildingbrands.com | Revision                 | Date  | Description   |
|  |  |                          |   |   |
| MUELLER<br>METAL BUILDINGS, DOORS & MORE   | CITY OF OGDEN - 212366<br>2549 WASHINGTON BLVD<br>OGDEN, UT 84401<br>MARA BROWN          | Project Name & Location: |   |   |
|  |  |                          |   |   |
|  |  | Customer:                |   |   |
|  |  | Drawing Status:          | <input type="checkbox"/> Issued For Approval<br><input type="checkbox"/> Not For Construction | <input checked="" type="checkbox"/> Issued For Construction |
|  |  | Drawn by:                | AXD 12/9/25   |   |
|  |  | Checked by:              | MC 12/15/25   |   |
|  |  | Project Engineer:        | RAR   |   |
|  |  | Job Number:              | 20-B-91454  |   |
|  |  | Sheet Number:            | E5 of 14  |   |
| <p>The engineer whose seal appears hereon is employed by or is contracted to provide engineering services for the manufacturer, Cornerstone Building Brands or one of its affiliates, for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project.</p> <p>KALUSHIKKUMAR J. PATEL, P.E.<br/>UTAH P.E. 12592792-2202</p> |  |                          |   |   |


Jan 02, 2026  
This item has been electronically signed and sealed by Kaushikumar J. Patel, P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.




▲ - DENOTES: (4) 1/2" Ø BOLTS AT PURFLIN OR GIRT CONNECTION TO CLIP. REFER TO CF01122

### Non-Standard PBR Wall Panel Fasteners

#17B member fasteners are to be used for panel to secondary attachment in lieu of #17A shown on the R Drawings




Sidewall Framing SWC at Grid Line C



Sidewall Sheeting SWC

| ZEE SECTION LAP TABLE |            |                  |            |
|-----------------------|------------|------------------|------------|
| SYMBOL                | LAP LENGTH | SYMBOL           | LAP LENGTH |
| □                     | 0'-0 1/4"  | □                | 2'-5 3/4"  |
| △                     | 0'-3 3/4"  | △                | 3'-1 3/4"  |
| ○                     | 1'-5 3/4"  | REFER TO CF01122 |            |



|   |  |                                     |      |             |
|---|--|-------------------------------------|------|-------------|
| <b>FORTIFY</b><br>BUILDING SOLUTIONS <sup>®</sup>   | 13105 Northwest Freeway, Suite 500<br>Houston, TX 77040<br>cornerstonebuildingbrands.com                                 | Revision                            | Date | Description |
| <b>MUELLER</b><br>METAL BUILDINGS, DOORS & MORE   | CITY OF OGDEN - 212366<br>2549 WASHINGTON BLVD<br>OGDEN, UT 84401<br>MARA BROWN<br>1300 VALLEY DR<br>ODEN, UT 84401-0808 | Project Name & Location:            |      |             |
| Customer:<br>CITY OF OGDEN - 212366<br>2549 WASHINGTON BLVD<br>OGDEN, UT 84401<br>MARA BROWN  | Issued For Construction  | <input checked="" type="checkbox"/> |      |             |
| Drawing Status:<br>Issued For Approval: <input type="checkbox"/> (Not For Construction) <input type="checkbox"/> Issued For Permit  |  |                                     |      |             |
| Scale: NOT TO SCALE   |  |                                     |      |             |
| Drawn by: AXD 12/9/25   |  |                                     |      |             |
| Checked by: MC 12/15/25   |  |                                     |      |             |
| Project Engineer: RAR   |  |                                     |      |             |
| Job Number: 20-B-91454  |  |                                     |      |             |
| Sheet Number: E6 of 14  |  |                                     |      |             |
| The engineer whose seal appears hereon is employed by or is contracted to provide engineering services for the manufacturer, Cornerstone Building Brands or one of its affiliates, for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project. |  |                                     |      |             |
| KAUSHIKKUMAR J. PATEL, P.E.<br>UTAH P.E. 12592792-2202  |  |                                     |      |             |


Jan 02, 2026  
This item has been electronically signed and sealed by Kaushikumar J. Patel, P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.




### Non-Standard PBR Wall Panel Fasteners

#17B member fasteners are to be used for panel to secondary attachment in lieu of #17A shown on the R Drawings

NOTE: FIELD BEVEL CUT WALL PANELS AT ENDWALLS TO FOLLOW ROOF SLOPE




Endwall Framing EWB at Grid Line 1




PBR Wall Panels  
Panel Coverage = 3'-0"  
Panel Color = S200 DESERT SAND  
Panel Pkg. Reqd. = PBS-1  
Field Cut Panel and Trim as  
required per Construction Details

Endwall Sheeting EWB



|  |   |  |  |   |
|--|---|--|--|---|
| FORTIFY<br>BUILDING SOLUTIONS <sup>®</sup>             | 13105 Northwest Freeway, Suite 500<br>Houston, TX 77040<br>cornerstonebuildingbrands.com  | Revision   | Date   | Description   |
|  |   | By   | Ck'd   |   |
| MUELLER<br>METAL BUILDINGS, ROOFS & MORE               | Customer:<br>CITY OF OGDEN - 212366<br>2549 WASHINGTON BLVD<br>OGDEN, UT 84401<br>MARA BROWN<br>1300 VALLEY DR<br>OGDEN, UT 84401-0808  | Project Name & Location:                         |  |   |
|  |   | <input type="checkbox"/> Issued For Construction | <input type="checkbox"/> Issued For Approval | <input checked="" type="checkbox"/> Issued For Construction |
| Scale: NOT TO SCALE                                    | Drawn by: AXD 12/9/25   | Checked by: MC 12/15/25                          | Project Engineer: RAR                        | Job Number: 20-B-91454                                      |
| Sheet Number: E7 of 14                                 | The engineer whose seal appears hereon is employed by or is contracted to provide engineering services for the manufacturer, Cornerstone Building Brands or one of its affiliates, for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project. |  |  |   |
| KAUSHIKKUMAR J. PATEL, P.E.<br>UTAH P.E. 12592792-2202 |   |  |  |   |




Jan 02, 2026

This item has been electronically signed and sealed by Kaushikumar J. Patel, P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.


### Non-Standard PBR Wall Panel Fasteners

#17B member fasteners are to be used for panel to secondary attachment in lieu of #17A shown on the R Drawings


NOTE: FIELD BEVEL CUT WALL PANELS AT ENDWALLS TO FOLLOW ROOF SLOPE



Endwall Framing EWD at Grid Line 5




Endwall Sheeting EWD



|                 |  |                          |   |
|-----------------|--|--------------------------|---|
| Customer:       | 13105 Northwest Freeway, Suite 500<br>Houston, TX 77040<br>cornerstonebuildingbrands.com                 | Project Name & Location: | MARA BROWN<br>1300 VALLEY DR<br>ODGEN, UT 84401-0808  |
| Drawing Status: | <input checked="" type="checkbox"/> Issued For Approval<br><input type="checkbox"/> Not For Construction | Issued For Construction  | <input checked="" type="checkbox"/> Issued For Permit |
| Scale:          | NOT TO SCALE   | Date:                    | 12/9/25   |
| Drawn by:       | AXD  | Checked by:              | MC  |
| Checked by:     | 12/15/25   | Project Engineer:        | RAR   |
| Job Number:     | 20-B-91454   | Sheet Number:            | E8 of 14  |

The engineer whose seal appears hereon is employed by or is contracted to provide engineering services for the manufacturer, Cornerstone Building Brands or one of its affiliates, for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project.

KAUSHIKKUMAR J. PATEL, P.E.  
UTAH P.E. 12592792-2202




Jan 02, 2026

This item has been electronically signed and sealed by Kaushikumar J. Patel, P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.

GENERAL NOTES  
FRAME CLEARANCES SHOWN ARE APPROXIMATE AND  
MAY VARY DUE TO CONDITIONS (DEFLECTION).  
VERTICAL CLEARANCE DIMENSIONS ARE FROM  
FINISHED FLOOR REFERENCE ELEVATION.


| APPROXIMATE MEMBER WEIGHTS |        |
|----------------------------|--------|
| PART MARK                  | WEIGHT |
| R1E                        | 176    |
| R7E                        | 218    |
| C1E                        | 243    |
| C2E                        | 243    |
| CSW2A                      | 256    |



Cross Section at Frame Line 1

| PRIMARY BUILT-UP MEMBER SIZES |                   |                  |           |             |           |         |
|-------------------------------|-------------------|------------------|-----------|-------------|-----------|---------|
| MARK                          | OUTSIDE FLG THICK | INSIDE FLG THICK | WEB THICK | START DEPTH | END DEPTH |         |
| (1)                           | 0.2500            | 5"               | 0.2500    | 5"          | 0.1340    | 9.0000  |
| (2)                           | 0.2500            | 5"               | 0.2500    | 5"          | 0.1340    | 10.0000 |
| (3)                           | 0.2500            | 5"               | 0.2500    | 5"          | 0.1340    | 8.0625  |
| (4)                           | 0.2500            | 5"               | 0.2500    | 5"          | 0.1340    | 8.0000  |


*Kaushikumar Patel*  
PROFESSIONAL ENGINEER  
No. 12592792  
Jan 02, 2026  
This item has been electronically signed and sealed by Kaushikumar J. Patel, P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.



|   |                                 |                                     |                       |                          |
|---|---------------------------------|-------------------------------------|-----------------------|--------------------------|
| <b>FORTIFY</b><br>BUILDING SOLUTIONS <sup>®</sup>   | Cornerstone Building Brands 500 | Revision                            | Date                  | Description              |
|   | Northwest Freeway, Suite 500    |                                     |                       |                          |
|   | CornerstoneBuildingBrands.com   |                                     |                       |                          |
| <b>MUELLER</b><br>METAL BUILDINGS, DOORS & MORE   | Project Name & Location:        |                                     |                       |                          |
|   | CITY OF OGDEN - 212366          |                                     |                       |                          |
|   | 2549 WASHINGTON BLVD            |                                     |                       |                          |
|   | OGDEN, UT 84401                 |                                     |                       |                          |
|   | MARA BROWN                      |                                     |                       |                          |
|   | 1300 VALLEY DR                  |                                     |                       |                          |
|   | ODGEN, UT 84401-0808            |                                     |                       |                          |
| Customer:<br>Drawing Status:  | Issued For Approval:            | <input checked="" type="checkbox"/> | Not For Construction: | <input type="checkbox"/> |
|   | Issued For Construction:        | <input type="checkbox"/>            | Issued For Permit:    | <input type="checkbox"/> |
| Scale: NOT TO SCALE   | Drawn by: AXD                   | 12/9/25                             | Checked by: MC        | 12/15/25                 |
| Project Engineer: RAR   | Job Number: 20-B-91454          |                                     |                       |                          |
| Sheet Number: E9 of 14  |                                 |                                     |                       |                          |
| The engineer whose seal appears hereon is employed by or is contracted to provide engineering services for the manufacturer, Cornerstone Building Brands or one of its affiliates, for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project. |                                 |                                     |                       |                          |
| KAUSHIKUMAR J. PATEL, P.E.<br>UTAH P.E. 12592792-2202   |                                 |                                     |                       |                          |

GENERAL NOTES  
FRAME CLEARANCES SHOWN ARE APPROXIMATE AND  
MAY VARY DUE TO CONDITIONS (DEFLECTION).

VERTICAL CLEARANCE DIMENSIONS ARE FROM FINISHED FLOOR REFERENCE ELEVATION.



## Cross Section at Frame Line 2

| PRIMARY BUILT-UP MEMBER SIZES |                     |       |        |                    |           |
|-------------------------------|---------------------|-------|--------|--------------------|-----------|
| DE FLG<br>WIDTH               | INSIDE FLG<br>THICK | WIDTH | THICK  | WEB<br>START DEPTH | END DEPTH |
| 5"                            | 0.2500              | 5"    | 0.1340 | 8,0000             | 11,5471   |
| 5"                            | 0.2500              | 5"    | 0.2500 | 11,5471            | 13,0000   |
| 5"                            | 0.2500              | 5"    | 0.1340 | 10,5000            | 12,5000   |


Jan 02, 2026

This item has been electronically signed and sealed by  
Hushikumar J. Patel, P.E. on the date and/or time  
stamp shown using a digital signature. Printed copies of  
this document are not considered signed and sealed  
until the signature must be verified by a 3rd Party  
Certificate Authority on any electronic copy.

A circular professional engineer license seal. The outer ring contains the text "PROFESSIONAL ENGINEER" at the top and "STATE OF UTAH" at the bottom, separated by a decorative border. The inner circle contains the text "No. 12592792" on the top line, "KAUSHIKUMAR J." on the middle line, and "PATEL" on the bottom line.

GENERAL NOTES  
FRAME CLEARANCES SHOWN ARE APPROXIMATE AND  
MAY VARY DUE TO CONDITIONS (DEFLECTION).

VERTICAL CLEARANCE DIMENSIONS ARE FROM FINISHED FLOOR REFERENCE ELEVATION.



### Cross Section at Frame Line 3

| PRIMARY BUILT-UP MEMBER SIZES |                     |       |        |                    |           |
|-------------------------------|---------------------|-------|--------|--------------------|-----------|
| DE FLG<br>WIDTH               | INSIDE FLG<br>THICK | WIDTH | THICK  | WEB<br>START DEPTH | END DEPTH |
| 5"                            | 0.2500              | 5"    | 0.1340 | 8,0000             | 11,5471   |
| 5"                            | 0.2500              | 5"    | 0.2500 | 11,5471            | 13,0000   |
| 5"                            | 0.2500              | 5"    | 0.1340 | 10,5000            | 12,5000   |


Jan 02, 2026

A circular seal for a professional engineer. The outer ring contains the text "PROFESSIONAL ENGINEER" at the top and "STATE OF UTAH" at the bottom. The inner circle contains the text "No. 12592792" on the top line, "KAUSHIKUMAR J." on the middle line, and "PATEL" on the bottom line.

GENERAL NOTES  
FRAME CLEARANCES SHOWN ARE APPROXIMATE AND  
MAY VARY DUE TO CONDITIONS (DEFLECTION).


VERTICAL CLEARANCE DIMENSIONS ARE FROM  
FINISHED FLOOR REFERENCE ELEVATION.

| APPROXIMATE MEMBER WEIGHTS |  | Ck'd  |
|----------------------------|--|---|
| PART MARK                  | WEIGHT                                       |   |
| R6F                        | 322  |   |
| C4F                        | 278  |   |
|                            |  | By  |
|                            |  | Description   |
|                            |  | Revision  |
|                            |  | Date  |
|                            |  | Project Name & Location:  |
|                            |  | CITY OF OGDEN - 212366<br>2549 WASHINGTON BLVD<br>OGDEN, UT 84401 |
|                            |  | MARA BROWN<br>1300 VALLEY DR<br>OGDEN, UT 84401-0808              |
|                            |  | Customer:   |
|                            |  | MARA BROWN  |
|                            |  | Drawing Status:   |
|                            | <input type="checkbox"/> Issued For Approval | <input checked="" type="checkbox"/> Issued For Construction       |
|                            | <input type="checkbox"/> Not For Permit      | <input type="checkbox"/> Issued For Permit                        |



GENERAL NOTES  
FRAME CLEARANCES SHOWN ARE APPROXIMATE AND  
MAY VARY DUE TO CONDITIONS (DEFLECTION).  
VERTICAL CLEARANCE DIMENSIONS ARE FROM  
FINISHED FLOOR REFERENCE ELEVATION.


| APPROXIMATE MEMBER WEIGHTS |        |
|----------------------------|--------|
| PART MARK                  | WEIGHT |
| R2E                        | 176    |
| R7E                        | 218    |
| C1E                        | 243    |
| C2E                        | 243    |
| CSW1A                      | 256    |



Cross Section at Frame Line 5

## PRIMARY BUILT-UP MEMBER SIZES

| MARK | OUTSIDE FLG |       | INSIDE FLG |       | WEB THICK | START DEPTH | END DEPTH |
|------|-------------|-------|------------|-------|-----------|-------------|-----------|
|      | THICK       | WIDTH | THICK      | WIDTH |           |             |           |
| ①    | 0.2500      | 5"    | 0.2500     | 5"    | 0.1340    | 9.0000      | 9.0000    |
| ②    | 0.2500      | 5"    | 0.2500     | 5"    | 0.1340    | 10.0000     | 8.0046    |
| ③    | 0.2500      | 5"    | 0.2500     | 5"    | 0.1340    | 8.0625      | 18.0000   |
| ④    | 0.2500      | 5"    | 0.2500     | 5"    | 0.1340    | 8.0000      | 8.0000    |



Jan 02, 2026  
This item has been electronically signed and sealed by Kaushikumar J. Patel, P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.

**FORTIFY**  
BUILDING SOLUTIONS  
Cornerstone Building Brands Suite 500  
Northwest Freeway, Houston, TX 77040  
cornerstonebuildingbrands.com

Project Name & Location:  
MARA BROWN  
1300 VALLEY DR  
ODGEN, UT 84401-0808


Customer:  
CITY OF OGDEN - 212366  
2549 WASHINGTON BLVD  
ODGEN, UT 84401  
MARA BROWN  
Drawing Status:  Issued For Approval  Not For Construction  Issued For Permit

Scale: NOT TO SCALE  
Drawn by: AXD 12/9/25  
Checked by: MC 12/15/25  
Project Engineer: RAR  
Job Number: 20-B-91454  
Sheet Number: E13 of 14


The engineer whose seal appears hereon is employed by or is contracted to provide engineering services for the manufacturer, Cornerstone Building Brands or one of its affiliates, for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project.

KAUSHIKUMAR J. PATEL, P.E.  
UTAH P.E. 12592792-2202


**CONNECTION CODES**  
(FOR TOP AND BOTTOM BOLT PATTERN)




CONNECTION 1B, 1I OR 1P




CONNECTION 1F




CONNECTION 1E




CONNECTION 2B, 2I OR 2P




CONNECTION 2F




CONNECTION 2E




CONNECTION 3B, 3I OR 3P




CONNECTION 3F




CONNECTION 3E



CONNECTION 4B, 4I OR 4P



CONNECTION 4F



CONNECTION 4E

**4 E /2 E H**  
CONNECTION DESIGNATION  
BLANK = STANDARD CONNECTION  
H = HEAVY CONNECTION  
BOTTOM CONNECTION CODE  
BOTTOM QUANTITY OF BOLT ROWS  
TOP CONNECTION CODE  
TOP QUANTITY OF BOLT ROWS  
**CONNECTION CODE FORMAT**

**CONNECTION CODE DESCRIPTION**

B = THIS DESCRIPTION CODE IS USED TO DEFINE SHEAR CONNECTIONS. BOLTS ARE LOCATED INSIDE THE TOP FLANGE AND CONNECTION PLATE IS RECESSED 1/8" BELOW THE TOP FLANGE. CONNECTION PLATE LENGTH MUST BE A MINIMUM OF HALF THE RAFTER WEB DEPTH AND SHALL NOT EXCEED THE RAFTER TOTAL DEPTH.

E = THIS DESCRIPTION CODE IS USED TO DEFINE MOMENT CONNECTIONS. BOLTS ARE LOCATED WITH ONE SET OUTSIDE THE TOP OR BOTTOM FLANGE AND THE REMAINING SETS ARE LOCATED INSIDE THE TOP OR BOTTOM FLANGE.

F = THIS DESCRIPTION CODE IS USED TO DEFINE MOMENT CONNECTIONS. BOLTS ARE LOCATED INSIDE THE TOP OR BOTTOM FLANGE AND CONNECTION PLATE PROJECTS 1/2" BEYOND THE TOP OR BOTTOM FLANGE.


I = THIS DESCRIPTION CODE IS USED TO DEFINE MOMENT CONNECTIONS. BOLTS ARE LOCATED INSIDE THE TOP OR BOTTOM FLANGE AND CONNECTION PLATE IS RECESSED 1/8" BELOW THE TOP OR BOTTOM FLANGE.

P = THIS DESCRIPTION CODE IS USED TO DEFINE SHEAR CONNECTIONS. BOLTS ARE LOCATED INSIDE THE TOP FLANGE AND CONNECTION PLATE IS RECESSED 1/8" BELOW THE TOP FLANGE. CONNECTION PLATE LENGTH MUST BE A MINIMUM OF HALF THE RAFTER WEB DEPTH AND SHALL NOT EXCEED THE RAFTER TOTAL DEPTH.

4X = THIS DESCRIPTION CODE IS USED TO DEFINE MOMENT CONNECTIONS. BOLTS ARE LOCATED WITH TWO SETS EACH SIDE OF THE TOP OR BOTTOM FLANGE WITH A GUSSET PLATE OUTSIDE THE TOP AND BOTTOM FLANGE OR COLUMN CAP PLATE.


**CONNECTION BOLT DATA**

| NAME   | DESCRIPTION FOR A325 BOLT DIMENSIONS   |   |  |              |              |              |
|--------|--|---|--|--------------|--------------|--------------|
|        | A325 CONNECTION BOLT DIMENSIONS  |   |  |              |              |              |
| D      | DIAMETER OF THE BOLT   | 1/2"  | 3/4"   | 7/8"         | 1"           | 1 1/4"       |
| HD     | BOLT HOLE DIAMETER   | 9/16"   | 13/16"   | 15/16"       | 1 1/16"      | 1 5/16"      |
| G      | BOLT GAUGE   | 2 1/2"  | 3"   | 4"           | 3 1/2"       | 4"           |
|        | MAX. WEB THICKNESS (Max. 5/16" Fillet Weld) WITHOUT WASHER                     | 1"  | 1 1/8"   | 1 7/8"       | 1 1/4"       | 1 3/8"       |
|        | MAX. WEB THICKNESS (Max. 5/16" Fillet Weld) WITH WASHER                        | 3/4"  | 7/8"   | 1 5/8"       | 7/8"         | 1 7/8"       |
| HG     | HEAVY CONN. BOLT GAUGE   | N/A   | 2 1/4"   | 2 5/8"       | 3"           | 3 3/4"       |
| S      | NORMAL BOLT SPACING  | 2 1/2"  | 3"   | 3 1/4"       | 3 1/2"       | 4"           |
| BSMIN  | MINIMUM SPACING BETWEEN TOP & BOTTOM SETS OF BOLTS                             | 1 1/2"  | 2 1/4"   | 2 5/8"       | 3"           | 3 3/4"       |
| BSMAX  | MAXIMUM BOLT SPACING BETWEEN TOP AND BOTTOM SETS OF BOLTS ON CONNECTION PLATES | 2'-0"   | 2'-0"  | 2'-0"        | 2'-0"        | 2'-0"        |
|        | SPLICE BOLT SPACING  | 1/2 BSMAX ( $\pm \frac{1}{16}$ ) WHEN BSMAX = 2'-0 1/16" TO 4'-0<br>(NOT TO EXCEED 2'-0)  | 1/3 BSMAX ( $\pm \frac{1}{16}$ ) WHEN BSMAX = 4'-0 1/16" TO 6'-0<br>1/4 BSMAX ( $\pm \frac{1}{16}$ ) WHEN BSMAX = 6'-0 1/16" TO 8'-0 |              |              |              |
| BFCD   | MINIMUM BOLT-TO-FLANGE CLEARANCE AT OUT OF NUT SEE BOLT AT FLANGE DETAIL       | 1 1/2"  | 1 3/4"   | 1 7/8"       | 2 1/4"       | 2 1/2"       |
| PF     | MINIMUM BOLT-TO-FLANGE CLEARANCE AT CONNECTION PLATE SEE BOLT AT FLANGE DETAIL | (BFCD + RNWT) PF INSIDE OF FLANGE IS INCREASED BASED ON THE YT & YB VALUE. PF FOR CONNECTION B, F, I AND P ARE THE SAME AS USED ON CONNECTION E |  |              |              |              |
| NWT    | NUT AND WASHER THICKNESS   | SEE BOLT AT FLANGE DETAIL. NUT THICKNESS IS EQUAL TO THE BOLT DIAMETER AND .15625" WASHER THICKNESS IS USED EVEN IF A WASHER IS NOT REQUIRED.   |  |              |              |              |
| RNWT   | RISE ON NUT AND WASHER THICKNESS   |   |  |              |              |              |
| TT     | THICKNESS TOP FLANGE   | REFER TO FRAME CROSS SECTION DRAWING FOR LARGEST FLANGE THICKNESS EITHER SIDE OF THE CONNECTION.  |  |              |              |              |
| TB     | THICKNESS BOTTOM FLANGE  |   |  |              |              |              |
| YT     | BOLT SPACING TOP (ROUND UP TO NEXT 1/2", MIN = S)                              | 3" + TT   | 3 1/2" + TT  | 3 3/4" + TT  | 4 1/2" + TT  | 5" + TT      |
| YB     | BOLT SPACING BOTTOM (ROUND UP TO NEXT 1/2", MIN = S)                           | or TB Sloped  | or TB Sloped   | or TB Sloped | or TB Sloped | or TB Sloped |
| EED(E) | MINIMUM END EDGE DIMENSION   | 1 1/4"  | 1 1/4"   | 1 1/2"       | 1 3/4"       | 2 1/4"       |
| EED(S) | MINIMUM SIDE EDGE DIMENSION  | 3/4"  | 1"   | 1 1/8"       | 1 1/4"       | 1 5/8"       |
| EEDK   | END EDGE DIMENSION AT KNEE CONNECTION  | 1 3/8"  | 1 3/8"   | 1 5/8"       | 1 7/8"       | 2 3/8"       |
| BCWM   | MINIMUM BOLT CLEARANCE FROM A FLANGE OR WEB WELD                               | 7/16"   | 5/8"   | 3/4"         | 13/16"       | 1"           |
|        | WITHOUT WASHER   | 9/16"   | 3/4"   | 7/8"         | 1"           | 1 1/4"       |
| WCSM   | MINIMUM WIDTH OF CONNECTION PLATE (Standard Connection)                        | 5"  | 6"   | 8"           | 8"           | 10"          |
| WCHM   | MINIMUM WIDTH OF CONNECTION PLATE (Heavy Connection)                           | N/A   | 10"  | 12"          | 12"          | 16"          |
| TCMIN  | MINIMUM THICKNESS OF CONNECTION PLATE  | 1/4"  | 3/8"   | 7/16"        | 1/2"         | 5/8"         |
|        |  |   |  |              |              | 1"           |




**STANDARD CONNECTION DESIGNATION**

(CODE 4E/2E SHOWN)




**HEAVY CONNECTION DESIGNATION**

(CODE 4EH/2EH SHOWN)



**CONNECTION B & P**

(Low Side Shown, High Side Similar)



**BOLT AT FLANGE DETAIL**

(Top Flange Shown, Bottom Flange Similar)

**Frame Documentation**  
**A325 Connection Bolt Details**


Page 05-12-10  
Date Mar '24 | Rev. 06

B 4E/2EH

Connection Code  
(See "Connection Code Format" on this drawing)  
Connection Location

CROSS SECTION CONNECTION CODE KEY  
(AS SHOWN AT CONNECTIONS ON FRAME CROSS SECTION DRAWINGS)

| Flange Brace Material Schedule |                           |
|--------------------------------|---------------------------|
| Part Mark                      | Material                  |
| FB4                            | L 2" x 2" x 14 Ga.        |
| FB5                            | L 2" x 2" x 14 Ga.        |
| FB6                            | L 2" x 2" x 1/8"          |
| FB7                            | L 2 1/2" x 2 1/2" x 3/16" |



**4X CONNECTION DESIGNATION**

(CODE 4X/4X SHOWN)

|   |  |
|---|--|
| Project Name & Location:  | 13105 Northwest Freeway, Suite 500 Houston, TX 77040 |
| Customer:   | MARA BROWN<br>1304 VALLEY DR<br>ODEN, UT 84401-0808  |
| Scale:  | NOT TO SCALE   |
| Drawn by:   | AXD 12/9/25  |
| Checked by:   | MC 12/15/25  |
| Project Engineer:   | RAR  |
| Job Number:   | 20-B-91454   |
| Sheet Number:   | E14 of 14  |
| The engineer whose seal appears hereon is employed by or is contracted to provide engineering services for the manufacturer, Cornerstone Building Brands or one of its affiliates, for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project. |  |
| KAUSHIKKUMAR J. PATEL, P.E.<br>UTAH P.E. 12592792-2202  |  |

Issued For Approval:  (Not For Permit)


Issued For Construction:

Issued For Approval:

Issued For Construction:

PROFESSIONAL ENGINEER  
No. 12592792  
KAUSHIKKUMAR J. PATEL  
STATE OF UTAH


Jan 02, 2026  
This item has been electronically signed and sealed by Kaushikumar J. Patel, P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.



### Anchor Rod Setting Plan


#### Anchor Rod Drawings

- This drawing is for anchor rod placement only and is not foundation design.
- Foundation must be square and level with all anchor rods true in size, location, and projection.
- Projection shown must be held to keep threads clear of finished concrete.
- The structural design data includes magnitude and location of design loads and support conditions, material properties, and type and size of major structural members necessary to show compliance with the Order Documents at the time of this issue. Any change to building loads or dimensions may change structural member sizes and locations shown. This structural design data will be superseded and voided by any future mailing.
- Anchor rod size as noted on the drawings has been determined by shear and tension analysis. The size, type, and location of the anchor rod and method of load transfer to the foundation are to be determined by the foundation engineer. Anchor rods are not provided by the metal building manufacturer.
- Anchor rods are ASTM F1554 Gr. 36 material unless noted otherwise.
- 3000 psi concrete compressive strength ( $f'_c$ ) is assumed for the purpose of column base plate design unless otherwise noted.




This item has been electronically signed and sealed by Kaushikumar J. Patel, P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.


| FRAMED OPENING SCHEDULE |                                | DETAIL QUAN. |
|-------------------------|--------------------------------|--------------|
| MARK                    | DESCRIPTION                    |              |
| [A]                     | 16'-0" X 14'-0" FRAMED OPENING | (1) 4        |




BASE PLATE SIZE = 6" W x 9 1/2" L x 3/8" THICK  
ANCHOR ROD SIZE = 3/8" DIA. (F1554 GR.36)  
ANCHOR ROD PROJECTION = 3"  
BOTTOM OF BASE PLATE ELEVATION = 100'-0"  
(ANCHOR BOLTS, NUTS AND WASHERS NOT BY ME)




BASE PLATE SIZE = 6" W x 8 1/4" L x 3/8" THICK  
ANCHOR ROD SIZE = 3/8" DIA. (F1554 GR.36)  
ANCHOR ROD PROJECTION = 3"  
BOTTOM OF BASE PLATE ELEVATION = 100'-0"  
(ANCHOR BOLTS, NUTS AND WASHERS NOT BY M)




BASE PLATE SIZE = 6" W X 9 1/4" L X 3/8" THICK  
ANCHOR ROD SIZE = 3/8" DIA. (F1554 GR.36)  
ANCHOR ROD PROJECTION = 3"  
BOTTOM OF BASE PLATE ELEVATION = 100'-0"  
(ANCHOR BOLTS, NUTS AND WASHERS NOT BY MB)




BASE PLATE SIZE = 6" W x 10" L x  $\frac{3}{8}$ " THICK  
ANCHOR ROD SIZE =  $\frac{3}{8}$ " DIA. (F-1554 GR.36)  
ANCHOR ROD PROJECTION = 3"  
BOTTOM OF BASE PLATE ELEVATION = 100'-0"  
(ANCHOR BOLTS, NUTS AND WASHERS NOT BY MBM)




BASE PLATE SIZE = 6'W x 10'<sup>1/2</sup>L x 3<sup>1/2</sup>" THICK  
ANCHOR ROD SIZE = 3<sup>1/2</sup>" DIA. (F1554 GR.36)  
ANCHOR ROD PROJECTION = 3"  
BOTTOM OF BASE PLATE ELEVATION = 100'-0"  
(ANCHOR BOLTS, NUTS AND WASHERS NOT BY




**A** OUT OF STEEL  
**F**



BASE PLATE SIZE = 6" W x 8  $\frac{1}{2}$ " L x  $\frac{3}{8}$ " THICK  
ANCHOR ROD SIZE =  $\frac{3}{8}$ " DIA. (F1554 GR.36)  
ANCHOR ROD PROJECTION = 3"  
BOTTOM OF BASE PLATE ELEVATION = 100'-0"  
(ANCHOR BOLTS, NUTS AND WASHERS NOT BY ME)




BASE PLATE SIZE = 6" W x 9 1/2" L x 3" THICK  
ANCHOR ROD SIZE = 3/8" DIA. (F1554 GR.36)  
ANCHOR ROD PROJECTION = 3"  
BOTTOM OF BASE PLATE ELEVATION = 100'-0"  
(ANCHOR BOLTS, NUTS AND WASHERS NOT BY M)




BASE PLATE SIZE = 3 1/2" W x 8" L x 1" THICK  
ANCHOR ROD SIZE =  $\frac{1}{4}$  DIA. (F1554 GR.55)  
ANCHOR ROD PROJECTION = 2"  
BOTTOM OF BASE PLATE ELEVATION = 100'-0"  
(ANCHOR BOLTS, NUTS AND WASHERS NOT BY MB)


AISC Code Of Standard Practice Tolerances For Setting Anchor Rods



### Anchor Rod Setting Tolerances



#### Base Plate And Anchor Rod




**FRAMED OPENING RAMP DETAIL**  
**OPTIONAL**

The engineer whose seal appears hereon is employed by or is contracted to provide engineering services for the manufacturer, Cornerstone Building Brands or one of its affiliates, for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project.

KAUSHIKKUMAR J. PATEL, P.E.  
UTAH P.E. 12592792-2202

FRAME ID #3  
cs 40/16/10.25 20/110.43  
USER NAME:Rafael.acerabod  
JOB NAME:91454A  
DATE:12/03/25 PAGE:3-2  
FILE:frames\_1.fra  
SUPPORT REACTIONS FOR EACH LOAD GROUP  
\*LOCATION: Gridlines: 3  
NOTES: (1) All reactions are in kips and kip-ft.  
(2) The seismic overstrength factor (Omega) is not included in the "RBDWEO" and "RBUPEQ" Load Group reactions.  
(3) Primary wind load cases are not concurrent.  
(4) X-bracing reactions (RBPULW and RBUPEQ) are combined with LWL and LEQ groups only.  
TIME:17:11:05

REACTION NOTATIONS



LOAD GROUP REACTION TABLE GRIDLINES \* = 1

| COLUMN     | *-C  |      |      | *-A  |      |      | *-B  |      |      |
|------------|------|------|------|------|------|------|------|------|------|
| LOAD GROUP | H    | V    | L    | H    | V    | L    | H    | V    | L    |
| DL         | 0.0  | 0.5  | -0.0 | -0.0 | 0.5  | -0.0 | 0.0  | 1.0  | -0.0 |
| COLL       | 0.0  | 0.1  | -0.0 | -0.0 | 0.1  | -0.0 | 0.0  | 0.2  | -0.0 |
| PLL1       | 0.1  | 2.0  | -0.0 | -0.1 | -0.2 | -0.0 | 0.0  | 2.3  | -0.0 |
| PLL2       | 0.1  | -0.2 | -0.0 | -0.1 | 2.0  | -0.0 | -0.0 | 2.3  | -0.0 |
| SNOW       | 0.0  | 2.2  | -0.0 | -0.2 | 2.0  | -0.0 | 0.0  | 6.0  | -0.0 |
| LL         | 0.2  | -0.8 | -0.0 | 0.2  | 1.8  | -0.0 | 0.0  | 4.6  | -0.0 |
| EQ         | -0.4 | -0.3 | -0.0 | -0.4 | 0.3  | -0.0 | 0.2  | 0.0  | -0.4 |
| WL1        | -1.7 | -3.0 | -0.0 | -1.6 | -0.7 | -0.0 | 0.0  | -4.3 | -0.0 |
| WL2        | -2.1 | -2.1 | -0.0 | -1.2 | 0.2  | -0.0 | 0.0  | -3.1 | -0.0 |
| LWL1       | 0.9  | -2.5 | -0.0 | -0.5 | -1.7 | -0.0 | -0.0 | -3.5 | -3.1 |
| LWL2       | 0.5  | -1.7 | -0.0 | -0.9 | -2.5 | -0.0 | -0.0 | -3.5 | -3.1 |
| LWL3       | 0.5  | -2.5 | -0.0 | -0.5 | -0.5 | -0.0 | -0.0 | -2.3 | -3.1 |
| LWL4       | 0.1  | -0.9 | -0.0 | -0.5 | -1.7 | -0.0 | 0.0  | -2.3 | 3.1  |
| WL3        | 1.6  | -0.7 | -0.0 | 1.7  | -3.0 | -0.0 | -0.0 | -4.3 | -0.0 |
| WL4        | 1.2  | 0.2  | -0.0 | 2.1  | -2.1 | -0.0 | -0.0 | -3.1 | -0.0 |
| SBAL       | 0.2  | 2.4  | -0.0 | -0.2 | 2.4  | -0.0 | 0.0  | 6.3  | -0.0 |
| RS         | 0.2  | 0.4  | -0.0 | -0.2 | 2.9  | -0.0 | -0.0 | 5.3  | -0.0 |
| LS         | 0.2  | 2.9  | -0.0 | -0.2 | 0.4  | -0.0 | 0.0  | 5.3  | -0.0 |


LOAD GROUP DESCRIPTION

DL : Roof Dead Load  
COLL : Roof Collateral Load  
PLL1 : Pattern Live Load [PLLxx]  
PLL2 : Pattern Live Load [PLLxx]  
SNOW : Roof Snow Load  
LL : Roof Live Load  
EQ : Lateral Seismic Load [parallel to plane of frame]  
WL1 : Wind from Left to Right with +Cp1  
WL2 : Wind from Left to Right with -Cp1  
WL3 : Windward Corner Right with +Cp1  
WL4 : Windward Corner Right with -Cp1  
WL5 : Wind from Right to Left with +Cp1  
WL6 : Wind from Right to Left with -Cp1  
SBAL : Code Calculated Balanced Roof Snow Load  
RS : Unbalanced Right Roof Snow Load  
LS : Unbalanced Left Roof Snow Load

ADDITIONAL NOTES:  
(1) Pattern live or snow load cases are not concurrent with any other live or snow load cases.

FRAME ID #1  
cs 40/16/19.75 20/110.44  
USER NAME:Rafael.acerabod  
JOB NAME:91454A  
DATE:12/03/25 PAGE:1-2  
FILE:frames\_1.fra  
SUPPORT REACTIONS FOR EACH LOAD GROUP  
\*LOCATION: Gridlines: 2 4  
NOTES: (1) All reactions are in kips and kip-ft.  
(2) The seismic overstrength factor (Omega) is not included in the "RBDWEO" and "RBUPEQ" Load Group reactions.  
(3) Primary wind load cases are not concurrent.  
(4) X-bracing reactions (RBPULW and RBUPEQ) are combined with LWL and LEQ groups only.  
TIME:17:10:50

REACTION NOTATIONS




LOAD GROUP REACTION TABLE GRIDLINES \* = 2 4

| COLUMN     | *-C  |       |      | *-A  |       |      |
|------------|------|-------|------|------|-------|------|
| LOAD GROUP | H    | V     | L    | H    | V     | L    |
| DL         | 0.4  | 1.4   | -0.0 | -0.4 | 1.4   | -0.0 |
| COLL       | 0.1  | 0.4   | -0.0 | -0.1 | 0.4   | -0.0 |
| PLL1       | 0.3  | 12.0  | -0.0 | -3.6 | 12.0  | -0.0 |
| PLL2       | 0.4  | -1.4  | -0.0 | -1.4 | 4.8   | -0.0 |
| SNOW       | 3.6  | 12.0  | -0.0 | -3.6 | 12.0  | -0.0 |
| LL         | 1.4  | -4.8  | -0.0 | -1.4 | 4.8   | -0.0 |
| RBDWEO     | -0.9 | -2.1  | -0.0 | 0.2  | 2.5   | -0.0 |
| EQ         | -0.7 | -0.6  | -0.0 | -0.7 | 0.6   | -0.0 |
| RBUPEQ     | 0.0  | -2.5  | -3.1 | -0.0 | -2.5  | -3.1 |
| WL1        | -3.5 | -7.0  | -0.0 | -0.9 | -4.2  | -0.0 |
| WL2        | -3.7 | -4.2  | -0.0 | -0.7 | -1.4  | -0.0 |
| WL3        | 0.9  | -4.2  | -0.0 | 3.5  | -7.0  | -0.0 |
| WL4        | 0.7  | -1.4  | -0.0 | 3.7  | -4.2  | -0.0 |
| LWL1       | 0.5  | -5.9  | -0.0 | -0.0 | -5.0  | -0.0 |
| RBPULW     | 0.0  | -2.3  | -2.9 | -0.0 | -2.3  | -2.9 |
| WL1        | 0.0  | -5.0  | -0.0 | -0.5 | -5.9  | -0.0 |
| WL2        | 0.2  | -5.3  | -0.0 | -0.2 | -2.2  | -0.0 |
| WL3        | -0.2 | -2.5  | -0.0 | 0.2  | -1.2  | -0.0 |
| WL4        | 3.2  | -10.8 | -0.0 | -3.2 | -10.8 | -0.0 |
| RS         | 2.7  | 6.1   | -0.0 | -2.7 | 10.9  | -0.0 |

FRAME ID #1  
cs 40/16/19.75 20/110.44  
USER NAME:Rafael.acerabod  
JOB NAME:91454A  
DATE:12/03/25 PAGE:1-3  
FILE:frames\_2\_4.fra  
SUPPORT REACTIONS FOR EACH LOAD GROUP  
\*LOCATION: Gridlines: 2 4  
NOTES: (1) All reactions are in kips and kip-ft.  
(2) The seismic overstrength factor (Omega) is not included in the "RBDWEO" and "RBUPEQ" Load Group reactions.  
(3) Primary wind load cases are not concurrent.  
(4) X-bracing reactions (RBPULW and RBUPEQ) are combined with LWL and LEQ groups only.  
TIME:17:10:50

REACTION NOTATIONS



LOAD GROUP REACTION TABLE GRIDLINES \* = 2 4

| COLUMN     | *-C  |      |      | *-A  |     |      |
|------------|------|------|------|------|-----|------|
| LOAD GROUP | H    | V    | L    | H    | V   | L    |
| LS         | 2.7  | 10.7 | -0.0 | -2.7 | 6.0 | -0.0 |
| RBDWLW     | -0.0 | 2.3  | -0.0 | 0.0  | 2.3 | -0.0 |

LOAD GROUP DESCRIPTION

LS : Unbalanced Left Roof Snow Load  
RBDWLW : Downward Acting Rod Brace Load from Long. Wind


FRAME ID #2  
cs 40/16/20. 20/110.43  
USER NAME:Rafael.acerabod  
JOB NAME:91454A  
DATE:12/03/25 PAGE:2-2  
FILE:frames\_3.fra  
SUPPORT REACTIONS FOR EACH LOAD GROUP  
\*LOCATION: Gridlines: 3  
NOTES: (1) All reactions are in kips and kip-ft.  
(2) The seismic overstrength factor (Omega) is not included in the "RBDWEO" and "RBUPEQ" Load Group reactions.  
(3) Primary wind load cases are not concurrent.  
(4) X-bracing reactions (RBPULW and RBUPEQ) are combined with LWL and LEQ groups only.  
TIME:17:10:59

REACTION NOTATIONS



| COLUMN     | *-C  |       |      | *-A  |        |      |
|------------|------|-------|------|------|--------|------|
| LOAD GROUP | H    | V     | L    | H    | V      | L    |
| DL         | 0.4  | 1.4   | -0.0 | -0.4 | 1.4    | -0.0 |
| COLL       | 0.1  | 0.4   | -0.0 | -0.1 | 0.4    | -0.0 |
| PLL1       | 3.6  | 12.0  | -0.0 | -3.6 | 12.0   | -0.0 |
| PLL2       | 1.4  | -4.8  | -0.0 | -1.4 | 4.8    | -0.0 |
| SNOW       | 3.6  | 12.0  | -0.0 | -3.6 | 12.0   | -0.0 |
| LL         | 1.4  | -4.8  | -0.0 | -1.4 | 4.8    | -0.0 |
| RBDWEO     | -0.9 | -2.1  | -0.0 | 0.2  | 2.5    | -0.0 |
| EQ         | -0.7 | -0.6  | -0.0 | -0.7 | 0.6    | -0.0 |
| RBUPEQ     | 0.0  | -2.5  | -3.1 | -0.0 | -2.5   | -3.1 |
| WL1        | -3.5 | -7.0  | -0.0 | -0.9 | -4.2   | -0.0 |
| WL2        | -3.7 | -4.2  | -0.0 | -0.7 | -1.4   | -0.0 |
| WL3        | 0.9  | -4.2  | -0.0 | 3.5  | -7.0   | -0.0 |
| WL4        | 0.7  | -1.4  | -0.0 | 3.7  | -4.2   | -0.0 |
| LWL1       | 0.5  | -5.9  | -0.0 | -0.0 | -5.0   | -0.0 |
| RBPULW     | 0.0  | -2.3  | -2.9 | -0.0 | -2.3   | -2.9 |
| WL1        | 0.0  | -5.0  | -0.0 | -0.5 | -5.9   | -0.0 |
| WL2        | 0.2  | -5.3  | -0.0 | -0.2 | -2.2   | -0.0 |
| WL3        | -0.2 | -2.5  | -0.0 | 0.2  | -1.2   | -0.0 |
| WL4        | 3.2  | -10.8 | -0.0 | -3.2 | -10.8  | -0.0 |
| RS         | 2.7  | 6.1   | -0.0 | -2.7 | 10.9</ |      |

|   |                         |                        |
|---|-------------------------|------------------------|
| FRAME ID #  | USER NAME:Refel.acerbab | DATE:12/03/25 PAGE:4-2 |
| rr1 40/18,10.25   | JOB NAME:91454          | FILE:frame_5.fra       |
| SUPPORT REACTIONS FOR EACH LOAD GROUP   |                         |                        |
| *LOCATION: Gridlines: 5   |                         | TIME:17:10:54          |
| NOTES: (1) Wind load cases are in lbs and kg--ft.                                   |                         |                        |
| (2) Primary wind load cases are not concurrent.                                     |                         |                        |
| (3) X-bracing reactions (RBUPW and RBUDW) are combined with WL and LEO groups only. |                         |                        |

**REACTION NOTATIONS**

**LOAD GROUP REACTION TABLE** GRIDLINES \* = 5

| LOAD GROUP | *C   |      |      | *A   |      |      | *B   |      |      |
|------------|------|------|------|------|------|------|------|------|------|
|            | H    | V    | L    | H    | V    | L    | H    | V    | L    |
| DL         | 0.0  | 0.5  | -0.0 | -0.0 | 0.5  | -0.0 | 0.0  | 1.0  | -0.0 |
| COLL       | 0.0  | 0.1  | -0.0 | -0.0 | 0.1  | -0.0 | 0.0  | 0.2  | -0.0 |
| PLL1       | 0.1  | -2.0 | -0.0 | -0.1 | -0.2 | -0.0 | 0.0  | 2.3  | -0.0 |
| PLL2       | 0.1  | -0.2 | -0.0 | -0.1 | 2.0  | -0.0 | -0.0 | 2.3  | -0.0 |
| SNOW       | 0.2  | 2.2  | -0.0 | -0.2 | 2.2  | -0.0 | 0.0  | 6.0  | -0.0 |
| LL         | 0.2  | 1.8  | -0.0 | -0.2 | 1.8  | -0.0 | 0.0  | 4.6  | -0.0 |
| EQ         | -0.4 | -0.3 | -0.0 | -0.4 | 0.3  | -0.0 | 0.2  | 0.0  | -0.4 |
| WL1        | -1.7 | -3.0 | -0.0 | -1.6 | -0.7 | -0.0 | 0.0  | -4.3 | -0.0 |
| WL2        | -2.1 | -2.1 | -0.0 | -1.2 | 0.2  | -0.0 | 0.0  | -3.1 | -0.0 |
| WL3        | 0.9  | -2.5 | -0.0 | -0.5 | -1.7 | -0.0 | -0.0 | -3.5 | -3.1 |
| WL4        | 0.5  | -1.7 | -0.0 | -0.9 | -2.5 | -0.0 | -0.0 | -3.5 | -3.1 |
| LS         | 0.2  | -0.5 | -0.0 | -0.2 | -0.5 | -0.0 | -0.0 | -2.3 | -3.1 |
| SBAL       | 0.1  | -0.9 | -0.0 | -0.5 | -1.7 | -0.0 | 0.0  | -2.3 | -3.1 |
| RS         | 1.6  | -0.7 | -0.0 | 1.7  | -3.0 | -0.0 | -0.0 | -4.3 | -0.0 |
| LS         | 1.2  | 0.2  | -0.0 | -0.2 | 2.4  | -0.0 | 0.0  | 6.3  | -0.0 |
| RS         | 0.2  | 0.4  | -0.0 | -0.2 | 2.9  | -0.0 | -0.0 | 5.3  | -0.0 |
| LS         | 0.2  | 2.9  | -0.0 | -0.2 | 0.4  | -0.0 | 0.0  | 5.3  | -0.0 |

**LOAD GROUP DESCRIPTION**

|      |   |
|------|---|
| DL   | : Roof Dead Load                                    |
| COLL | : Roof Collateral Load                              |
| PLL1 | : Pattern Live Load [PLLxx]                         |
| PLL2 | : Pattern Live Load [PLLxx]                         |
| SNOW | : Roof Snow Load                                    |
| LL   | : Roof Live Load                                    |
| EQ   | : Lateral Seismic Load [parallel to plane of frame] |
| WL1  | : Wind from Left to Right with +CGp1                |
| WL2  | : Wind from Left to Right with -CGp1                |
| WL3  | : Windward Corner Left with +CGp1                   |
| WL4  | : Windward Corner Right with +CGp1                  |
| WL5  | : Windward Corner Left with -CGp1                   |
| WL6  | : Windward Corner Right with -CGp1                  |
| WL7  | : Wind from Right to Left with +CGp1                |
| WL8  | : Wind from Right to Left with -CGp1                |
| SBAL | : Code Calculated Balanced Roof Snow Load           |
| RS   | : Unbalanced Right Roof Snow Load                   |
| LS   | : Unbalanced Left Roof Snow Load                    |

**ADDITIONAL NOTES:**  
 (1) Pattern live or snow load cases are not concurrent with any other live or snow load cases.

**NOTES**

- 1) THE REACTIONS PROVIDED ARE BASED ON THE ORDER DOCUMENTS AT THE TIME OF MAILING. ANY CHANGES TO BUILDING LOADS OR DIMENSIONS MAY CHANGE THE REACTIONS. THE REACTIONS WILL BE SUPERSEDED AND VOIDED BY ANY FUTURE MAILING.
- 2) THE REACTIONS PROVIDED HAVE BEEN CREATED WITH THE FOLLOWING LAYOUT (UNLESS NOTED OTHERWISE).
  - a) A REACTION TABLE IS PROVIDED WITH THE REACTIONS FOR EACH LOAD GROUP.
  - b) RIGID FRAMES
    - 1) GABLED BUILDINGS
      - (a) LEFT AND RIGHT COLUMNS ARE DETERMINED AS IF VIEWING THE LEFT SIDE OF THE BUILDING AS SHOWN ON THE ANCHOR ROD DRAWING, FROM THE OUTSIDE OF THE BUILDING.
      - (b) INTERIOR COLUMNS ARE SPACED FROM LEFT SIDE TO RIGHT SIDE.
    - 2) SINGLE SLOPE BUILDINGS
      - (a) LEFT COLUMN IS THE LOW SIDE COLUMN.
      - (b) RIGHT COLUMN IS THE HIGH SIDE COLUMN.
      - (c) INTERIOR COLUMNS ARE SPACED FROM LOW SIDE TO HIGH SIDE.
  - c) ENDWALLS
    - 1) LEFT AND RIGHT COLUMNS ARE DETERMINED AS IF VIEWING THE WALL FROM THE OUTSIDE.
    - 2) INTERIOR COLUMNS ARE SPACED FROM LEFT TO RIGHT.
- d) ANCHOR ROD SIZE IS DETERMINED BY SHEAR AND TENSION AT THE BOTTOM OF THE BASE PLATE. THE LENGTH OF THE ANCHOR ROD AND METHOD OF LOAD TRANSFER TO THE FOUNDATION ARE TO BE DETERMINED BY THE FOUNDATION ENGINEER.
- e) ANCHOR RODS ARE ASTM F1554 Gr. 36 MATERIAL UNLESS NOTED OTHERWISE ON THE ANCHOR ROD LAYOUT DRAWING.
- f) X-BRACING

- (1) ROD BRACING REACTIONS HAVE BEEN INCLUDED IN VALUES SHOWN IN THE REACTION TABLES.
- (2) FOR IBC AND UBC BASED BUILDING CODES, WHEN X-BRACING IS PRESENT ON THE SIDEWALL, INDIVIDUAL LONGITUDINAL SEISMIC LOADS (RBUPW AND RBUDW) DO NOT INCLUDE THE AMPLIFICATION FACTOR  $R_a$ .
- (3) FOR CANADA BUILDING CODE (NBC), WHEN X-BRACING IS PRESENT IN THE SIDEWALL OR ENDWALL, INDIVIDUAL LONGITUDINAL SEISMIC LOADS (RBUPW AND RBUDW) ARE Multiplied BY FORCE REDUCTION FACTOR  $R_a$ , WHEN SPECIFIED, OR PERIOD-SPECIAL ACCELERATION RATIO  $[F_{AS}(0.2)]$  IS GREATER THAN 0.45.

- 3) REACTIONS PROVIDED ARE UN-FACTORED FOR EACH LOAD GROUP APPLIED TO THE COLUMN. THE FOUNDATION ENGINEER WILL APPLY THE APPROPRIATE LOAD FACTORS AND COMBINE THE REACTIONS IN ACCORDANCE WITH THE BUILDING CODE AND DESIGN SPECIFICATIONS TO DETERMINE BEARING PRESSURES AND CONCRETE DESIGN. THE FACTORS APPLIED TO LOAD GROUPS FOR THE STEEL COLUMN DESIGN MAY BE DIFFERENT THAN THE FACTORS USED IN THE FOUNDATION DESIGN.
- a) FOR PROJECTS USING ULTIMATE DESIGN WIND SPEEDS SUCH AS 2012 IBC, 2015 IBC, OR FLORIDA BUILDING CODE, THE WIND LOAD REACTIONS ARE AT A STRENGTH VALUE WITH A LOAD FACTOR OF 1.0.
- b) FOR IBC CODES, THE SEISMIC REACTIONS PROVIDED ARE AT A STRENGTH LEVEL AND DO NOT CONTAIN THE RHO FACTOR.
- c) FOR NBC CODES, THE SEISMIC REACTIONS PROVIDED DO NOT CONTAIN THE R<sub>a</sub>, R<sub>o</sub> FACTOR.

THE MANUFACTURER DOES NOT PROVIDE "MAXIMUM" LOAD COMBINATION REACTIONS. HOWEVER, THE INDIVIDUAL LOAD REACTIONS PROVIDED MAY BE USED BY THE FOUNDATION ENGINEER TO DETERMINE THE APPLICABLE LOAD COMBINATIONS FOR HIS/HER DESIGN PROCEDURES AND ALLOW FOR AN ECONOMICAL FOUNDATION DESIGN.

|   |  |  |   |
|---|--|--|---|
| <b>FORTIFY</b><br>BUILDING SOLUTIONS <sup>®</sup>   | 13105 Northwest Freeway, Suite 500<br>Houston, TX 77040                                    | Project Name & Location:<br>MARA BROWN<br>1300 VALLEY DR<br>ODGEN, UT 84401-0888 | <input checked="" type="checkbox"/> Issued For Construction |
|   |  |  | <input type="checkbox"/> Issued For Approval                |
| <b>MUELLER</b><br>METAL BUILDINGS, ROOFS & MORE   | Customer:<br>CITY OF OGDEN-212366<br>2549 WASHINGTON BLVD<br>OGDEN, UT 84401<br>MARA BROWN | Drawing Status:<br><input type="checkbox"/> Not For Permit                       | <input type="checkbox"/> Issued For Construction            |
|   |  |  | <input type="checkbox"/> Issued For Permit                  |
| Scale: NOT TO SCALE   |  |  |   |
| Drawn by: DJC 12/5/25   |  |  |   |
| Checked by:   |  |  |   |
| Project Engineer: RAR   |  |  |   |
| Job Number: 20-B-91454  |  |  |   |
| Sheet Number: F4 of 4   |  |  |   |
| <p>The engineer whose seal appears hereon is employed by or is contracted to provide engineering services for the manufacturer, Cornerstone Building Brands or one of its affiliates, for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project.</p> <p>KAUSHIKKUMAR J. PATEL, P.E.<br/>UTAH P.E. 12592792-2202</p> |  |  |   |

Jan 02, 2026  
 This item has been electronically signed and sealed by Kaushikumar J. Patel, P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.

*Kaushikumar J. Patel*  
 Kaushikumar J. Patel, P.E.  
 No. 12592792  
 STATE OF UTAH  
 PROFESSIONAL ENGINEER  
 KAUSHIKKUMAR J. PATEL

## Field Service Procedures

In Order To Give You Prompt Services And Keep Problems To A Minimum, Please Handle Any Shortages Or Back Charges In The Following Manner:  
 1. Carefully Check Your Packing List While Unloading.  
 2. Mark Any Items Which Appear To Be Missing And Notify The Field Service Department At The Number Shown In The Title Block As Soon As Possible. Calling Someone Else Could Delay The Proper Response.

**INITIAL CLAIM:**  
 In The Event Of An Error, The Customer Must Promptly Make A Written Or Verbal "Initial Claim" To The Manufacturer For The Correction Of Design, Drafting, Bill Of Materials Or Fabrication Error.

The "Initial Claim" Includes:  
 1. Description Of The Nature And Extent Of The Errors, Including Quantities.  
 2. Description Of The Nature And Extent Of Proposed Corrective Work, Including Estimated Man-Hours.  
 3. Materials To Be Purchased From Other Than The Manufacturer, Including Estimated Quantities And Cost.  
 4. Maximum Total Cost Of Proposed Corrective Work And Materials To Be Purchased From Other Than The Manufacturer.

**SHORT MATERIALS:**  
 Immediately Upon Delivery Of Materials, Quantities Are To Be Verified By The Customer Against Quantities That Are Billed On The Shipping Documents. Neither The Manufacturer Nor The Carrier Is Responsible For Material Shortages Against The Quantities Billed On The Shipping Documents If Such Shortages Are Not Noted On The Shipping Documents When The Material Is Delivered And Acknowledged By The Carrier's Agent. If The Carrier Is The Manufacturer, Claims For Shortages Are To Be Made By The Customer To The Common Carrier. If The Material Quantities Received Are Correct According To The Quantities Billed On The Shipping Documents, But Are Less Than The Quantities Ordered Or The Quantities That Are Necessary To Complete The Metal Building According To The Order Documents, Claim Is To Be Made To The Manufacturer.

**DAMAGED OR DEFECTIVE MATERIAL:**  
 Damaged Or Defective Material, Regardless Of The Degree Of Damage, Must Be Noted On The Shipping Documents By The Customer And Acknowledged By The Carrier's Agent. The Manufacturer Is Not Responsible For Material Damaged In Unloading Of Packages Or Nested Materials, Including, But Not Limited To: Fasteners, Sheet Metal, "C" And "Z" Sections And Covering Panels That Become Wet And/Or Damaged By Water While In The Possession Of Others. Packaged Or Nested Material That Become Wet In Transit Must Be Unpacked, Unstacked And Dried By The Customer. If The Carrier Is The Manufacturer, The Customer Must Make Claim For Damaged Directly To The Manufacturer. If The Carrier Is A Common Carrier, The Customer Must Make The Claim For Damage To The Common Carrier. The Manufacturer Is Not Liable For Any Claim Whatever Including, But Not Limited To Labor Charges Of Consequential Damages Resulting From Customer's Use Of Damaged Or Defective Materials That Can Be Detected By Visual Inspection.

**EXCESSIVE MATERIAL:**  
 The Manufacturer Reserves The Right To Recover Any Material Delivered In Excess Of Those Required By The Order Documents.

**OIL CANNING IS NOT A CAUSE FOR REJECTION**

## Types Of Finishes

**SHOP PRIMED STEEL:**  
 All Structural Members Of The Metal Building System Not Fabricated Of Corrosion Resistant Material Or Protected By A Corrosion Resistant Coating Are Painted With One Coat Of Shop Primer Meeting The Performance Requirements Of SSPC Paint Specification No.15. The Coat Of Shop Primer Is Intended To Protect The Steel Framing For Only A Short Period Of Exposure To Ordinary Atmospheric Conditions. Shop Primed Steel Which Is Stored In The Field Pending Erection Should Be Kept Free Of The Ground And So Positioned As To Minimize Water Holding Pockets, Dust, Mud And Other Contamination Of The Primer Film. Repairs Of Damaged To Primed Surfaces And/Or Removal Of Foreign Material Due To Improper Field Storage Or Site Conditions Are Not The Responsibility Of The Manufacturer. The Manufacturer Is Not Responsible For Deterioration Of The Shop Coat Of Primer Or Corrosion That May Result From Exposure To Atmospheric And Environmental Conditions, Nor The Compatibility Of The Primer To Any Field Applied Coating. Minor Abrasions To The Shop Coat (Including Galvanizing) Caused By Handling, Loading, Shipping, Unloading And Erection After Painting Or Galvanizing Are Unavoidable. (MBMA 2012, Chapter IV 4.2.4).

**GAVALUME:**  
 Galvalume Is The Trade Name For A Patented Steel Sheet And Coil Product Having A Coating Of Corrosion Resistant Aluminum-Zinc Alloy. The Mixture Is Balanced To Obtain The Coating That Retains The Corrosion Resistance And Heat Reflectivity Of Aluminum And Galvanic Protection Of Zinc. The Best Properties Of Both Aluminum And Zinc Are Combined In This Coating And Offer Added Service Life For The Building.

**Pre-Painted:**  
 Using Galvalume Steel As A Substrate, Pre-Painted Steel Is Given An Additional Rust Inhibitor Primer Coat. This Primer Coat Further Increases The Corrosion Resistance. These Coatings Are Applied To The Exterior Surface Of The Panels And A Wash Coat Designed Only For Interior Use, Is Applied On The Opposite Side. Galvalume And Pre-Painted Steel Can Give Excellent Service For Many Years If A Few Rules Concerning Their Care And Maintenance Are Observed. All Of These Finishes Are Equally Subject To Damage And Corrosion When Care Is Not Provided.

**PAINT AND COATING MAINTENANCE:**  
 Remove Smudge Marks From Bare Galvalume:  
 Formula 409 Has Proven To Be Somewhat Effective. Lightly Rub With A Clean Cloth And Rinse With Water. Do Not Rub More Than Required To Remove Smudge Marks. No Product Will Remove All Smudge Marks.

Remove Rust Stains:  
 Soft Scrub Without Bleach Has Proven To Be Somewhat Effective. Rub With A Soft Cloth And Rinse With Water. Do Not Rub More Than Required To Remove Stain. No Product Will Completely Remove Rust Stains.

To Touch-Up Scratches In Paint (Not Bare Metal):  
 Clean Area To Be Painted With Mild Detergent. Rinse Thoroughly And Dry. Using A Small Artist's Brush, Lightly Apply A Minimal Amount Of Color Matched Touch-Up Paint Required To Fill/Cover The Scratch. Contact The Building Manufacturer For Assistance With Ordering/Purchasing Touch-Up Paint As Needed.

## Authorization For Corrective Work

Normal Erection Operations Include The Correction Of Minor Misfits By Amounts Of Redring, Chipping, Welding Or Cutting And The Drawing Of Elements Into Line Through The Use Of Drift Pins. Errors That Cannot Be Corrected By The Forgoing Means Or Which Require Major Changes In The Member Configuration Should Be Reported Immediately To The Owner And The Fabricator By The Erector, To Enable Whoever Is Responsible Either To Correct The Error Or Approve The Most Efficient And Economical Method Of Correction To Be Used By Others. (AISC 303-10, Section 7.14). If The Error Is The Fault Of The Manufacturer An "Authorization For Corrective Work" Must Be Issued In Writing By The Manufacturer To Authorize The Corrective Work At A Cost Not To Exceed The Maximum Total Cost Set Forth. Alternative Corrective Work Other Than That Proposed In The "Initial Claim" May Be Directed By The Manufacturer In The "Authorization Of Corrective Work". Only The Field Service Department May Authorize Corrective Work.

**FINAL CLAIM:**  
 The "Final Claim" In Writing Must Be Forwarded By The Customer To The Manufacturer Within (10) Days Of The Completion Of The Corrective Work Authorized By The Manufacturer.

### THE "FINAL CLAIM" MUST INCLUDE:

1. Actual Number Of Man-Hours By Dated Of Direct Labor Use On Corrective Work And Actual Hourly Rate Of Pay.
2. Taxes And Insurance On Total Actual Direct Labor.
3. Other Direct Costs On Actual Direct Labor.
4. Cost Of Materials (Not Minor Supplies) Authorized By The Manufacturer To Be Purchased From Other Than The Manufacturer, Including Copies Of Paid Invoices.
5. Total Actual Direct Cost Of Corrective Work (Sum Of 1, 2, 3, And 4). The "Final Claim" Is Credited To The Customer By The Manufacturer In The Amount Not To Exceed The Lesser Of The Maximum Total Cost Set Forth In The "Authorization For Corrective Work" Or The Total Direct Cost Of Corrective Work.

### \*\* IMPORTANT NOTE \*\*

Cost Of Equipment (Rental Or Depreciation), Small Tools, Supervision, Overhead And Profit Are Not Subjected To Claims.

### SHIPMENT ARRIVAL TIME:

Every Effort Will Be Made To See That The Carrier Arrives At The Jobsite On The Requested Hour. Manufacturer Makes No Warranty And Accepts No Responsibility For Costs Associated With A Shipment Not Arriving At The Requested Time Unless A Separate Agreement Has Been Made In Writing For A Guaranteed Arrival Time.

## Unloading, Handling And Storage

### STRUCTURAL:

A Great Amount Of Time And Trouble Can Be Saved If The Building Parts Are Unloaded At The Building Site According To A Pre-Arranged Plan. Proper Location And Handling Of Components Will Eliminate Unnecessary Handling.

### NOTE:

Piece Marks Are Stenciled On The Primary Structural Members At The Lower End, 1'-0" From The End. Inspect All Shipments Prior To Releasing The Tie-downs For Loads That May Have Shifted During Transit.

### REMEMBER SAFETY FIRST:

Blocking Under Columns And Rafters Protect The Splice Plates And The Slab From Damage During The Unloading Process. It Also Facilitates The Placing Of Slings And Cables Around Members For Later Lifting And Allows Members To Be Bolted Together Into Sub-assemblies While On The Ground. Extra Care Should Always Be Exercised In The Unloading Operation To Prevent Injuries From Handling Steel And To Prevent Damage To Materials And The Concrete Slab. If Water Is Allowed To Remain For Extended Periods In Bundles Of Primed Parts Such As Girts, Purlins, Etc., The Pigment Will Fade And The Paint Will Gradually Soften Reducing Its Bond To The Steel. Therefore, Upon Receipt Of A Job, All Bundles Of Primed Parts Should Be Stored At An Angle To Allow Any Trapped Water To Drain Away And Permit Air Circulation For Drying. Puddles Of Water Should Not Be Allowed To Collect And Remain On Columns Or Rafters For Some Reason.

### THE COAT OF SHOP PRIMER:

The Coat Of Shop Primer Is Intended To Protect The Steel Framing Only For A Short Period Of Exposure To Ordinary Atmospheric Conditions. The Coat Of Shop Primer Does Not Provide The Uniformity Of Appearance, Or The Durability And Corrosion Resistance Of A Field Applied Finish Coat Of Paint Over Shop Primer.

### CAUTION:

Care Should Always Be Taken When Walking On Panels. Use Safety Lines And Net When Necessary. Panels Are Slippery, Wipe Dry Any Moisture Or Surface Material That Has Puddle From Bundles Stored On A Slope. Dew, Frost, Or Other Forms Of Moisture Greatly Increase The Slipperiness Of The Panels. Always Assume Panel Surface Is Slippery And Act Accordingly. Never Walk On Skylights Or Translucent Panels.

Use Wood Blocking To Elevate And Slope The Panels In A Manner That Allows Moisture To Drain. Wood Blocking Placed Between Bundles Will Provide Additional Air Circulation. When Handling Or Unstacking The Panels, Lift Rather Than Slide Them Apart. Buried Edges May Scratch The Coated Surfaces When Sheets Are Slid Over One Another. Never Allow Panels To Be Walked On While On The Ground.

### DRAINAGE:

## Roof And Wall Panels

Manufacturer's Roof And Wall Panels Include Color Coated, Galvalume, And Galvanized, Provides Excellent Service Under Widely Varied Conditions. All Unloading And Erection Personnel Should Fully Understand That These Panels Are Quality Merchandise, Which Merits Cautious Care And Handling.

### UNDER NO CIRCUMSTANCES SHOULD PANELS BE HANDLED ROUGHLY

Packages Of Sheets Should Be Lifted Off The Truck With Extreme Care Taken To Ensure That No Damage Occurs To Ends Of The Sheets Or To Side Ribs. The Packages Should Be Stored Off The Ground Sufficiently High To Allow Air Circulation Underneath The Packages. This Avoids Ground Moisture And Deters People From Walking On The Packages. One End Of The Package Should Be Elevated To Encourage Drainage In Case Of Rain. The Manufacturer Exercises Caution During Fabrication An Shipping Operations To Ensure That All Panel Stock Is Kept Dry. However Due To Climatic Conditions, Water Formed By Condensation Of Humid Air Become Trapped Between Sheets. Water Can Also Be Trapped Between The Stacked Sheets When Exposed To Rain. This May Discoloration Caused By Trapped Moisture. The Stain Is Usually Superficial And Has Little Effect On The Appearance Or Service Life Of The Panels As Long As It Not Permitted To Remain On The Panel. However, Moisture In Contact With The Surface Of The panel Over An Extended Period Can Severely Attack The Finish And Reduce The Effective Service Life. See R1-07 Titled "Damage From Condensation Or Trapped Water".

### CAUTION:

Care Should Always Be Taken When Walking On Panels. Use Safety Lines And Net When Necessary. Panels Are Slippery, Wipe Dry Any Moisture Or Surface Material That Has Puddle From Bundles Stored On A Slope. Dew, Frost, Or Other Forms Of Moisture Greatly Increase The Slipperiness Of The Panels. Always Assume Panel Surface Is Slippery And Act Accordingly. Never Walk On Skylights Or Translucent Panels.

Personnel Walking On The Panel Can Cause Damage. Workmen Should Step Or Walk In The Broad Flat Areas Of The Panel And Avoid Stepping On The Panel Ends And Edges Which Can Be Bent By Careless Handling. If This Damage Is Severe, The Edges Must Be Straighten Prior To Erection Since The Appearance And/Or Weather Tightness Of The Panel Could Be Affected. Dragging One Panel Across Another Can Cut Or Abrade The Coating Causing Unsightly Marks On The Panel Surface.

Attempts To Erect Panels During Windy Conditions Should Be Avoided To Prevent Damage And Of Safety Considerations.

Leaving Dirt Piled Against The Exterior Wall Panels At The Foundation Will Cause Panel Damage. This Dirt May Be Wet Or At Least Contain Some Moisture. Mud May Have Splashed Onto The Wall During Construction. Corrosion Damage May Occur Where This Dirt Is Melt Contacts The Panel. In Areas Where Lime Stabilization Of The Soil Is Required, Corrosion Damage From The Soil's Content Will Be Accelerated And Most Likely Be Severe. All Dirt Must Be Removed From The Panel Walls At The Time Of Completion Of Work. Pre-Painted Panels May Require Touch-up If The Coating Has Been Damaged During Handling Or Erection.

The Appearance Of The Building May Be Affected If Damaged Spots Or Scratches Are Located In Highly Visible Places Such As Around Doors, Windows, Etc.. If Damage Is Extensive Then Replacement Of The Entire Panel Should Be Considered.

## Safety Commitment

The Builder/Contractor Is Responsible For Applying And Observing All Pertinent Safety Rules And OSHA Standards As Applicable.

The Building Manufacturer Has A Commitment To Manufacture Quality Building Components That Can Be Safely Erected. However The Safety Commitment And Job Site Practices Of The Erector Are Beyond The Control Of The Building Manufacturer.

It Is Strongly Recommended That Safe Working Conditions And Accident Prevention Practices Be The Top Priority Of Any Job Site.

Local, State And Federal Safety And Health Standards, Whether Standard Statuary Or Customary, Should Always Be Followed To Help Ensure Worker Safety.

Make Sure All Employees Know The Safest And Most Productive Way Of Erecting A Building. Emergency Procedures Should Be Known To All Employees. Daily Meetings Highlighting Safety Procedures Are Also Recommended. The Use Of Hard Hats, Rubber Sole Shoes For Roof Work, Proper Equipment For Handling Material And Safety Nets Where Applicable Are Recommended

For The Purposes Of Determining Lift Requirements, No Bundle Supplied By The Manufacturer Will Exceed 4,000 Pounds. For Further Information Also Reference The Bill Of Materials For Individual Member Weights Of Structural Members. If Additional Information Is Required Contact The Field Service Department.

**ICE AND SNOW REMOVAL:**  
 Excessive Ice And Snow Removal Should Be Removed From The Roof Immediately To Prevent Damage To Roof And Possible Collapse. Do Not Use Metal Tools To Remove The Ice Or Snow As This Can Damage The Paint And/Or Galvalume Coatings. Also Be Careful Around Pipes And Flashing's. Be Extremely Careful If Your Roof Has Light Transmitting Panels. These Panels Will Not Support A Person's Weight And Will Be Difficult Or Impossible To See If They Are Covered With Ice Or Snow. See MBMA Low-Rise Building Systems Manual, Appendix A For Details On Snow Removal Procedures. These Procedures Should Commence When Half Of The Design Roof Snow Load Is Realized.

**DEBRIS REMOVAL:**  
 Any Foreign Debris Such As Sawdust, Dirt, Leaves, Animal Droppings, Etc. Will Cause Corrosion Of The Roof, Gutters, Trim, Etc. If Left On The Building Surface For A Long Enough Time, The Roof Should Be Periodically Inspected For Such Conditions And If Found, They Should Be Rectified In A Manner Consistent With These Roof Maintenance Guidelines. Never Allow Treated Lumber Or Concrete/Mortar/GROUT To Come In Contact With Roof Panels, Especially Galvalume Panels Under Normal Exposure.

**PERIODIC INSPECTION:**  
 All High-Strength Shall Be Periodically Inspected For Tightness. Particularly In Crane Buildings And After Seismic Or Wind Activity. The Crane Manufacturer Will Specify A Minimum Period But It Should Not Exceed Two Years.

**DRAINAGE:**  
 1. Keep Roof Free Of Debris And Keep Debris Out Of Gutter To Allow Water Quickly Drain From The Roof.  
 2. Do Not Use Wood Blocking To Hold Equipment Off The Panel Seams. This Blocks The Flow Of Water And Hold Moisture.  
 3. Do Not Allow Rooftop AC Units Or Evaporative Coolers To Drain Onto The Roof.  
 4. Anything That Traps Or Holds Moisture On A Roof Will Cause Premature Corrosion.

## Roof Maintenance Guidelines

1. Inspect Roof For Damage After Heavy Storms.

2. Inspect And Reseal As Necessary All Roof Curbs And Other Penetrations With Urethane Sealant.

3. Always Get Manufacturer Approval Before Making Any Modifications To The Roof.

4. Repaint Any Areas That Are Susceptible To Rust As Required.

5. When Performing Roof Maintenance, Always Take The Following Precautions:

- a. Use Fall Protection And Other Safety Protection As Required.
- b. Do Not Walk On Roof Flashing Such As Gutter, Rake, Hip Or Ridge Flash.
- c. Do Not Walk On Light Transmitting Panels (LTP's). They Will Not Support A Person's Weight.
- d. Guard All LTP's And Roof Openings.
- e. Step Only In The Panel Flat Directly On Or In Close Proximity To A Supporting Roof Structural.

6. After Other Trades Have Been On The Roof For Any Reason, Inspect The Roof For Damage Caused By Workers Including Chemical Or Solvent Spills, Scratches In The Paint Or Galvalume Coating, Excessive Foot Traffic And Punctures. Make Sure That All Debris Or Scrap Left Behind By Workers Is Removed From The Roof Immediately. Avoid Using Cutoff Saws And Welding Equipment Over The Roof. The Roof Must Adequately Protected.

**FOOT TRAFFIC:**  
 Keep Foot Traffic To A Minimum. Heavy Foot Traffic Can Cause Pounding On Low Pitched Roofs. This Is Particularly True Just Upslope From The Eave And At Endlaps.

Always Walk In The Flat Of The Panel Near A Supporting Roof Structural. Do Not Walk On Trim Or In Gutters.

On Bare Galvalume Roofs, Excessive Foot Traffic May Cause Black Burnish Marks. If Regular Foot Traffic Is Planned For A Roof, Provisions Should Be Made For A Properly Designed And Installed Walkway System. In Order To Limit Access To The Roof, Roof Hatchets Or Access Ladders Should Be Locked At All Times. A Sign Posted At The Access Site Stating That Only Authorized Personnel Are Allowed On The Roof. In Addition A Log Book Should Be Kept Of All Visits To The Roof And The Reason For Such Visits.

**DISSIMILAR METALS:**  
 Never Allow Your Roof To Come In Contact With, Or Water Runoff From Any Dissimilar Metal Including But Not Limited To: Copper, Lead Or Graphite. This Includes Copper And Arsenic Salts Used In Treated Lumber, Calcium Used In Concrete, Mortar And Grout.

**ROOF AND WALL PANEL DAMAGE DURING CONSTRUCTION**

## Roof And Wall Panel Damage During Construction

The Quality Of Workmanship In Steel Construction Practices And Handling Methods Used During The Construction Of The Metal Building Can Significantly Affect The Appearance And Performance Of The Building Panels. Panel Damage During Construction Can Be The Result Of Faulty Installation Methods And/or Carelessness.

Overdriven Fasteners Cause Indentations Or Shallow Pockets In The Panel Around The Fastener Head. Rain, Water Or Condensation Moisture Combined With Atmospheric Pollutants (principally Sulfur Dioxide) And Dirt Particles Collect In These Pockets. The Combination Of Pollutants And Water Creates Acid Solutions That Will Cause Corrosion Damage To The Panel And Fastener. Rain May Wash Some Pollutants Away, But Moisture In Form Of High Humidity Can Keep These Areas Wet And Continue The Problem. Overdriven The Fastener Also Forces The Sealing Washer From Under The Head Creating A Leak At This Point. Proper Torque Adjustment Of The Screw Gun Or Preferably The Use Of A Depth Gauge Will Eliminate The Problem Of Overdriven Fasteners.

It Is Extremely Important That All Drill Shavings From The Installation Of Panel Fasteners And Fillings From The Saw Cutting Of Panels Be Removed From The Panel Surface. Corrosion Can Occur In A Matter Of Hours When These Shavings Or Fillings Are Not Removed And Are In Contact With Water Or Condensed Moisture. When Panels Are Pre-Drilled Or Cut In The Stack Prior To Erection All Shavings Must Be Cleaned From Both Sides Of The Panel To Prevent Corrosion Of The Panel By These Particles. It Is Imperative That The Roof Be Swept Clean At Least Daily And Certainly At Job Completion. The Final Cleaning Of The Roof Should Be Done Prior To Installing The Gutter So That The Shavings Are Not Deposited Into The Gutter And Left To Corrode. Any Other Foreign Objects Or Debris Left By Construction Personnel Should Also Be Removed From The Roof During The Erection Of The Roof And The Installation Of Such Equipment As Air Condition Units, Etc..











Personnel Walking On The Panel Can Cause Damage. Workmen Should Step Or Walk In The Broad Flat Areas Of The Panel And Avoid Stepping On The Panel Ends And Edges Which Can Be Bent By Careless Handling. If This Damage Is Severe, The Edges Must Be Straighten Prior To Erection Since The Appearance And/Or Weather Tightness Of The Panel Could Be Affected. Dragging One Panel Across Another Can Cut Or Abrade The Coating Causing Unsightly Marks On The Panel Surface.





Attempts To Erect Panels During Windy Conditions Should Be Avoided To Prevent Damage And Of Safety Considerations.

Leaving Dirt Piled Against The Exterior Wall Panels At The Foundation Will Cause Panel Damage. This Dirt May Be Wet Or At Least Contain Some Moisture. Mud May Have Splashed Onto The Wall During Construction. Corrosion Damage May Occur Where This Dirt Is Melt Contacts The Panel. In Areas Where Lime Stabilization Of The Soil Is Required, Corrosion Damage From The Soil's Content Will Be Accelerated And Most Likely Be Severe. All Dirt Must Be Removed From The























| Page   | CF02035  | Rev | 04 |
|--|--|-----|----|
| By   |  |     |    |
| Crk'd  |  |     |    |
| Description  |  |     |    |
| Revision   |  |     |    |
| Date   |  |     |    |
| Project Name & Location:                             | Cornerstone Building Brands 500 Northwest Freeway, Suite 500 Houston, TX 77040 |     |    |
| 13105 MARA BROWN 1300 VALLEY DR OGDEN, UT 84401-0808 |  |     |    |
| Issued For Construction                              | <input checked="" type="checkbox"/>  |     |    |
| Issued For Approval                                  | <input type="checkbox"/>   |     |    |
| Issued For Permit                                    | <input type="checkbox"/>   |     |    |




|   |                                     |
|---|-------------------------------------|
| <b>FORTIFY</b><br>BUILDING SOLUTIONS  | <input checked="" type="checkbox"/> |
| Customer:<br>CITY OF OGDEN - 212366<br>2549 WASHINGTON BLVD<br>OGDEN, UT 84401  | <input type="checkbox"/>            |
| Drawing Status:<br><input type="checkbox"/> Issued For Approval<br><input type="checkbox"/> Issued For Construction   | <input type="checkbox"/>            |
| Scale: NOT TO SCALE   |                                     |
| Drawn by: AXD 12/9/25   |                                     |
| Checked by: MC 12/15/25   |                                     |
| Project Engineer:   |                                     |
| Job Number: 20-B-91454  |                                     |
| Sheet Number: R5 of 12  |                                     |
| The engineer whose seal appears hereon is employed by or is contracted to provide engineering services for the manufacturer, Cornerstone Building Brands or one of its affiliates, for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project. |                                     |
| KAUSHIKKUMAR J. PATEL, P.E.<br>UTAH P.E. 12592792-2202  |                                     |
| Jan 02, 2026  |                                     |


This item has been electronically signed and sealed by Kaushikumar J. Patel, P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.







### Door Elevation




The Adequacy Of The 1"Ø Base Anchor Is Not The Responsibility Of The Building Manufacturer. The Adequacy Of These Base Anchors Should Be Determined By A Qualified Foundation Engineer.


Verify Door Jamb Base Clip Dimensions With Patterns Shown Prior To Placement Of Door Anchors And Adjust Patterns If Needed.

Note: 12 $\frac{1}{4}$ " Frames May Not Have Kerf Door Frame Feature Depending On Door Manufacturer


## Knock Down Door Anchor Placement



## Section A



## ection B






## Section C

| Customer:   | Project Name & Location:   | Drawing Status: | Issued For Approval<br>(Not For Construction) | Issued For Construction             |
|---|--|-----------------|---|-------------------------------------|
|  <b>MUELLER</b><br>HEAT BUILDINGS, ROOFING & MORE  | <b>FORTIFY</b><br>BUILDING SOLUTIONS <sup>SM</sup><br>13105 Northwest Freeway, Suite 500<br>Houston, TX 77040<br>cornerstonebuildingbrands.com |                 | <input type="checkbox"/>                      | <input checked="" type="checkbox"/> |
| Scale:  | NOT TO SCALE   |                 |   |                                     |
| Drawn by:   | AXD  | 12/9/25         |   |                                     |
| Checked by:   | MC   | 12/15/25        |   |                                     |
| Project Engineer:   |  |                 |   |                                     |
| Job Number:   | 20-B-91454   |                 |   |                                     |
| Sheet Number:   | R7 of 12   |                 |   |                                     |
| The engineer whose seal appears hereon is employed by or is contracted to provide engineering services for the manufacturer, Cornerstone Building Brands or one of its affiliates, for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project. |  |                 |   |                                     |
| KAUSHIKKUMAR J. PATEL, P.E.<br>UTAH P.E. 12592792-2202  |  |                 |   |                                     |

02, 2026

Item has been electronically signed and sealed by  
Hikummar J. Patel, P.E. on the date and/or time  
shown using a digital signature. Printed copies of  
document are not considered signed and sealed  
until the signature must be verified by a 3rd Party  
with Authority on any electronic copy.

Knock Down Door - Girt At 7'-6" Without Low Girt








| Revision | Date   | Description   | By | Ck'd  |
|----------|--|---|----|---|
| 13105    | Northwest Freeway, Suite 500<br>Houston, TX 77040<br>cornerstonebuildingbrands.com | Project Name & Location:<br>MARA BROWN<br>1300 VALLEY DR<br>ODEN, UT 84401-0808 |    | <input checked="" type="checkbox"/> Issued For Construction |

**FORTIFY**  
BUILDING SOLUTIONS  
METAL BUILDINGS, DOORS & MORE  
Customer: CITY OF ODEN-212366  
2549 WASHINGTON BLVD  
ODEN, UT 84401  
MARA BROWN  
Drawing Status:  Issued For Approval  
 Not For Construction  
 Issued For Permit

Scale: NOT TO SCALE  
Drawn by: AXD 12/9/25  
Checked by: MC 12/15/25  
Project Engineer:  
Job Number: 20-B-91454  
Sheet Number: R8 of 12











The engineer whose seal appears hereon is employed by or is contracted to provide engineering services for the manufacturer, Cornerstone Building Brands or one of its affiliates, for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project.





KAUSHIKKUMAR J. PATEL, P.E.  
UTAH P.E. 12592792-2202



Jan 02, 2026  
No. 12592792  
KAUSHIKKUMAR J. PATEL  
PROFESSIONAL ENGINEER  
STATE OF UTAH  
KAUSHIKKUMAR J. PATEL  
No. 12592792  
KAUSHIKKUMAR J. PATEL  
PROFESSIONAL ENGINEER  
STATE OF UTAH  
This item has been electronically signed and sealed by Kaushikumar J. Patel, P.E. on the date and/or time stamp shown using a digital signature. Printed copies of this document are not considered signed and sealed and the signature must be verified by a 3rd Party Certificate Authority on any electronic copy.




















**FORTIFY**  
BUILDING SOLUTIONS

|  |   |  |
|--|---|--|
| Cornerstone Building Brands 500<br>Houston, TX 77040<br>cornerstonebuildingbrands.com    | Project Name & Location:<br>MARA BROWN<br>1300 VALLEY DR<br>ODEN, UT 84401-0808 | Issued For Construction: <input checked="" type="checkbox"/> |
| 13105 Northstar Freeway, Suite 500<br>Houston, TX 77040<br>cornerstonebuildingbrands.com | Issued For Approval: <input type="checkbox"/>                                   | Issued For Construction: <input type="checkbox"/>            |

**MUELLER**  
METAL BUILDINGS, DOORS & MORE

|   |   |
|---|---|
| CUSTOMER:<br>CITY OF OGDEN - 212366<br>2549 WASHINGTON BLVD<br>OGDEN, UT 84401<br>MARA BROWN  | Drawing Status:<br><input type="checkbox"/> Issued For Approval<br><input type="checkbox"/> Issued For Construction |
| Scale: NOT TO SCALE   | Drawn by: AXD 12/9/25   |
| Checked by: MC 12/15/25   | Project Engineer:   |
| Job Number: 20-B-91454  | Sheet Number: R11 of 12   |
| The engineer whose seal appears hereon is employed by or is contracted to provide engineering services for the manufacturer, Cornerstone Building Brands or one of its affiliates, for the materials described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for this project. |   |
| KAUSHIKKUMAR J. PATEL, P.E.<br>UTAH P.E. 12592792-2202  |   |







December 03, 2025

CITY OF OGDEN-212366  
2549 WASHINGTON BLVD  
Ogden, UT 84401

20-B-91454  
MARA BROWN  
1300 VALLEY DR OGDEN, UT 84401-0808  
40'0" x 80'0" x 16'0"

To Whom It May Concern:

This is to certify that materials for the subject structure have been designed in accordance with the order documents, specifically as shown per the attached Engineering Design Criteria Sheet.

Aspects of code compliance as related to use or occupancy, such as sprinkler requirements, are not addressed by these documents.

These materials, when properly erected on an adequate foundation in accordance with the erection drawings as supplied and using the components as furnished, will meet the attached loading requirements.

This certification does not cover field modifications, or the design of materials not furnished by Heritage Building Systems.


The attached design criteria and calculations are to remain with and form part of this Letter of Certification.

The calculations and the metal building they represent are the product of Heritage Building Systems or a division of its affiliate Cornerstone Building Brands. The engineer whose seal appears hereon is employed by either Heritage Building Systems or a division of its affiliate Cornerstone Building Brands and is not the engineer of record for this project.

Cordially,

Heritage Building Systems  
Materials for Metal Buildings  
A Cornerstone Building Brands Company

Kaushikkumar J. Patel, P.E.  
Design Engineer



This document has been  
digitally signed.

12/08/2025



## DESIGN PACKAGE

**BUILDER: CITY OF OGDEN-212366**

**CUSTOMER: MARA BROWN**

**JOB NUMBER: 20-B-91454**

### TABLE OF CONTENTS

|                     | Page |
|---------------------|------|
| Design Criteria     | 1    |
| Drawing Notes       | 2-3  |
| Deflection Criteria | 4    |
| Building A          | 5-16 |

Note to Detailing: Eds2Tekla Report (Y)

Original Design Completed thru Change Order # 0

Date: 12/03/2025

### Revision History

| Rev# | Update Reactions? | Reason for Revision | Pages Revised | Date Revised | Eng. |
|------|-------------------|---------------------|---------------|--------------|------|
|      |                   |                     |               |              |      |
|      |                   |                     |               |              |      |
|      |                   |                     |               |              |      |
|      |                   |                     |               |              |      |
|      |                   |                     |               |              |      |

Design Engineer: Rafael Arce Rabadan (Caryville)

Checking Engineer: Emmanuel Lopez Guillen

Sealing Engineer: Kaushikkumar J. Patel, P.E.

Job Number .....: 20-B-91454  
Builder .....: CITY OF OGDEN-212366  
Jobsite Location .....: MARA BROWN, OGDEN, UT

Building Code .....: 2021 IBC

Building Risk Category .....: Normal (Risk Category II)

Roof Dead Load

    Superimposed .....: 2.22 psf

    Collateral .....: 1.00 psf  
    (1.00 psf Other)

Roof Live Load .....: 20.00 psf reduction allowed

Snow

    Ground Snow Load (Pg) .....: 43.00 psf

    Snow Importance Factor (I) ..: 1.00

    Snow Exposure Factor (Ce) ..: 0.90

    Thermal Factor (Ct) .....: 1.00

    Slope Factor (Cs) .....: 1.00

    Sloped Roof Snow (Ps) .....: 27.09 psf

    Minimum Roof Snow Load (Pm) : 30.00 psf

Wind

    Ultimate Wind Speed (Vult) ..: 110 mph

    Nominal Wind Speed (Vasd) ...: 85 mph (IBC section 1609.3.1)

    Serviceability Wind Speed ...: 74 mph

    Ground Elevation Factor ....: 0.85 (4458 ft ASL)

    Wind Exposure Category ....: C

    Exposure Coefficient (MWFRS): 0.860

    Enclosure Classification ...: Enclosed Building

    Internal Pressure Coef (GCpi): 0.18/-0.18

    Unfactored Wall Loads for components not provided by building manufacturer

    Zone 5 Areas (within 4.00' of corner) : 20.82 psf pressure -27.76 psf suction

    Zone 4 Areas (away from corners) : 20.82 psf pressure -22.55 psf suction

    These values are the maximum values required based on a 10 sq ft area.

    Components with larger areas may have lower wind loads.

Seismic

    Seismic Importance Factor (Ie): 1.00

    Seismic Design Category ....: D

    Soil Site Class .....: D Stiff Soil (Default)

    Ss .....: 1.351 g                   Sds .....: 1.081 g

    S1 .....: 0.498 g                   Sd1 .....: 0.598 g

    Analysis Procedure .....: Equivalent Lateral Force

    Column Line                        1-5                   SWA & SWC

    Basic Force Resisting System     C4                   B3

    Response Modification Coefficient (R)   3.50           3.25

    Seismic Response Coefficient (Cs)    0.309           0.333

    Design Base Shear in kips (V)       6.32           6.26

    Basic Structural System (from ASCE 7-16 Table 12.2-1)

    B3 - Ordinary Steel Concentrically Braced Frame

    C4 - Ordinary Steel Moment Frame

Material properties of steel bar, plate, and sheet used in the fabrication of built-up structural framing members conform to ASTM A529, ASTM A572, or ASTM A1011 with 55 ksi min. yield, except flanges wider than 12" and thicker than 3/8", all flanges thicker than 1", and all webs thicker than 3/8" are 50 ksi min. yield. Rod X-bracing conforms to ASTM A529 or ASTM A572 with 50 ksi min. yield. Cable X-bracing conforms to ASTM A475 7 Strand Extra High-Strength grade. Hot rolled structural shapes conform to ASTM A992, ASTM A529, or ASTM A572 with 50 ksi min. yield. Hot rolled angles, other than flange braces, conform to ASTM A36 minimum. Round and rectangular HSS conforms to ASTM A500 Grade B. Cold-formed steel secondary framing Members conform to ASTM A1011 or ASTM A653 Grade 55 with 55 ksi min. yield. For Canada, material properties conform to CAN/CSA G40.20/G40.21 or equivalent.

Unless otherwise noted, special inspection of fabricated items is not required. Per IBC section 1704.2.5.1, fabricator is approved to perform such work without special inspection through maintenance of IAS AC 472 certification MB-136.

Bolted joints with A325 Type 1 bolts greater than 1/2" diameter are specified as pre-tensioned joints in accordance with the most recent edition of the RCSC Specification for Structural Joints Using ASTM A325 or A490 Bolts. Pre Tensioning can be accomplished by using the turn-of-nut method of tightening, calibrated wrench, twist-off-type tension-control bolts or direct-tension indicator as acceptable to the Inspecting Agency and Building Official. Installation inspection requirements for pre-tensioned joints (Specification for Structural Joints Section 9.2) using turn-of-nut method is suggested. The connections on this project are not slip critical.

Design criteria as noted is as given within order documents and is applied in general accordance with the applicable provisions of the model code and/or specification indicated. Neither the metal building manufacturer nor the certifying engineer declares or attests that the loads as designated are proper for local provisions that may apply or for site specific parameters. The design criteria is supplied by the builder, project owner, or an Architect and/or Engineer of Record for the overall construction project.

This project is designed using manufacturer's standard serviceability criteria. Generally this means that all deflections are within typical performance limits for normal occupancy and standard metal building products.

The metal building manufacturer has not designed the structure for snow accumulation loads at the ground level which may impose snow loads on the wall framing provided by the manufacturer.

This metal building system is designed as an Enclosed Building. Exterior and/or operable components including, but not limited to, doors, windows, vents, etc. ("Components") must be designed to withstand the required component and cladding wind pressures specified by the building code. In order to maintain the metal building system's Enclosed Building condition, all Components shall be closed when wind velocities reach half the designed wind load for the metal building system as shown on the drawings and design criteria documentation. Failure to maintain the metal building system's Enclosed Building condition will violate and void all warranties and certifications applicable to the material supplied by the metal building

manufacturer.

The use of fully exposed for the snow exposure results in the rigid frames being designed for only 90 percent of the roof snow load that is used for partially exposed. For a fully exposed snow exposure to be used, all of the following conditions must be true:

1. The roof is exposed to wind on all sides with no obstructions higher than the roof located closer to the building than a distance equal to 10 times the height of the obstruction above the roof.
2. The roof is exposed to wind on all sides with no significant obstructions on the roof such as parapet walls or large roof top mechanical units.
3. The roof is not exposed to accumulation of snow due to drifting or sliding from adjacent structures.

Framed openings, walk doors, and open areas shall be located in the bay and elevation as shown in the erection drawings. The cutting or removal of girts shown on the erection drawings due to the addition of framed openings, walk doors, or open areas not shown may void the design certifications supplied by the metal building manufacturer.

The framing at BLDG A Frame Line 1 and 5 is NOT designed to receive a future bay addition. Corresponding frame reactions are calculated based upon actual tributary area.

Job Number .....: 20-B-91454  
Builder .....: CITY OF OGDEN-212366  
Jobsite Location .....: MARA BROWN, OGDEN, UT

The material supplied by the manufacturer has been designed with the following minimum deflection criteria. The actual deflection may be less depending on actual load and actual member length.

BUILDING DEFLECTION LIMITS .....: BLDG-A

| Roof Limits             | Rafters | Purlins | Panels |
|-------------------------|---------|---------|--------|
| -----                   | -----   | -----   | -----  |
| Live: L/                | 180     | 150     | 60     |
| Snow: L/                | 180     | 180     | 60     |
| Serviceability Wind: L/ | 180     | 180     | 60     |
| Total Gravity: L/       | 120     | 120     | 60     |
| Total Uplift: L/        | N/A     | N/A     | 60     |

| Frame Limits            | Sidesway |
|-------------------------|----------|
| -----                   | -----    |
| Live: H/                | 60       |
| Snow: H/                | 60       |
| Serviceability Wind: H/ | 60       |
| Seismic Drift: H/       | 40       |
| Total Gravity: H/       | 60       |
| Service Seismic: H/     | 40       |


| Wall Limits               | Limit |
|---------------------------|-------|
| -----                     | ----- |
| Total Wind Panels: L/     | 60    |
| Total Wind Girts: L/      | 90    |
| Total Wind EW Columns: L/ | 120   |

The Service Seismic limit as shown here is at service level loads.

key Strut: x=double Z,  
              xx=triple Z,  
              o=pipe(FM)

## BUILDING A

Builder :  
CITY OF OGDEN-212366  
Job No: 91454A run01  
Version: ver01-rafael.arce  
Wed Dec 3 17:04:22 2025



Owner :  
MARA BROWN  
OGDEN UT 84401-0808  
P.O. HBS-PH-254812...

Heritage

Design Summary Program

Design Summary Report

User: Rafael.arcer Job Number: 91454A  
Version: 8.23.4 run01 Date: 12/03/25  
Start Time: 17:04:08

R:\..\20-B-91454\ver01-rafael.arcerabadan\BLDG-A\run01\91454A\_bldg\_A\_01.cds

---

#### BUILDING-A-DESIGN SUMMARY REPORT

All connections use ASTM F3125 Gr. A325N bolts, unless noted otherwise.  
All anchor rods are checked according to ASTM F1554 Gr. 36 strengths.

Roof Plane ----- RPA

R:\jobs\Active\Eng\20-B-91454\ver01-rafael.arcerabadan\BLDG-A\run01\AroofRPA\_01.edf

Panel ..... PBR  
Panel width ..... 36 in.  
Panel gage ..... 26 ga.  
Purlins ..... 55.0 ksi yield strength  
Eave struts ..... 55.0 ksi yield strength

Horz. Purlin Spacing: 2@4.3989 2@5'0 1.2022

| Bay<br># | Length<br>(ft) | Member<br>Identification | Brace<br>Locations | L Lap<br>Exten | R Lap<br>Exten |
|----------|----------------|--------------------------|--------------------|----------------|----------------|
| 1        | 20.000         | 8X2.5Z14                 | None               | S 0.000        | 2.479 C        |
| 2        | 20.000         | 8X2.5Z14                 | None               | C 2.479        | 1.479 C        |
| 3        | 20.000         | 8X2.5Z14                 | None               | C 1.479        | 2.479 C        |
| 4        | 20.000         | 8X2.5Z14                 | None               | C 2.479        | 0.000 S        |

---

Purlin Clip Use 2 A325 Bolts  
@ Level: 2,3,4,5  
@ Supports: 1,2,3,4,5

Purlin Stiffened Clips  
@ Level: 2,5  
@ Supports: 1,2,3,4,5

Purlin Backup Plate  
@ Level: 2,5  
@ Supports: 1,2,3,4,5

Heritage

Design Summary Program  
Design Summary Report

User: Rafael.arcer Job Number: 91454A  
Version: 8.23.4 run01 Date: 12/03/25  
Start Time: 17:04:08

R:\..\20-B-91454\ver01-rafael.arcerabadan\BLDG-A\run01\91454A\_bldg\_A\_01.cds

---

Roof Plane ----- RPC

R:\jobs\Active\Eng\20-B-91454\ver01-rafael.arcerabadan\BLDG-A\run01\AroofRPC\_01.edf

Panel ..... PBR  
Panel width ..... 36 in.  
Panel gage ..... 26 ga.  
Purlins ..... 55.0 ksi yield strength  
Eave struts ..... 55.0 ksi yield strength

Horz. Purlin Spacing: 2@4.3989 2@5'0 1.2022

| Bay # | Length (ft) | Member Identification | Brace Locations | L Exten | R Exten |
|-------|-------------|-----------------------|-----------------|---------|---------|
| 1     | 20.000      | 8X2.5Z14              | None            | S 0.000 | 2.479 C |
| 2     | 20.000      | 8X2.5Z14              | None            | C 2.479 | 1.479 C |
| 3     | 20.000      | 8X2.5Z14              | None            | C 1.479 | 2.479 C |
| 4     | 20.000      | 8X2.5Z14              | None            | C 2.479 | 0.000 S |

---

Purlin Clip Use 2 A325 Bolts

@ Level: 2,3,4,5  
@ Supports: 5,4,3,2,1

Purlin Stiffened Clips

@ Level: 2,5  
@ Supports: 5,4,3,2,1

Purlin Backup Plate

@ Level: 2,5  
@ Supports: 5,4,3,2,1

|     |              |                       |      |   |
|-----|--------------|-----------------------|------|---|
| SWC | Eave Strut @ | 16.000 (ft): 8X3.5E14 | Bays | 1 |
| SWC | Eave Strut @ | 16.000 (ft): 8X3.5E14 | Bays | 2 |
| SWC | Eave Strut @ | 16.000 (ft): 8X3.5E14 | Bays | 3 |
| SWC | Eave Strut @ | 16.000 (ft): 8X3.5E14 | Bays | 4 |

|     |                |                       |      |   |
|-----|----------------|-----------------------|------|---|
| RPC | Purlin Strut @ | 20.000 (ft): 8X2.5Z14 | Bays | 1 |
| RPC | Purlin Strut @ | 20.000 (ft): 8X2.5Z14 | Bays | 2 |
| RPC | Purlin Strut @ | 20.000 (ft): 8X2.5Z14 | Bays | 3 |
| RPC | Purlin Strut @ | 20.000 (ft): 8X2.5Z14 | Bays | 4 |

|     |              |                       |      |   |
|-----|--------------|-----------------------|------|---|
| SWA | Eave Strut @ | 16.000 (ft): 8X3.5E14 | Bays | 1 |
| SWA | Eave Strut @ | 16.000 (ft): 8X3.5E14 | Bays | 2 |
| SWA | Eave Strut @ | 16.000 (ft): 8X3.5E14 | Bays | 3 |
| SWA | Eave Strut @ | 16.000 (ft): 8X3.5E14 | Bays | 4 |

Note: 1) All roof and wall strut bay numbers are as viewing the roof or wall plane  
2) All purlin strut locations for all roof planes are measured from back sidewall  
3) All purlin strut rows use the same lap lengths as the main purlin design.

Heritage

Design Summary Program

Design Summary Report

User: Rafael.arcer Job Number: 91454A  
Version: 8.23.4 run01 Date: 12/03/25  
Start Time: 17:04:09

R:\..\20-B-91454\ver01-rafael.arcerabadan\BLDG-A\run01\91454A\_bldg\_A\_01.cds

---

- 4) Eave strut interior connection at SWA uses (2)-1/2" A325 bolts.
- 5) Eave strut interior connection at SWC uses (2)-1/2" A325 bolts.
- 6) Eave strut connection at end-frame uses (4)-1/2" A325 bolts.

Bracing ---- Roof: 1 bays Rod

Plane SWA : 1 bays Rod: Hillside Washers  
Plane SWC : 1 bays Rod: Hillside Washers  
Plane EWB : End Frame  
Plane EWD : End Frame

Heritage

Design Summary Program

Design Summary Report

User: Rafael.arcer Job Number: 91454A  
Version: 8.23.4 run01 Date: 12/03/25  
Start Time: 17:04:09

R:\..\20-B-91454\ver01-rafael.arcerabadan\BLDG-A\run01\91454A\_bldg\_A\_01.cds

---

Sidewall Plane SWA -- ( 8.250" Inset columns)

R:\jobs\Active\Eng\20-B-91454\ver01-rafael.arcerabadan\BLDG-A\run01\AwallSWA\_01.edf

Panel ..... PBR  
Panel width ..... 36 in.  
Panel gage ..... 26 ga.  
Girts ..... 55.0 ksi yield strength

Girts Spacing: 7'6 4'2

| Bay # | Elev. (ft-in) | Length (ft) | Member Size Identification | Brace Locations | L Exten | R Exten |
|-------|---------------|-------------|----------------------------|-----------------|---------|---------|
| 1     | 7'6           | 20.000      | 8X2.5Z16                   | None            | S 0.000 | 1.479 C |
| 2     | 7'6           | 20.000      | 8X2.5Z16                   | None            | C 1.479 | 1.479 C |
| 3     | 7'6           | 20.000      | 8X2.5Z16                   | None            | C 1.479 | 1.479 C |
| 4     | 7'6           | 20.000      | 8X2.5Z16                   | None            | C 1.479 | 0.000 S |
| 1     | 11'8          | 20.000      | 8X2.5Z16                   | None            | S 0.000 | 1.479 C |
| 2     | 11'8          | 20.000      | 8X2.5Z16                   | None            | C 1.479 | 1.479 C |
| 3     | 11'8          | 20.000      | 8X2.5Z16                   | None            | C 1.479 | 1.479 C |
| 4     | 11'8          | 20.000      | 8X2.5Z16                   | None            | C 1.479 | 0.000 S |

Note: Maximum distance to extend girt from adjacent bay is 36.00 inches.

Heritage

Design Summary Program

Design Summary Report

User: Rafael.arcer Job Number: 91454A  
Version: 8.23.4 run01 Date: 12/03/25  
Start Time: 17:04:09

R:\..\20-B-91454\ver01-rafael.arcerabadan\BLDG-A\run01\91454A\_bldg\_A\_01.cds

---

Sidewall Plane SWC -- ( 8.250" Inset columns)

R:\jobs\Active\Eng\20-B-91454\ver01-rafael.arcerabadan\BLDG-A\run01\AwallSWC\_01.edf

Panel ..... PBR  
Panel width ..... 36 in.  
Panel gage ..... 26 ga.  
Girts ..... 55.0 ksi yield strength

Girts Spacing: 7'6 4'2

| Bay # | Elev. (ft-in) | Length (ft) | Member Size Identification | Brace Locations | L Exten | R Exten |
|-------|---------------|-------------|----------------------------|-----------------|---------|---------|
| 1     | 7'6           | 20.000      | 8X2.5Z16                   | None            | S 0.000 | 1.479 C |
| 2     | 7'6           | 20.000      | 8X2.5Z16                   | None            | C 1.479 | 1.479 C |
| 3     | 7'6           | 20.000      | 8X2.5Z16                   | None            | C 1.479 | 1.479 C |
| 4     | 7'6           | 20.000      | 8X2.5Z16                   | None            | C 1.479 | 0.000 S |
| 1     | 11'8          | 20.000      | 8X2.5Z16                   | None            | S 0.000 | 1.479 C |
| 2     | 11'8          | 20.000      | 8X2.5Z16                   | None            | C 1.479 | 1.479 C |
| 3     | 11'8          | 20.000      | 8X2.5Z16                   | None            | C 1.479 | 1.479 C |
| 4     | 11'8          | 20.000      | 8X2.5Z16                   | None            | C 1.479 | 0.000 S |

Note: Maximum distance to extend girt from adjacent bay is 36.00 inches.

Heritage

Design Summary Program  
Design Summary Report

User: Rafael.arcer Job Number: 91454A  
Version: 8.23.4 run01 Date: 12/03/25  
Start Time: 17:04:09

R:\..\20-B-91454\ver01-rafael.arcerabadan\BLDG-A\run01\91454A\_bldg\_A\_01.cds

---

Endwall Plane EWB Design .....RIGID BEARING FRAME

R:\jobs\Active\Eng\20-B-91454\ver01-rafael.arcerabadan\BLDG-A\run01\AwallEWB\_01.edf

Panel ..... PBR  
Panel width ..... 36 in.  
Panel gage ..... 26 ga.

Girts ..... 55.0 ksi yield strength

Girts Spacing: 7'6 6'6

| Bay # | Elev. (ft-in) | Length (ft) | Member Size Identification | Brace Locations | L Exten | R Exten |       |   |
|-------|---------------|-------------|----------------------------|-----------------|---------|---------|-------|---|
| 1     | 7'6           | 19.312      | 8X2.5Z16                   | F.O.            | S       | 0.000   | 0.000 | S |
| 2     | 7'6           | 19.312      | 8X2.5Z16                   | F.O.            | S       | 0.000   | 0.000 | S |
| 1     | 14'0          | 19.312      | 8X2.5C14                   | None            | S       | 0.000   | 0.000 | S |
| 2     | 14'0          | 19.312      | 8X2.5C14                   | None            | S       | 0.000   | 0.000 | S |

Framed Openings:

| Width | Height | Sill Ht | Jamb     | Header/Sill       | Bay | Distance |
|-------|--------|---------|----------|-------------------|-----|----------|
| 16'0  | 14'0   | N/A     | 8X2.5C16 | <u>Toe up Cee</u> | 1   | 2'6      |
| 16'0  | 14'0   | N/A     | 8X2.5C16 | <u>Toe up Cee</u> | 2   | 1'0      |

Columns ---- ( 0.000" Inset columns)

| Col. # | Dist. from left | Description Member Size Ident. | Base Elev (ft) | Base plate design information Thickness & rods |
|--------|-----------------|--------------------------------|----------------|--|
| 1-B    | 20.000'         | <u>Frame Line 1</u>            |                |  |

Endwall Column to Bridge Channel Connections:

Strut-to-Column Clip  
Col. No. Endwall Plane 1

---

Plane SWC:  
1-B At Peak, Type 3 Conn., (4)-1/2" A325N  
CF Brdg Channel (0.375") w/ (4)-3/4" A325N bolts  
W8x10 Column Extension w/ 12.000" lap length  
8X2.5C12 Bridge Channel

Plane SWA:

Heritage

Design Summary Program  
Design Summary Report

User: Rafael.arcer Job Number: 91454A  
Version: 8.23.4 run01 Date: 12/03/25  
Start Time: 17:04:09

R:\..\20-B-91454\ver01-rafael.arcerabadan\BLDG-A\run01\91454A\_bldg\_A\_01.cds

---

Endwall Plane EWD Design .....RIGID BEARING FRAME

R:\jobs\Active\Eng\20-B-91454\ver01-rafael.arcerabadan\BLDG-A\run01\AwallEWD\_01.edf

Panel ..... PBR  
Panel width ..... 36 in.  
Panel gage ..... 26 ga.

Girts ..... 55.0 ksi yield strength

Girts Spacing: 7'6 6'6

| Bay # | Elev. (ft-in) | Length (ft) | Member Size Identification | Brace Locations | L Exten | R Exten |       |   |
|-------|---------------|-------------|----------------------------|-----------------|---------|---------|-------|---|
| 1     | 7'6           | 19.312      | 8X2.5Z16                   | F.O.            | S       | 0.000   | 0.000 | S |
| 2     | 7'6           | 19.312      | 8X2.5Z16                   | F.O.            | S       | 0.000   | 0.000 | S |
| 1     | 14'0          | 19.312      | 8X2.5C14                   | None            | S       | 0.000   | 0.000 | S |
| 2     | 14'0          | 19.312      | 8X2.5C14                   | None            | S       | 0.000   | 0.000 | S |

Framed Openings:

| Width | Height | Sill Ht | Jamb     | Header/Sill       | Bay | Distance |
|-------|--------|---------|----------|-------------------|-----|----------|
| 16'0  | 14'0   | N/A     | 8X2.5C16 | <u>Toe up Cee</u> | 1   | 2'6      |
| 16'0  | 14'0   | N/A     | 8X2.5C16 | <u>Toe up Cee</u> | 2   | 1'0      |

Columns ---- ( 0.000" Inset columns)

| Col # | Dist. from left | Description Member Size Ident. | Base E elev (ft) | Base plate design information Thickness & rods |
|-------|-----------------|--------------------------------|------------------|--|
| 5-B   | 20.000'         | <u>Frame Line 5</u>            |                  |  |

Endwall Column to Bridge Channel Connections:

Strut-to-Column Clip

Col. No. Endwall Plane 5

Plane SWA:

5-B At Peak, Type 3 Conn., (4)-1/2" A325N  
CF Brdg Channel (0.375") w/ (4)-3/4" A325N bolts  
W8x10 Column Extension w/ 12.000" lap length  
8X2.5C12 Bridge Channel


Plane SWC:

| Frames ----- | Type   | Span         | Live | Wind   | Eave  | Trib | Grid Labels |
|--------------|--------|--------------|------|--------|-------|------|-------------|
| CS           | 40.000 | 20.00/110.00 |      | 16.00/ | 19.75 | 2,4  |             |
| CS           | 40.000 | 20.00/110.00 |      | 16.00/ | 20.00 | 3    |             |
| MS           | 40.000 | 20.00/110.00 |      | 16.00/ | 10.25 | 1    |             |
| MS           | 40.000 | 20.00/110.00 |      | 16.00/ | 10.25 | 5    |             |

Note: Use square anchor rod layout.

**Heritage Building Systems** FRAME ID #3  
8600 S. I-35, Oklahoma City, OK 73149 ms1 40./16./10.25 20./110./43. USER NAME:Rafael.arcerabad DATE:12/03/25 TIME:17:11:05 PAGE: 3 -1  
JOB NAME:91454A FILE:frame\_1.fra  
LOCATION: Gridlines 1  
DETAIL FILE: \20-B-91454\ver01-rafael.arcerabadan\BLDG-A\Drftg\x03L  
BOLTS-A325 FULLY TIGHT WEIGHT: 1340 lbs  
PURLINS(horz. from eave): 8"-Z 204"4", 13/16", 205'  
GIRTS (vert. from floor): 8"-Z 7'6", 4'2" (8.25")


(1) All sectional dimensions are in inches.  
(2) All Flange lengths are measured along outer flange.



**CONNECTION DETAILS : GRIDLINES \* = 1**

| Location  | (1)*-C    | (2)    | (3)        | (4)       | (5)      | (6)       | (7)     | (8)*-B    | (9)          |
|-----------|-----------|--------|------------|-----------|----------|-----------|---------|-----------|--------------|
| Web Dep.  | 9.0       | 9.0    | 9.0        | N/A       | 10.0     | 8.0       | 17.5135 | 8.0       | 8.0          |
| Type      | BASE      | SPLICE | HORZ STF   | CAP (EXT) | 2E/2E    | 2E/2E     | SPLICE  | BASE      | CAP/STF      |
| Plate(DN) | 6.0X0.375 | N/A    | 2.375X0.25 | 5.0X0.25  | 8.0X0.75 | 6.0X0.375 | N/A     | 6.0X0.375 | 6.0X0.375    |
| Plate(UP) | N/A       | N/A    | N/A        | N/A       | 8.0X0.75 | 6.0X0.375 | N/A     | N/A       | 2.375X0.3125 |
| Bolts     | (4)-3/4   | N/A    | N/A        | N/A       | (8)-3/4  | (8)-3/4   | N/A     | (4)-3/4   | (4)-1/2      |


**Heritage Building Systems** FRAME ID #1 DATE: 12/03/25 TIME: 17:10:50 PAGE: 1 -1  
8600 S. I-35, Oklahoma City, OK 73149 cs 40./16./19.75 20./110./43. USER NAME: Rafael.arcerabad  
JOB NAME: 91454A FILE: frames\_2\_4.fra  
LOCATION: Gridlines 2 4  
DETAIL FILE: \20-B-91454\ver01-rafael.arcerabadan\BLDG-A\Drftg\x01L  
BOLTS: A325 FULLY TIGHT WEIGHT: 1248 lbs  
PURLINS (horiz. from eave): 8"-Z 204.4 13/16", 285'  
GIRTS (vert. from floor): 8"-Z 7'6", 4'2" (8.25")



**CONNECTION DETAILS : GRIDLINES \* = 2 4**

| Location  | (1)*-C    | (2)     | (3)        | (4)       | (5)      | (6)    | (7)     |
|-----------|-----------|---------|------------|-----------|----------|--------|---------|
| Web Dep.  | 8.0       | 11.4668 | 13.0       | N/A       | 13.5     | 13.5   | 13.5    |
| Type      | BASE      | SPLICE  | HORZ STF   | CAP (EXT) | 2E/2E    | SPLICE | 2E/2E   |
| Plate(DN) | 6.0X0.375 | N/A     | 2.375X0.25 | 5.0X0.25  | 6.0X0.75 | N/A    | 6.0X0.5 |
| Plate(UP) | N/A       | N/A     | N/A        | N/A       | 6.0X0.75 | N/A    | 6.0X0.5 |
| Bolts     | (4)-3/4   | N/A     | N/A        | N/A       | (8)-3/4  | N/A    | (8)-3/4 |


**Heritage Building Systems** FRAME ID #2  
8600 S. I-35, Oklahoma City, OK 73149 cs 40./16./20. 20./110./43. USER NAME:Rafael.arcerabad DATE:12/03/25 TIME:17:10:59 PAGE: 2 -1  
DETAIL FILE: \20-B-91454\ver01-rafael.arcerabadan\BLDG-A\Drftg\x02L JOB NAME:91454A FILE:frame\_3.fra  
LOCATION: Gridlines 3  
BOLTS-A325 FULLY TIGHT WEIGHT: 1248 lbs  
PURLINS(horz. from eave): 8"-Z 204.4 13/16", 285'  
GIRTS (vert. from floor): 8"-Z 7'6", 4'2" (8.25")



**CONNECTION DETAILS : GRIDLINES \* = 3**

| Location  | (1)*-C    | (2)     | (3)        | (4)       | (5)      | (6)    | (7)     |
|-----------|-----------|---------|------------|-----------|----------|--------|---------|
| Web Dep.  | 8.0       | 11.4668 | 13.0       | N/A       | 13.5     | 13.5   | 13.5    |
| Type      | BASE      | SPLICE  | HORZ STF   | CAP (EXT) | 2E/2E    | SPLICE | 2E/2E   |
| Plate(DN) | 6.0x0.375 | N/A     | 2.375x0.25 | 5.0x0.25  | 6.0x0.75 | N/A    | 6.0x0.5 |
| Plate(UP) | N/A       | N/A     | N/A        | N/A       | 6.0x0.75 | N/A    | 6.0x0.5 |
| Bolts     | (4)-3/4   | N/A     | N/A        | N/A       | (8)-3/4  | N/A    | (8)-3/4 |

**Heritage Building Systems** FRAME ID #4 DATE: 12/03/25 PAGE: 4 - 1  
 8600 S. I-35, Oklahoma City, OK 73149 ms1 40./16./10.25 20./110./43. TIME: 17:10:54 FILE: frame\_5.fra  
**LOCATION:** Gridlines 5 (1) All sectional dimensions are in inches.  
**DETAIL FILE:** \20-B-91454\ver01-rafael.arcerabadan\BLDG-A\Drftg\x04L (2) All Flange lengths are measured along outer flange.  
**BOLTS:**A325 FULLY TIGHT WEIGHT: 1340 lbs  
**PURLINS**(horz. from eave): 8"-Z 2@4'4 13/16", 2@5'  
**GIRTS** (vert. from floor): 8"-Z 7 1/2", 4 1/2" (8.25")



CONNECTION DETAILS : GRIDLINES \* = 5

| Location  | ①*-C      | ②        | ③          | ④         | ⑤        | ⑥         | ⑦        | ⑧)*-B     | ⑨            |
|-----------|-----------|----------|------------|-----------|----------|-----------|----------|-----------|--------------|
| Web Dep.  | 9.0       | 9.0      | 9.0        | N/A       | 10.0     | 8.0       | 17.5135  | 8.0       | 8.0          |
| Type      | BASE      | SPLICING | HORZ STF   | CAP (EXT) | 2E/2E    | 2E/2E     | SPLICING | BASE      | CAP/STF      |
| Plate(DN) | 6.0x0.375 | N/A      | 2.375x0.25 | 5.0x0.25  | 8.0x0.75 | 6.0x0.375 | N/A      | 6.0x0.375 | 6.0x0.375    |
| Plate(UP) | N/A       | N/A      | N/A        | N/A       | 8.0x0.75 | 6.0x0.375 | N/A      | N/A       | 2.375x0.3125 |
| Bolts     | (4)-3/4   | N/A      | N/A        | N/A       | (8)-3/4  | (8)-3/4   | N/A      | (4)-3/4   | (4)-1/2      |

Eds2Tekla

User:  
rafael.arcerabada  
n

Job Number: 20-B-91454

Oklahoma City

Date: 12/03/2025 05:28:53 PM

Relative path: \\OKCSNA01\TS\jobs\Active\Eng\20-B-91454

Building: BLDG-A

CDS file name: 20-B-91454\_BLDG-A\_Eds2Tekla.cds

## Planes

| Name | File  |
|------|---|
| SWA  | \ver01-rafael.arcerabandan\BLDG-A\run01\AwallSWA_01.edf |
| EWD  | \ver01-rafael.arcerabandan\BLDG-A\run01\AwallEWD_01.edf |
| SWC  | \ver01-rafael.arcerabandan\BLDG-A\run01\AwallSWC_01.edf |
| EWB  | \ver01-rafael.arcerabandan\BLDG-A\run01\AwallEWB_01.edf |
| RPA  | \ver01-rafael.arcerabandan\BLDG-A\run01\AroofRPA_01.edf |
| RPC  | \ver01-rafael.arcerabandan\BLDG-A\run01\AroofRPC_01.edf |

## Frames

| Frame Line | Left Frame | Left File                                    | Right Frame | Right File                                   |
|------------|------------|--|-------------|--|
| 1          | E          | \ver01-rafael.arcerabandan\BLDG-A\DRFTG\x03L | E           | \ver01-rafael.arcerabandan\BLDG-A\DRFTG\x03L |
| 2          | F          | \ver01-rafael.arcerabandan\BLDG-A\DRFTG\x01L | F           | \ver01-rafael.arcerabandan\BLDG-A\DRFTG\x01L |
| 3          | G          | \ver01-rafael.arcerabandan\BLDG-A\DRFTG\x02L | G           | \ver01-rafael.arcerabandan\BLDG-A\DRFTG\x02L |
| 4          | F          | \ver01-rafael.arcerabandan\BLDG-A\DRFTG\x01L | F           | \ver01-rafael.arcerabandan\BLDG-A\DRFTG\x01L |
| 5          | H          | \ver01-rafael.arcerabandan\BLDG-A\DRFTG\x04L | H           | \ver01-rafael.arcerabandan\BLDG-A\DRFTG\x04L |

## Portal Frames

| Plane Name | Bay | Frame | File |
|------------|-----|-------|------|
|            |     |       |      |



## REACTIONS

**BUILDER: CITY OF OGDEN-212366**

**CUSTOMER: MARA BROWN**

**JOB NUMBER: 20-B-91454**

### Notes

1. The reactions provided are based on the Order Documents at the time of mailing. Any changes to building loads or dimensions may change the reactions. The reactions will be superseded and voided by any future mailing.
2. The reactions provided have been created with the following layout (unless noted otherwise).
  - a. A reaction table is provided with the reactions for each load group.
  - b. Rigid Frames  
See Note 3.
  - c. Endwalls  
1. See Note 3.
  - d. X-Bracing
    1. X- Bracing reactions are included in values shown in the reaction tables.
    2. For IBC and UBC based building codes, when x-bracing is present in the sidewall, individual longitudinal seismic loads (RBUPEQ, RBDWEQ, E+, E- and LEQ) do not include the amplification factor, W
    3. For IBC and UBC based building codes, when x-bracing is present in the endwall, individual transverse seismic loads (EL & ER) do not include the amplification factor, W
  - e. The metal building manufacturer is responsible only for the portion of the anchor rod design pertaining to the transfer of forces between the base plate bearing and the anchor rod's shear and tension. The metal building manufacturer is not responsible for the anchor rod embedment for transfer of forces to the foundation. The metal building manufacturer does not design and is not responsible for the design, material, and construction of the foundation embedments. The end use customer shall assure that adequate provisions are made to the foundation design for loads imposed by column reactions of the building, other imposed loads, and bearing capacity of the soil and other conditions of the building site. It is recommended that the anchorage and foundation of the building be designed by a registered professional engineer competent in the design of such structures.
    - i. (ref. Appendix A3 of the MBMA Metal Building Systems Manual)
  - f. Anchor rods are ASTM F1554 Gr. 36 material unless noted otherwise on the anchor rod layout drawing.
3. Reactions are provided as un-factored for each load group applied to the column. The factors applied to load groups for the steel column design may be different than the factors used in the foundation design. The foundation engineer shall apply the appropriate load factors and combine the reactions in accordance with the building code and design specifications for proper foundation design.
  - a. For projects using ultimate design wind speeds such as 2012 IBC, 2015 IBC, or Florida building code, the wind load reactions are at a strength value with a load factor of 1.0.
  - b. For IBC codes, the seismic reactions provided are at a strength level with a load factor of 1.0, and do not contain the rho factor.  
*The manufacturer does not provide "maximum" load combination reactions. However, the individual load reactions provided may be used by the foundation engineer to determine the applicable load combinations for his/her design procedures and allow for an economical foundation design.*

## SUPPORT REACTIONS FOR EACH LOAD GROUP

\*LOCATION: Gridlines: 1


NOTES:(1) All reactions are in kips and kip-ft.

(2) Primary wind load cases are not concurrent.

(3) X-bracing reactions (RBPULW and RBUPEQ) are combined with LWL and LEQ groups only.

TIME:17:11:05

## REACTION NOTATIONS



## LOAD GROUP REACTION TABLE GRIDLINES \* = 1

| COLUMN | *-C  |      |      | *-A  |      |      | *-B  |      |      |
|--------|------|------|------|------|------|------|------|------|------|
|        | H    | V    | L    | H    | V    | L    | H    | V    | L    |
| DL     | 0.0  | 0.5  | -0.0 | -0.0 | 0.5  | -0.0 | 0.0  | 1.0  | -0.0 |
| COLL   | 0.0  | 0.1  | -0.0 | -0.0 | 0.1  | -0.0 | 0.0  | 0.2  | -0.0 |
| PLL1   | 0.1  | 2.0  | -0.0 | -0.1 | -0.2 | -0.0 | 0.0  | 2.3  | -0.0 |
| PLL2   | 0.1  | -0.2 | -0.0 | -0.1 | 2.0  | -0.0 | -0.0 | 2.3  | -0.0 |
| SNOW   | 0.2  | 2.7  | -0.0 | -0.2 | 2.7  | -0.0 | 0.0  | 6.9  | -0.0 |
| LL     | 0.2  | 1.8  | -0.0 | -0.2 | 1.8  | -0.0 | 0.0  | 4.6  | -0.0 |
| EQ     | -0.4 | -0.3 | -0.0 | -0.4 | 0.3  | -0.0 | 0.2  | 0.0  | -0.4 |
| WL1    | -1.7 | -3.0 | -0.0 | -1.6 | -0.7 | -0.0 | 0.0  | -4.3 | -0.0 |
| WL2    | -2.1 | -2.1 | -0.0 | -1.2 | 0.2  | -0.0 | 0.0  | -3.1 | -0.0 |
| LWL1   | 0.9  | -2.5 | -0.0 | -0.5 | -1.7 | -0.0 | -0.0 | -3.5 | -3.1 |
| LWL2   | 0.5  | -1.7 | -0.0 | -0.9 | -2.5 | -0.0 | -0.0 | -3.5 | -3.1 |
| LWL3   | 0.5  | -1.7 | -0.0 | -0.1 | -0.9 | -0.0 | 0.0  | -2.3 | 3.1  |
| LWL4   | 0.1  | -0.9 | -0.0 | -0.5 | -1.7 | -0.0 | 0.0  | -2.3 | 3.1  |
| WL3    | 1.6  | -0.7 | -0.0 | 1.7  | -3.0 | -0.0 | -0.0 | -4.3 | -0.0 |
| WL4    | 1.2  | 0.2  | -0.0 | 2.1  | -2.1 | -0.0 | -0.0 | -3.1 | -0.0 |
| SBAL   | 0.2  | 2.4  | -0.0 | -0.2 | 2.4  | -0.0 | 0.0  | 6.3  | -0.0 |
| RS     | 0.2  | 0.4  | -0.0 | -0.2 | 2.9  | -0.0 | -0.0 | 5.3  | -0.0 |
| LS     | 0.2  | 2.9  | -0.0 | -0.2 | 0.4  | -0.0 | 0.0  | 5.3  | -0.0 |

## LOAD GROUP DESCRIPTION

|      |   |   |
|------|---|---|
| DL   | : | Roof Dead Load                                    |
| COLL | : | Roof Collateral Load                              |
| PLL1 | : | Pattern Live Load [PLLxx]                         |
| PLL2 | : | Pattern Live Load [PLLxx]                         |
| SNOW | : | Roof Snow Load                                    |
| LL   | : | Roof Live Load                                    |
| EQ   | : | Lateral Seismic Load [parallel to plane of frame] |
| WL1  | : | Wind from Left to Right with +GCpi                |
| WL2  | : | Wind from Left to Right with -GCpi                |
| LWL1 | : | Windward Corner Left with +GCpi                   |
| LWL2 | : | Windward Corner Right with +GCpi                  |
| LWL3 | : | Windward Corner Left with -GCpi                   |
| LWL4 | : | Windward Corner Right with -GCpi                  |
| WL3  | : | Wind from Right to Left with +GCpi                |
| WL4  | : | Wind from Right to Left with -GCpi                |
| SBAL | : | Code Calculated Balanced Roof Snow Load           |
| RS   | : | Unbalanced Right Roof Snow Load                   |
| LS   | : | Unbalanced Left Roof Snow Load                    |

## ADDITIONAL NOTES:

( 1 ) Pattern live or snow load cases are not concurrent with any other live or snow load cases.


## SUPPORT REACTIONS FOR EACH LOAD GROUP

\*LOCATION: Gridlines: 2 4

NOTES:(1) All reactions are in kips and kip-ft.  
 (2) The seismic overstrength factor (Omega) is not included in the "RBDWEQ" and "RBUPEQ" Load Group reactions.  
 Seismic "BASE-ONLY" combination reactions include an overstrength factor of: 2.000  
 (3) Primary wind load cases are not concurrent.  
 (4) X-bracing reactions (RBPULW and RBUPEQ) are combined with LWL and LEQ groups only.

TIME:17:10:50

## REACTION NOTATIONS



## LOAD GROUP REACTION TABLE GRIDLINES \* = 2 4

| COLUMN     | *-C  |      |      | *-A  |      |      |
|------------|------|------|------|------|------|------|
|            | H    | V    | L    | H    | V    | L    |
| LOAD GROUP |      |      |      |      |      |      |
| DL         | 0.4  | 1.4  | -0.0 | -0.4 | 1.4  | -0.0 |
| COLL       | 0.1  | 0.4  | -0.0 | -0.1 | 0.4  | -0.0 |
| SNOW       | 3.5  | 11.9 | -0.0 | -3.5 | 11.8 | -0.0 |
| LL         | 1.4  | 4.7  | -0.0 | -1.4 | 4.7  | -0.0 |
| RBDWEQ     | -0.0 | 2.5  | -0.0 | 0.0  | 2.5  | -0.0 |
| EQ         | -0.7 | -0.6 | -0.0 | -0.7 | 0.6  | -0.0 |
| RBUPEQ     | 0.0  | -2.5 | -3.1 | -0.0 | -2.5 | -3.1 |
| WL1        | -3.4 | -6.9 | -0.0 | -0.9 | -4.1 | -0.0 |
| WL2        | -3.7 | -4.2 | -0.0 | -0.7 | -1.4 | -0.0 |
| WL3        | 0.9  | -4.1 | -0.0 | 3.4  | -6.9 | -0.0 |
| WL4        | 0.7  | -1.4 | -0.0 | 3.7  | -4.2 | -0.0 |
| LWL1       | 0.4  | -5.9 | -0.0 | -0.0 | -4.9 | -0.0 |
| RBUPLW     | 0.0  | -2.3 | -2.9 | -0.0 | -2.3 | -2.9 |
| LWL2       | 0.0  | -4.9 | -0.0 | -0.4 | -5.9 | -0.0 |
| LWL3       | 0.2  | -3.1 | -0.0 | 0.2  | -2.2 | -0.0 |
| LWL4       | -0.2 | -2.2 | -0.0 | -0.2 | -3.1 | -0.0 |
| SBAL       | 3.2  | 10.7 | -0.0 | -3.2 | 10.7 | -0.0 |
| RS         | 2.7  | 6.0  | -0.0 | -2.7 | 10.7 | -0.0 |

## LOAD GROUP DESCRIPTION

|        |   |   |
|--------|---|---|
| DL     | : | Roof Dead Load                                    |
| COLL   | : | Roof Collateral Load                              |
| SNOW   | : | Roof Snow Load                                    |
| LL     | : | Roof Live Load                                    |
| RBDWEQ | : | Downward Acting Rod Brace Load from Long. Seismic |
| EQ     | : | Lateral Seismic Load [parallel to plane of frame] |
| RBUPEQ | : | Upward Acting Rod Brace Load from Long. Seismic   |
| WL1    | : | Wind from Left to Right with +GCpi                |
| WL2    | : | Wind from Left to Right with -GCpi                |
| WL3    | : | Wind from Right to Left with +GCpi                |
| WL4    | : | Wind from Right to Left with -GCpi                |
| LWL1   | : | Windward Corner Left with +GCpi                   |
| RBUPLW | : | Upward Acting Rod Brace Load from Long. Wind      |
| LWL2   | : | Windward Corner Right with +GCpi                  |
| LWL3   | : | Windward Corner Left with -GCpi                   |
| LWL4   | : | Windward Corner Right with -GCpi                  |
| SBAL   | : | Code Calculated Balanced Roof Snow Load           |
| RS     | : | Unbalanced Right Roof Snow Load                   |

## SUPPORT REACTIONS FOR EACH LOAD GROUP

\*LOCATION: Gridlines: 2 4

NOTES:(1) All reactions are in kips and kip-ft.

TIME:17:10:50


(2) The seismic overstrength factor (Omega) is not included in the "RBDWEQ" and "RBUPEQ" Load Group reactions.

Seismic "BASE-ONLY" combination reactions include an overstrength factor of: 2.000

(3) Primary wind load cases are not concurrent.

(4) X-bracing reactions (RBPULW and RBUPEQ) are combined with LWL and LEQ groups only.

## REACTION NOTATIONS



## LOAD GROUP REACTION TABLE GRIDLINES \* = 2 4

| COLUMN     | *-C  |      |      | *-A  |     |      |
|------------|------|------|------|------|-----|------|
| LOAD GROUP | H    | V    | L    | H    | V   | L    |
| LS         | 2.7  | 10.7 | -0.0 | -2.7 | 6.0 | -0.0 |
| RBDWLW     | -0.0 | 2.3  | -0.0 | 0.0  | 2.3 | -0.0 |

## LOAD GROUP DESCRIPTION

LS : Unbalanced Left Roof Snow Load

RBDWLW : Downward Acting Rod Brace Load from Long. Wind


## SUPPORT REACTIONS FOR EACH LOAD GROUP

\*LOCATION: Gridlines: 3

NOTES:(1) All reactions are in kips and kip-ft.  
 (2) The seismic overstrength factor (Omega) is not included in the "RBDWEQ" and "RBUPEQ" Load Group reactions.  
 Seismic "BASE-ONLY" combination reactions include an overstrength factor of: 2.000  
 (3) Primary wind load cases are not concurrent.  
 (4) X-bracing reactions (RBPULW and RBUPEQ) are combined with LWL and LEQ groups only.

TIME:17:10:59

## REACTION NOTATIONS



## LOAD GROUP REACTION TABLE GRIDLINES \* =

3

| COLUMN | *-C  |      |      | *-A  |      |      |
|--------|------|------|------|------|------|------|
|        | H    | V    | L    | H    | V    | L    |
| DL     | 0.4  | 1.4  | -0.0 | -0.4 | 1.4  | -0.0 |
| COLL   | 0.1  | 0.4  | -0.0 | -0.1 | 0.4  | -0.0 |
| SNOW   | 3.6  | 12.0 | -0.0 | -3.6 | 12.0 | -0.0 |
| LL     | 1.4  | 4.8  | -0.0 | -1.4 | 4.8  | -0.0 |
| RBDWEQ | -0.0 | 2.5  | -0.0 | 0.0  | 2.5  | -0.0 |
| EQ     | -0.7 | -0.6 | -0.0 | -0.7 | 0.6  | -0.0 |
| RBUPEQ | 0.0  | -2.5 | -3.1 | -0.0 | -2.5 | -3.1 |
| WL1    | -3.5 | -7.0 | -0.0 | -0.9 | -4.2 | -0.0 |
| WL2    | -3.7 | -4.2 | -0.0 | -0.7 | -1.4 | -0.0 |
| WL3    | 0.9  | -4.2 | -0.0 | 3.5  | -7.0 | -0.0 |
| WL4    | 0.7  | -1.4 | -0.0 | 3.7  | -4.2 | -0.0 |
| LWL1   | 0.5  | -5.9 | -0.0 | -0.0 | -5.0 | -0.0 |
| RBUPLW | 0.0  | -2.3 | -2.9 | -0.0 | -2.3 | -2.9 |
| LWL2   | 0.0  | -5.0 | -0.0 | -0.5 | -5.9 | -0.0 |
| LWL3   | 0.2  | -3.2 | -0.0 | 0.2  | -2.2 | -0.0 |
| LWL4   | -0.2 | -2.2 | -0.0 | -0.2 | -3.2 | -0.0 |
| SBAL   | 3.2  | 10.8 | -0.0 | -3.2 | 10.8 | -0.0 |
| RS     | 2.7  | 6.1  | -0.0 | -2.7 | 10.9 | -0.0 |

## LOAD GROUP DESCRIPTION

|        |   |   |
|--------|---|---|
| DL     | : | Roof Dead Load                                    |
| COLL   | : | Roof Collateral Load                              |
| SNOW   | : | Roof Snow Load                                    |
| LL     | : | Roof Live Load                                    |
| RBDWEQ | : | Downward Acting Rod Brace Load from Long. Seismic |
| EQ     | : | Lateral Seismic Load [parallel to plane of frame] |
| RBUPEQ | : | Upward Acting Rod Brace Load from Long. Seismic   |
| WL1    | : | Wind from Left to Right with +GCpi                |
| WL2    | : | Wind from Left to Right with -GCpi                |
| WL3    | : | Wind from Right to Left with +GCpi                |
| WL4    | : | Wind from Right to Left with -GCpi                |
| LWL1   | : | Windward Corner Left with +GCpi                   |
| RBUPLW | : | Upward Acting Rod Brace Load from Long. Wind      |
| LWL2   | : | Windward Corner Right with +GCpi                  |
| LWL3   | : | Windward Corner Left with -GCpi                   |
| LWL4   | : | Windward Corner Right with -GCpi                  |
| SBAL   | : | Code Calculated Balanced Roof Snow Load           |
| RS     | : | Unbalanced Right Roof Snow Load                   |

## SUPPORT REACTIONS FOR EACH LOAD GROUP

\*LOCATION: Gridlines: 3

NOTES:(1) All reactions are in kips and kip-ft.

(2) The seismic overstrength factor (Omega) is not included in the "RBDWEQ" and "RBUPEQ" Load Group reactions.


Seismic "BASE-ONLY" combination reactions include an overstrength factor of: 2.000

(3) Primary wind load cases are not concurrent.

(4) X-bracing reactions (RBPULW and RBUPEQ) are combined with LWL and LEQ groups only.

TIME:17:10:59

## REACTION NOTATIONS



## LOAD GROUP REACTION TABLE GRIDLINES \* = 3

| COLUMN     | *-C  |      |      | *-A  |     |      |
|------------|------|------|------|------|-----|------|
| LOAD GROUP | H    | V    | L    | H    | V   | L    |
| LS         | 2.7  | 10.9 | -0.0 | -2.7 | 6.1 | -0.0 |
| RBDWLW     | -0.0 | 2.3  | -0.0 | 0.0  | 2.3 | -0.0 |

## LOAD GROUP DESCRIPTION

LS : Unbalanced Left Roof Snow Load

RBDWLW : Downward Acting Rod Brace Load from Long. Wind


## SUPPORT REACTIONS FOR EACH LOAD GROUP

\*LOCATION: Gridlines: 5

NOTES:(1) All reactions are in kips and kip-ft.  
(2) Primary wind load cases are not concurrent.  
(3) X-bracing reactions (RBPULW and RBUPEQ) are combined with LWL and LEQ groups only.

TIME:17:10:54

## REACTION NOTATIONS



## LOAD GROUP REACTION TABLE GRIDLINES \* =

5

| COLUMN | *-C  |      |      | *-A  |      |      | *-B  |      |      |
|--------|------|------|------|------|------|------|------|------|------|
|        | H    | V    | L    | H    | V    | L    | H    | V    | L    |
| DL     | 0.0  | 0.5  | -0.0 | -0.0 | 0.5  | -0.0 | 0.0  | 1.0  | -0.0 |
| COLL   | 0.0  | 0.1  | -0.0 | -0.0 | 0.1  | -0.0 | 0.0  | 0.2  | -0.0 |
| PLL1   | 0.1  | 2.0  | -0.0 | -0.1 | -0.2 | -0.0 | 0.0  | 2.3  | -0.0 |
| PLL2   | 0.1  | -0.2 | -0.0 | -0.1 | 2.0  | -0.0 | -0.0 | 2.3  | -0.0 |
| SNOW   | 0.2  | 2.7  | -0.0 | -0.2 | 2.7  | -0.0 | 0.0  | 6.9  | -0.0 |
| LL     | 0.2  | 1.8  | -0.0 | -0.2 | 1.8  | -0.0 | 0.0  | 4.6  | -0.0 |
| EQ     | -0.4 | -0.3 | -0.0 | -0.4 | 0.3  | -0.0 | 0.2  | 0.0  | -0.4 |
| WL1    | -1.7 | -3.0 | -0.0 | -1.6 | -0.7 | -0.0 | 0.0  | -4.3 | -0.0 |
| WL2    | -2.1 | -2.1 | -0.0 | -1.2 | 0.2  | -0.0 | 0.0  | -3.1 | -0.0 |
| LWL1   | 0.9  | -2.5 | -0.0 | -0.5 | -1.7 | -0.0 | -0.0 | -3.5 | -3.1 |
| LWL2   | 0.5  | -1.7 | -0.0 | -0.9 | -2.5 | -0.0 | -0.0 | -3.5 | -3.1 |
| LWL3   | 0.5  | -1.7 | -0.0 | -0.1 | -0.9 | -0.0 | 0.0  | -2.3 | 3.1  |
| LWL4   | 0.1  | -0.9 | -0.0 | -0.5 | -1.7 | -0.0 | 0.0  | -2.3 | 3.1  |
| WL3    | 1.6  | -0.7 | -0.0 | 1.7  | -3.0 | -0.0 | -0.0 | -4.3 | -0.0 |
| WL4    | 1.2  | 0.2  | -0.0 | 2.1  | -2.1 | -0.0 | -0.0 | -3.1 | -0.0 |
| SBAL   | 0.2  | 2.4  | -0.0 | -0.2 | 2.4  | -0.0 | 0.0  | 6.3  | -0.0 |
| RS     | 0.2  | 0.4  | -0.0 | -0.2 | 2.9  | -0.0 | -0.0 | 5.3  | -0.0 |
| LS     | 0.2  | 2.9  | -0.0 | -0.2 | 0.4  | -0.0 | 0.0  | 5.3  | -0.0 |

## LOAD GROUP DESCRIPTION

|      |   |   |
|------|---|---|
| DL   | : | Roof Dead Load                                    |
| COLL | : | Roof Collateral Load                              |
| PLL1 | : | Pattern Live Load [PLLxx]                         |
| PLL2 | : | Pattern Live Load [PLLxx]                         |
| SNOW | : | Roof Snow Load                                    |
| LL   | : | Roof Live Load                                    |
| EQ   | : | Lateral Seismic Load [parallel to plane of frame] |
| WL1  | : | Wind from Left to Right with +GCpi                |
| WL2  | : | Wind from Left to Right with -GCpi                |
| LWL1 | : | Windward Corner Left with +GCpi                   |
| LWL2 | : | Windward Corner Right with +GCpi                  |
| LWL3 | : | Windward Corner Left with -GCpi                   |
| LWL4 | : | Windward Corner Right with -GCpi                  |
| WL3  | : | Wind from Right to Left with +GCpi                |
| WL4  | : | Wind from Right to Left with -GCpi                |
| SBAL | : | Code Calculated Balanced Roof Snow Load           |
| RS   | : | Unbalanced Right Roof Snow Load                   |
| LS   | : | Unbalanced Left Roof Snow Load                    |

## ADDITIONAL NOTES:

( 1 ) Pattern live or snow load cases are not concurrent with any other live or snow load cases.



**Galvalume Roof**

**White Trim**

**Desert Sand Sides**

**Pre-colored metal siding and roof.**

|   |                         |
|---|-------------------------|
| <b>BLDG-C</b>   |                         |
| <b>SHEET</b>  | <b>0</b>                |
| REV. 0 DATE 12/23/2025  |                         |
| DESCRIPTION 0 MM/DD/YY DESCRIPTION                                      |                         |
| PROFESSIONAL ENGINEER   |                         |
| DANIEL SHIPP GILLES   |                         |
| NO. 4039584-2002  |                         |
| EXP. 12/31/2025   |                         |
| STATE OF CIVIL UTAH   |                         |
|   |                         |
| <b>DESIGNED</b>   | <b>DBR</b>              |
| <b>DRAWN</b>  | <b>DBR</b>              |
| <b>CHECKED</b>  | <b>DSG</b>              |
| <b>DRAWING SCALE</b>  |                         |
| <b>H:</b>   | <b>T" = 20' (22x34)</b> |
| <b>V:</b>   | <b>T" = 40' (11x17)</b> |
| This drawing measures one inch equals one inch on the original drawing. |                         |
| <b>EL MONTE CART SHED</b>   |                         |
| 1300 VALLEY DR  |                         |
| PLOT DATE: 12/24/2025 8:40 AM   |                         |
| DRAWING NAME: Foundation Detail.dwg                                     |                         |
|   |                         |
| 2549 Washington Blvd, Suite 760 Ogden, UT 84401                         |                         |
| Phone: 801-629-8980 engineering.ogdencity.com                           |                         |